



ZONING BYLAW

NO. 2500, 2007

Appendix "A"

TABLE OF CONTENTS

DIVISION 1	TITLE	6
DIVISION 2	ADMINISTRATION	6
Part 1	Application.....	6
Part 2	Enforcement.....	6
Part 3	Prohibition.....	6
Part 4	Violation	6
Part 5	Penalty.....	6
Part 6	Appeal	7
Part 7	Severability	7
DIVISION 3	INTERPRETATION	8
Part 1	Definitions.....	8
DIVISION 4	BASIC PROVISIONS	20
Part 1	Conformity.....	20
Part 2	Non-conforming uses.....	20
Part 3	Licences, Permits and Compliance with Other Bylaws.....	20
Part 4	Additional Requirements	20
DIVISION 5	AMENDMENT	21
DIVISION 6	GENERAL REGULATIONS	22
Part 1	Number and Location of Principal Buildings on a Lot.....	22
Part 2	Accessory Buildings and Structures	22
Part 3	Home Occupation	22
Part 4	Garage Sales.....	24
Part 5	Siting of Development Adjacent to or on Watercourses	24
Part 6	Siting Exceptions	24
Part 7	Sight Triangle.....	25
Part 8	Fences	25
Part 9	Use of Mobile Homes and Trailers	26
Part 10	Prefabricated, Modular or Factory Made Dwelling Units	26
Part 11	Parking and Storage of Commercial or Derelict Vehicles or Refuse	26
Part 12	Signs.....	26
Part 13	Subdivision for Relative	26
Part 14	Landscaping Requirements.....	27
Part 15	Bed and Breakfast Accommodation	27
Part 16	Lot Size and Lot Frontage Exceptions.....	27
Part 17	Prohibited Uses in All Zones	28
Part 18	Urban Agriculture.....	28
DIVISION 7	OFF-STREET PARKING AND LOADING SPACES	32
Part 1	Off-Street Parking space Requirements.....	32

Part 2	Off-Street Loading Space Requirements	36
Part 3	Bicycle Parking Requirements	36
Schedule 7A	– Required Number of Off-Street Parking spaces.....	39
Schedule 7B	– Parking Stall and Aisle Dimensions	42
Schedule 7C	– Parking Covenant	43
Schedule 7D	– Designation for Parking Stalls for People with a Disability	45
Schedule 7E	– Downtown Amenities Incentive Area	47
Schedule 7F	– Downtown Amenities Incentive Area.....	48
DIVISION 8	CLASSIFICATION OF ZONES	49
Introduction.....		49
Part 1 - Residential Small Scale Multi Unit Housing (R-SSMUH).....		54
Part 2 - Residential One A Zone (R-1A).....		55
Part 3 - Residential Three Zone (R-3)		57
Part 3 - Residential Three A Zone (R-3A)		60
Part 3 - Residential Three B Zone (R-3B).....		62
Part 4 - Residential Four Zone (R-4)		64
Part 4 - Residential Four A Zone (R-4A).....		66
Part 4 - Residential Four B Zone (R-4B)		69
Part 5 - Residential Five Zone (R-5).....		72
Part 6 - Mobile Home Residential Subdivision Zone (MH-1).....		74
Part 7 - Mobile Home Park Residential Zone (MH-2)		76
Part 8 - Multiple Use One Zone (MU-1)		83
Part 9 - Multiple Use Two Zone (MU-2).....		85
Part 10 - Multiple Use Three Zone (MU-3).....		88
Part 11 - Multiple Use Four Zone (MU-4)		91
Part 12 - Multiple Use Five Zone (MU-5).....		94
Part 13 - Commercial One Zone (C-1)		97
Part 13 - Commercial One A (C-1A)		100
Part 14 - Commercial Two Zone (C-2).....		102
Part 14 - Commercial Two A Zone (C-2A)		107
Part 15 - Commercial Three Zone (C-3).....		110
Part 16 - Commercial Four Zone (C-4)		112
Part 17 - Commercial Five Zone (C-5).....		114
Part 18 - Industrial One Zone (I-1)		116
Part 19 - Industrial Two Zone (I-2)		118
Part 20 - Industrial Three Zone (I-3)		121
Part 21 - Public Use and Assembly One Zone (PA-1)		123
Part 22 - Public Use and Assembly Two Zone (PA-2).....		125
Part 23 - Public Use and Assembly Three Zone (PA-3).....		127
Part 24 - Public Use and Assembly Four Zone (PA-4).....		129
Part 25 - Agricultural One Zone (A-1)		131
Part 26 - Agricultural Two Zone (A-2).....		133

Part 27 - Comprehensive Development One Zone (CD-1).....	135
Part 28 - Comprehensive Development Zone Three Zone (CD-3).....	143
Part 29 - Comprehensive Development Zone Four Zone (CD-4)	145
Part 30 - Comprehensive Development Zone Six Zone (CD-6).....	147
Part 31 - Comprehensive Development Zone Seven Zone (CD-7)	149
Part 32 - Comprehensive Development Eight Zone (CD-8).....	153
Part 33 - Comprehensive Development Nine Zone (CD-9)	156
Part 34 - Comprehensive Development Ten Zone (CD-10).....	158
Part 35 - Comprehensive Development Eleven Zone (CD-11)	160
Part 36 - Comprehensive Development Twelve Zone (CD-12)	162
Part 37 - Comprehensive Development Fourteen Zone (CD-14).....	164
Part 38 - Comprehensive Development Fifteen Zone (CD-15).....	166
Part 39 - Comprehensive Development Sixteen Zone (CD-16)	169
Part 40 - Comprehensive Development Seventeen Zone (CD-17).....	171
Part 41 - Comprehensive Development Nineteen Zone (CD-19).....	173
Part 42 - Comprehensive Development Twenty-One Zone (CD- 21)	176
Part 43 - Comprehensive Development Twenty-Two Zone (CD-22)	179
Part 44 - Comprehensive Development Twenty-Three Zone (CD- 23)	181
Part 45 - Comprehensive Development Twenty-Four Zone (CD- 24)	184
Part 46 - Comprehensive Development Twenty-Five Zone (CD- 25).....	187
Part 47 - Comprehensive Development Twenty-Six Zone (CD-26)	189
Part 48 - Comprehensive Development Twenty-Six Zone Amendment (CD-26A).....	198
Part 49 - Comprehensive Development Twenty-Seven Zone (CD-27).....	204
Part 50 - Comprehensive Development Twenty-Eight Zone (CD-28).....	209
Part 51 - Comprehensive Development Twenty-Nine Zone (CD-29).....	215
Part 52 - Comprehensive Development Thirty Zone (CD-30)	218
Part 53 - Comprehensive Development Thirty-One Zone (CD-31).....	223
Part 54 - Comprehensive Development Thirty-Two Zone (CD-32)	229
Part 55 - Comprehensive Development Thirty-Four Zone (CD-34)	238
Part 56 - Comprehensive Development Thirty-Five Zone (CD-35).....	243
Part 57 - Comprehensive Development Thirty-Six Zone (CD-36)	253
Part 58 - Comprehensive Development Thirty-Eight Zone (CD-38)	259

DIVISION 9 TEMPORARY USE PERMIT 259

DIVISION 10 DEVELOPMENT PERMIT AREAS 263

DIVISION 11 ADOPTION 264

Part 1 Repeal of Previous Bylaws	264
Part 2 Effective Date of Bylaw.....	264

MAPS

Schedule 8 – Zoning Map.....	after 264
------------------------------	-----------

THE CORPORATION OF THE CITY OF COURTENAY

BYLAW NO. 2500

A Bylaw to establish zones and regulate the use of land, buildings
and structures within the zones.

WHEREAS Division (7) of Part 26 of the Local Government Act Chapter 323 provides that the *Council* of the Corporation of the *City* of Courtenay may by bylaw, divide the whole or a portion of the area of the *municipality* into zones and define each zone;

AND WHEREAS said division further provides that the *Council* of the Corporation of the *City* of Courtenay may by bylaw, regulate within the zones, the use of land, buildings and structures; regulate the density of the use of land, buildings and structures; and the area, shape and dimensions of all parcels of land that may be created by *subdivision* under the Land Title Act or the Condominium Act;

AND WHEREAS the *Council* of the Corporation of the *City* of Courtenay deem it necessary and expedient to reconsider the zoning regulations in the *City* of Courtenay;

AND WHEREAS the "Official Community Plan Bylaw No. 2387, 2005" has been adopted;

AND WHEREAS there is a need for land use regulation within the *City* of Courtenay reflecting the intent of the Official Community Plan;

AND WHEREAS there is a need to consolidate the existing zoning bylaws within the *City* of Courtenay;

NOW THEREFORE the *Council* of the Corporation of the *City* of Courtenay in open meeting assembled, enacts as follows:

DIVISION 1 TITLE

- 1.1 This Bylaw may be cited for all purposes as "Zoning Bylaw No. 2500, 2007".

DIVISION 2 ADMINISTRATION

Part 1 Application

- 2.1.1 This Bylaw shall be applicable to all land, buildings and structures therein of the Corporation of the *City* of Courtenay.
- 2.1.2 For the purpose of this Bylaw the schedules referred to herein are attached hereto and form an integral part of this Bylaw.

Part 2 Enforcement

- 2.2.1 The Administrator, or his appointed designate, shall determine whether the regulations under this Bylaw are being observed and is hereby authorized to enter any *building* or on property for the purpose of enforcing this Bylaw.
- 2.2.2 It shall be unlawful for any person to prevent or obstruct any official from the carrying out his duties under this Bylaw.

Part 3 Prohibition

- 2.3.1 It shall be unlawful for any person to cause, suffer, or permit any *building* or *structure* to be constructed, reconstructed, altered, moved, extended or used, or land to be occupied or used, in contravention of this Bylaw or otherwise to contravene or fail to comply with this Bylaw.

Part 4 Violation

- 2.4.1 Any person who violates any of the provisions of this Bylaw, or who suffers or permits any act or thing to be done in contravention of this Bylaw, or who neglects to do or refrains from doing any act or thing which is required to be done by any of the provisions of this Bylaw, shall be deemed to have violated the provisions of this Bylaw.

Part 5 Penalty

- 2.5.1 Any person who violates the provisions of this Bylaw is liable on summary conviction to a penalty not exceeding Two Thousand (\$2,000.00) Dollars or imprisonment for a period not exceeding thirty (30) days.
- 2.5.2 Each day during which such violation is continued shall be deemed to constitute a new and separate offence.

Part 6 Appeal

2.6.1 The Board of Variance established under the Board of Variance Bylaw of the *City* of Courtenay shall hear and determine any appeal pursuant to the Local Government Act.

Part 7 Severability

2.7.1 If any provision of this Bylaw is found invalid by any court of competent jurisdiction, such decision shall not affect the validity of the remaining portions of this Bylaw.

DIVISION 3 INTERPRETATION

Part 1 Definitions

In this Bylaw, unless the context otherwise requires:

"**accessory**" means ancillary and subordinate to a permitted *principal use* or *building* on the same lot.

3135 "**accessory dwelling unit**" means a self-contained dwelling unit, located on the same parcel of land as another dwelling unit that is separate, subordinate in size and accessory to the primary residence, and does not include a mobile home, recreational vehicle, or a storage container.

"**agriculture**" means growing, rearing, producing or harvesting agricultural crops or livestock and includes processing on a *parcel* the primary agricultural products harvested, reared or produced on that *parcel* and the storage of farm machinery, implements and agricultural supplies, but excludes *intensive agriculture* and the wholesale distribution of farm products.

"**agricultural business**" means a business in which one or more agricultural operations are conducted, and includes a wildlife interpretive centre, farm education or farm research institution to the extent that the institution conducts one or more farm operations.

"**aisle space**" means the area of a *parcel* which provides space for motor vehicle access and does not include required space for motor vehicle parking.

"**alteration**" means a structural change to a *building* and also includes:

- (a) an addition to gross *floor area* or *height*;
- (b) the removal of a portion of the *building*;
- (c) construction of, cutting into, or removal of any wall, partition, column, beam, joist, floor or chimney; and
- (d) any change to or closing of any required means of access.

"**assembly hall**" means the use of a *building* or *structure* for the assembly, gathering, or meeting of persons for religious, charitable, philanthropic, cultural, educational or any other purpose not otherwise specifically defined in the Bylaw.

"**auction centre**" means the offering for sale of new and used goods by means of a request or invitation for bids but it does not include *retail* sales nor the sale of poultry or livestock nor any outdoor storage or sales of goods, equipment or materials.

"**bingo facility**" means any place that is used for both paper and electronic bingo and *accessory* food sales pursuant to a license issued by or under the authority of the provincial government and includes sale of provincial government lottery products but does not include gaming tables, slot machines, video lottery terminals or off-track betting.

"**boarding**" means the provision of sleeping accommodation in a *dwelling unit*, with or without meals, for the payment of rent.

"**building**" means a *structure* used or intended for supporting or sheltering any use or occupancy and includes a *retaining wall* 1.2 m in *height* or over.

“building area” means the greatest horizontal area of a *building* above grade within the outside surface of exterior walls or within the outside surface of exterior walls and the centre line of firewalls.

"building, accessory" means a *building*, the use of which is ancillary to that of the *principal building* on the same *lot*.

"building agricultural" means a *building*, the use of which is primarily for the growing, rearing, storage processing or sale of agricultural products on properties where the land is classified as farm pursuant to the Assessment Act.

“building supply store” means the use of land, buildings and/or structures for the purpose of *retail* sales of materials used in construction.

"campground" means premises occupied and maintained for temporary accommodation of travellers in trailers, tents, or recreation vehicles. It does not include a *mobile home park*, *motel* or *hotel*.

2935 **"cannabis”** has the same meaning as in the Cannabis Act (Canada), subject to any prescribed modifications

2803 **"care facility"** means a use or facility in which food, lodging and care or supervision is provided, with or without charge, to persons unrelated to the operator of the facility, who on account of age, infirmity, physical or mental disability, require special care.

"City" means either

- (a) the Corporation of the *City* of Courtenay, in its corporate capacity, or
- (b) the lands comprised within the municipal boundaries of the Corporation of the *City* of Courtenay as the context shall require.

3074 **“class I bicycle parking space”** means a bicycle parking space provided within a bike rack and is intended to be for visitor or temporary bike parking.

3074 **“class II bicycle parking space”** means a bicycle parking space provided within a controlled access secure space such as a bicycle room, or a bicycle locker and is intended to be for longer term permanent bicycle parking.

2618 **“cluster housing”** means a cluster of residential buildings and accessory uses comprised of not less than three dwelling units. Cluster housing may contain a mix of single residential dwellings, duplex dwellings, townhouses, and apartments.

"community service" means a use that may:

- (a) provide adult *day care*;
- (b) provide referral, counselling or physical or mental health services;
- (c) provide drop-in or activity space.

2563 **“container”** means a non-combustible unit designed to be used for the shipping, transporting or storage of goods and includes cargo containers, but specifically excludes dumpsters and recycling containers intended for neighbourhood collection.

“corner lot” means a *lot* at the intersection or junction of two or more streets which has both a front *lot line* and exterior side *lot line*.

"Council" means the *Council* of the Corporation of the *City* of Courtenay.

2803 **“Cultural Facility”** means a museum, art gallery, library or theatre for the performing arts.

"day care" means a facility providing group *day care*, family *day care*, nursing school, child minding, out of school care, or specialized *day care* in accordance with the provisions of the *Community Care facility Act*.

“dry cleaning” means a *building* used for the purpose of receiving articles or goods of fabric or leather to be subjected to the process of *dry cleaning*, dry dyeing, or cleaning, processing or repairing and for the distribution of such articles and goods which have been subject to any such processes.

2618 **“dwelling apartment”** means a building divided into not less than three dwelling units other than a townhouse and specifically excludes a building used for a hotel or motel.

3135 **"dwelling, duplex"** means a building consisting of two dwelling units structurally adjoined back-to-front, side-by-side, or one above the other, and for certainty does not include a building that only contains a principal *dwelling unit* that contains a *secondary suite*.

2618 **“dwelling, multi-residential”** means an apartment dwelling, cluster housing, townhouse dwelling.

"dwelling, single residential" means a detached *building* containing one *dwelling unit*, occupied or intended to be occupied as a single *residence*.

3135 **"dwelling, townhouse"** means a *building* consisting of three or more dwelling units, where each unit has at least two separate direct accesses to the outside.

"dwelling unit" means one or more inter-connected room designed, occupied or intended for occupancy by a single household and containing living, sleeping and sanitary facilities and not more than one set of kitchen facilities and for the purposes of this definition electrical wiring and plumbing installations designed or intended to be connected to cooking or dishwashing equipment constitute “kitchen facilities” whether or not they are so connected.

"facility for adults with a disability" means a facility that is operated by a non-profit society or private contractor either licensed or under permit from the Provincial Government and funded by the Ministry of Social Services and Housing, whose purpose is limited to the provision of *day care* program for counselling, teaching and job training services for adults with disabilities.

"fairground" means the use of land, buildings and structures for community events including rodeos, equestrian and related events, exhibitions, and outdoor markets. The gathering of stalls, booths or amusements for entertainment is permitted and may include the sale of goods displayed in such stalls, booths or outdoor display areas.

2948 **“family development centre”** means a facility that includes preschool, education, skills training, literacy courses, employment readiness, career counselling, job search, resume writing, job placement, curriculum upgrades, youth and elder programming, health and wellness programs complex learning behavioural programs, legal aid, poverty law advocacy, family law advocacy, general advocacy, food bank, public legal education and services, social services and associated ancillary uses.

2803 **“Farmers Market”** means the temporary use of buildings, structures or land for the purpose of selling agricultural products, crafts and liquor and ancillary food concessions and entertainment.

“fence” means any *structure* erected as an enclosure, barrier or boundary and, without limiting the generality hereof, includes trellises, walls and like structures.

“financial institution” means a bank, credit union, acceptance corporation, trust company, finance company or similar establishments but does not include a *building* or premises containing a single bank machine.

“fitness facility” means the use of land, buildings or structures for gymnasium, indoor or outdoor racquet courts, curling rinks, skating rinks, swimming pools, dance studios, aerobic studios or weight room and specifically excludes *games room* and entertainment facilities.

“floor area” means the space on any *storey* of a *building* between exterior walls and required firewalls, including the space occupied by interior walls and partitions, but not including exits and vertical service spaces that pierce the *storey*, and the area of an enclosed attached *garage* to a maximum size of twenty (20) square metre, per *dwelling unit*.

“floor area ratio” means the figure obtained when the gross *floor area* of all the floors of the buildings on a *lot* is divided by the area of the *lot* excluding *underground parking* or basement area containing heating, laundry or storage facilities, and unenclosed decks, as illustrated in Figure 1.




Figure 1: Floor Area Ratio

3066 **“food bank”** means the storage and unremunerated distribution of food, clothing and personal care and similar items, as well as ancillary office and donations drop off activities.

“funeral home” means an establishment with facilities for the preparation of the dead for burial or cremation, for the viewing of bodies, and for funerals.

“games room” means any room, *building*, store, or other place open to the public and containing two or more amusement machines.

“garage” means any *building* used or intended or designed for use as a place for the keeping of motor vehicles.

“garden store” means the use of land, buildings, and/or structures for the purpose of *retail* sales of trees, plants, flowers, and associated gardening or *landscaping* supplies and outdoor garden equipment.

“general service” means a business which provides services, other than *personal service* to the individual or to other businesses but excludes automotive service uses and industrial equipment rental.

“golf course” means the playing area and other open space of a *golf course* but excludes any *building* except as expressly permitted;

2551

“granny flat” means an accessory dwelling unit located in an accessory building accessory to a single residential use on a lot which is a single real estate entity.

“grocery store” means a *building* used for the sale primarily of food products, and which specifically excludes the use of specialty products as a *principal use*.

“height of building” means the vertical distance from the curb level to the highest point of the roof surface if a flat roof; the deck line of a mansard roof; and to the mean *height* level between the eaves and ridge of a gable, hip, or gambrel roof. When a *building* is situated on ground above the curb level, such *height* shall be measured from the average elevation of the natural grade of the *lot* along the front of the *building*, as illustrated in Figure 2.

“home occupation” means a non-employable type of occupation clearly incidental to the use of a *dwelling unit* for residential purposes, carried on in a home by the residential tenants of such home, and the occupation is limited to the provisions of Section 6.3.1 of this Bylaw.

“hotel” means a *building* or group of buildings intended to be occupied primarily by the traveling public which provides three or more separate sleeping units with separate entrances to a common hallway.




Figure 2: Height of Building

2512

“household” means an individual; two or more persons related by blood, marriage, adoption or foster parenthood; or not more than (5) unrelated persons.

3135

“impermeable surface” means a surface which either prevents or impedes the entry of water into the soil mantle as under natural conditions prior to development, and/or a hard surface area which causes water to run off the surface in greater quantities or at an increased rate of flow from the flow present under natural conditions prior to development.

“indoor entertainment facility” means an enclosed facility whose *principal use* is family entertainment, including pool halls, bowling alleys and the like, but excluding bingo facilities.

“intensive agriculture” means the use of land, buildings and structures by a commercial operation for:

- (a) the confinement of poultry, livestock or fur bearing animals or
- (b) the growing of mushroom

“junk yard” means a place where old articles, waste, or discarded material are stored or kept, whether or not for commercial purposes or as part of a trade or calling, and such materials shall include rubber tires, metal, plastics, plastic containers, glass, papers, sacks, wire, ropes, rags, machinery, cans or any other scrap or salvage.

“laundromat” means a *building* providing washing, drying, or dry-cleaning machines for rental use to the general public.

“landscaping” means any combination of trees, bushes, plants, flowers, lawns, bark mulch, decorative boulders and gravel, decorative paving, planters, foundations, sculptures, fences, and the like arranged and maintained so as to enhance the appearance of a property, or where necessary, to effectively screen a *lot*, site or *storage yard*. *Landscaping* does not include parking areas, sidewalks, and uncleared undergrowth or weed growth.

“licensed premises” means an establishment serving liquor for consumption on the premises.

“liquor store” means the business through which a person may *retail* to the general public liquor and liquor products.

“lot” means an area of land designated as a separate and distinct *parcel* on a legally recorded *subdivision* plan or description filed in the Land Registry *Office*;

“lot area” means the total horizontal area within the *lot lines* of a *lot* and includes both land and water surfaces, but excludes any dedicated rights-of-way;

“lot coverage” means the total horizontal area measured to the outside of the exterior walls of the buildings on a *lot*, expressed as a percentage of the *lot area*;

“lot line” means the legally defined line or lines bounding any *parcel*:

- (a) exterior side *lot line* means a *lot line* or lines adjoining a public *street*;
- (b) front *lot line* means a *lot line* common to the *lot* and abutting highway excluding a lane, or where there is more than one such line, the shortest such line shall be considered as the front *lot line* and where it cannot be defined, then it will be

determined by the City; for a *panhandle lot*, the line separating the body of the *lot* from a *panhandle* shall be considered the front *lot line*.

- (c) interior side *lot line* means a *lot line* not being a rear *lot line* and common to more than one *parcel*.
- (d) rear *lot line* means the *lot line* opposite to and most distant from the front *lot line* or, where a rear portion of the *parcel* is bounded by intersecting side *lot lines*, it shall be the point of such intersection.

“manufacturing” means those operations which are a necessary part of and clearly related to the production of articles and goods, including the repairing of articles and *retail* and wholesale sales provided the merchandise being sold is distributed from the *lot*.

“medical clinic” is a facility or part thereof where doctors provide professional medical or dental services within a shared *floor area* with a common reception area and support facilities and specially excludes a *veterinary clinic*.

2935

“Medical Marihuana Production Facility” means a building or part thereof used by a licensed producer, as defined in the Access to Cannabis for Medical Purposes Regulations (ACMPR) under the Controlled Drugs and Substances Act, and any subsequent regulations or Acts, to produce marihuana for medical use, including cultivation, drying, testing and research laboratory, storage, destroying, packaging and shipping and includes the sale of marihuana only to customers who are not present on the same premises.

“mobile home” means a *dwelling unit* designed to be moved from time to time, which arrives at the site where it is to be occupied complete and ready for occupancy except for placing on foundation supports, connection of utilities, and some incidental assembly, and meets or exceeds Canadian Standards Association Z-240 Standards but specifically excludes *recreational vehicles*.

“mobile home pad” means an area within a *mobile home* space designated, designed and prepared for the support of a *mobile home* surfaces with compacted gravel, asphalt or concrete pavement with provisions for anchorage in accordance with the *building* regulations adopted pursuant to the Local Government Act and amendments thereto.

“mobile home park” means an un-subdivided *parcel* of land, not subdivided pursuant to the Condominium Act and amendments thereto, on which are situated *mobile homes* for the purpose of providing residential accommodation.

“mobile home space” means an area of land intended for the use of one *mobile home* and situated within a *mobile home park*.

“mobile home subdivision” means a *subdivision* designed and intended for residential use where *residence* is in *mobile homes* exclusively.

“motel” means sleeping units within one or more buildings, in which the traveling public is provided, for consideration, with lodging and parking, the entrance to each of the sleeping units being from the outdoors.

“municipality” means the Corporation of the *City* of Courtenay.

“natural boundary” means the visible high water mark of any lake, river, stream or other

watercourse where the presence and action of the water are so common and usual, and so long continued in all ordinary years as to mark upon the soil of the bed of the lake, river, stream, or other body of water a character distinct from that of the banks thereof, in respect to vegetation as well in respect to the nature of the soil itself.

“nightclub” means an establishment licensed to serve liquor in conjunction with live entertainment and /or dancing as a Liquor primary establishment under the *Liquor Control and Licensing Act* and amendments thereto.

“non-conforming building or use” means any *building* or use which does not conform to all the regulations of this Bylaw or any amendments thereto, for the zoning district in which such *building* or use is located.

“nursery and greenhouse” means the use of lands principally involved in *agriculture* and horticulture, and *accessory* product sales and garden supply sales, but specifically excludes the sale of agricultural or horticultural machinery.

“office” means the occupancy or use of a *building* for the purpose of carrying out business or professional activities, but specifically excludes *retail* trade and *personal service*.

“outdoor sales” means the use of land for the *retail* sale of goods and services which require outdoor viewing and/or large space including the display, sale or rental of automobiles, heavy equipment, *recreational vehicles*, manufactured homes, watercrafts and marine products, lumber and *building* products and includes *accessory* servicing of such equipment and shall not exceed the maximum *lot coverage* of the zone.

“panhandle” means a narrow strip of land which provides access and highway frontage to a *parcel*, and which form part of that *parcel*, as illustrated in Figure 3:




Figure 3: Panhandle Lot

“parcel” see “lot”

- 2875 **“parkade”** means a multilevel building designed for the parking of motor vehicles.
- “parking lot”** means a *lot* used for parking motor vehicles.
- “parking space”** means a space for the parking of one vehicle either outside or inside a *building* or *structure*, but does not include manoeuvring aisles and other areas providing access to the space.
- 2875 **“pay parking operation”** means the use of a *building*, *structure*, *parkade*, or all or part of a *lot* or *parking lot* for the parking of motor vehicles for a fee.
- “permitted use”** means the principal permissible purpose for which land, buildings or structures may be used, and for the purpose of this Bylaw all uses not listed as permitted shall be deemed to be a prohibited use in that zone.
- “personal service”** means an establishment primarily engaged in providing services involving the care of a person or his or her personal goods or apparel.
- “pet daycare”** means the use of a building for the purposes of daytime care of domestic pets and does not include overnight care or the outdoor accommodation or storage of domestic pets.
- “principal building”** means the main *building* or *structure* on a *parcel* of land which reflects the primary use of that land.
- “principal use”** means the main purpose for which land, buildings, or structures are ordinarily used.
- “private swimming pool”** means any constructed or prefabricated pool, situated on or below ground level, used or intended to be used for swimming, bathing or wading, and having a depth of more than 0.6 m, which is situated on any privately-owned real property and is considered an *accessory structure*, and which does not fall within the jurisdiction of the Provincial Regulations governing Public Swimming Pools under the *Provincial Health Act*.
- 3025 **“produce sales stand”** means an accessory structure used for the sole purpose of displaying and selling urban agriculture products produce grown on the property where the stand is located and operated in accordance with Part 3 and Part 18 of Division 6 of this bylaw.
- “recreational vehicle”** means any vehicle, trailer, coach, house car, *structure*, or conveyance designed to travel or be transported on a highway and constructed or equipped to be used as temporary living or sleeping quarters by travellers.
- 2586 **“recycling facility”** means the buying, collection, sorting, and temporary storage of bottles, cans, newspapers and similar household goods for reuse where all handling and storage is contained within an enclosed building.
- 2990 **“rental apartment”** means, in relation to a dwelling unit in a multi-residential building, a tenancy governed by a landlord tenancy agreement that complies with the *Residential Tenancy Act*.
- “residence”** means:

- (a) occupancy or use of a *building* or part thereof as a dwelling; and
- (b) the dwelling occupied or used.

“retail” means the sale of goods to the general public.

2935 **“retail store”** means the business of selling goods or merchandise to the ultimate consumer for personal consumption or household use and not for resale purposes and includes convenience stores, video rental, household equipment rental, retail warehouses and flea markets which are wholly enclosed within a building but excludes the sale of liquor and liquor products and the sale of cannabis.

“retaining wall” means a wall of any *height*, which may consist of concrete, rock, steel or wood but specifically prohibits the use of tires or creosote treated wood.

3135 **“secondary suite”** means a *dwelling unit* which is:

- (a) accessory to the principal use being made of the lot upon which the secondary suite is located, and
- (b) located within a building of residential occupancy.

“service and repair” means the servicing, testing, repairing and installing of parts, machinery and equipment and such use shall be undertaken within an enclosed *building*.

“service station” means a use providing for the *retail* sale of motor fuels or lubricating oils; may include the servicing or repair of motor vehicles, the sale of automotive accessories and the rental of trailers and motor vehicles but excludes all other sales and services.

“setback” means the required minimum horizontal distance measured from the respective *lot line* or *natural boundary* to any *building* or *structure* or part thereof.

“shopping centre” means a commercial use, located on a *lot*, exceeding 3000m² of *floor area* and incorporating a group of commercial establishments planned, constructed or managed as an entity having common or shared parking available to customers and employees.

“site area” means the same as *lot area* where only one *lot* is involved, and means the total horizontal area within the *lot lines* of all the lots to be covered by a use. In the case of a strata title *lot*, *site area* shall mean the area of the parent *lot* prior to the creation of strata lots.

“small item sales, service, rental and repair” encompassed the repair of small item, including but not limited to computers, small appliances, bicycles, jewellery and watches, tools and small equipment, within an enclosed *building*.

“storage yard” means an area outside of an enclosed *building* where construction materials and equipment, solid fuels, lumber, new *building* materials, monuments, and stone products, public serve and utility equipment, or other materials, goods, products, vehicles, equipment or machinery are stored, baled, piled or handled, sold or distributed whether a principal or *accessory* use; but specifically excludes the use of containers.

2935 **“storefront cannabis retailer”** means a premises where cannabis is sold or otherwise provided to a person who attends at the premises.

“storey” means a habitable space between two floors or between any floor and the upper surface of the floor next above, except that the topmost *storey* shall be that portion of a

building included between the upper surface of the topmost floor and the ceiling above. A basement which contains habitable accommodation shall be considered as a *storey*.

"**street**" includes a *street*, road, lane, bridge, viaduct and any other way open to public use, but does not include a private right-of-way on private property. Notwithstanding the above, for the purposes of frontage affecting *subdivision*, a lane shall not be considered road frontage.

"**structure**" means a construction of any kind, whether fixed to, supported by, or sunk into land or water and includes swimming pools and major improvements *accessory* to the *principal use* of land, but specifically excludes *landscaping*, paving improvements, *retaining walls* under 1.0 m in *height*, and fences under 2.0 m in *height*.

"**studio**" means a place for the study of an art and includes painting, sculpting, photography, dancing, singing, acting, and the making of motion pictures and the transmission of radio and television program.

"**subdivision**" means any change in the existing size, shape, number or arrangement of a *parcel* registered in the Land Title *Office* so as to require that a new Certificate of Indefeasible Title be issued.

"**transportation depot**" means a premise used for the pick-up and discharge of fare paying, intercity and intracity bus, train and taxi passengers and may include vehicle bays and shelters and convenience retail stores.

"**underground parking**" means those areas used for parking which are within the outermost walls of a *building*, or those parking structures, the roof of which is below the average elevation of adjoining streets, lanes, or adjacent sites, but shall not include under *building* carports in *apartment* buildings.

3025 "**urban agriculture**" means the growing of fruits and vegetables, flowers, native and ornamental plants, edible berries and food perennials for beautification, education, recreation, community use, personal consumption, sales of produce grown on the lot or the donation of vegetables, fruits, edible flowers and berries only. This includes the keeping of honey bees when operating in accordance with Section 6.18.1.

3038 "**urban agriculture – raising of hens**" means the raising of hens on an residential lot when operating in accordance with Section 6.18.1.

"**useable open space**" means a level, unobstructed area or areas available for safe and convenient use by the property's occupants and shall include private space for each unit within a project, providing for recreational or leisure space normally carried outdoors. *Useable open space* shall exclude areas used for off-*street* parking, off-*street* loading, service driveways and *landscaping* along property boundary and *building* perimeter.

"**utility facility**" means the use of land, buildings or structures for the provision of community water or sewer services, park, public access, pipelines, electric and telephone service, fire hall, government *office* or cemetery.

"**veterinary clinic**" means a facility or part thereof wherein animals of all kinds are treated and kept for treatment by a registered veterinarian, and where such animals can be temporarily boarded.

"watercourse" is any natural or man-made depression with well defined banks and a bed 0.6 m or more below the surrounding land serving to give direction to a current of water at least six months of the year or having a drainage area of two (2) square kilometres or more upstream of the point of consideration, or as required by a designated official of the Ministry of Environment of the Province of British Columbia.

3135

"yard" means an open space that lies between the principal or accessory building or buildings measured from the building wall and the nearest lot line which is unoccupied and unobstructed from the ground upward including, as illustrated in Figure 4 and detailed below:




Figure 4: Required Yards

- (a) **"front yard"** means that portion of the lot extending from one side of the lot to the other at the narrowest point of the lot with road frontage. The depth of the front yard shall mean the minimum required distance from the front lot line to a line drawn parallel to it.
- (b) **"rear yard"** means that portion of the lot opposite to the front yard extending from one side of the lot to the other. The depth of the rear yard shall mean the distance from the rear lot line to a line drawn parallel to it. Where the rear portion of the lot is bounded by intersecting side lot lines, the depth of the rear yard shall mean the distance from the point of intersection to a line drawn parallel to the front lot line.
- (c) **"side yard"** means that portion of the lot extending from the front yard to the rear yard and may be an interior side yard which abuts the side lot line of an adjacent lot, or an exterior side yard which abuts a street. The width of the side yard shall mean the distance from the side lot line to the line drawn parallel to it.

DIVISION 4 BASIC PROVISIONS

Part 1 Conformity

- 4.1.1 Subject to the provisions of the Local Government Act respecting *non-conforming uses*, land or the surface of water shall not be used, buildings and structures constructed, altered, located or used, contrary to this Bylaw.
- 4.1.2 No use shall be permitted except as otherwise provided for in this Bylaw.

Part 2 Non-conforming uses

- 4.2.1 “*Non-conforming uses*” and siting shall be regulated in accordance with the provisions of Section 911 of the Local Government Act.

Part 3 Licences, Permits and Compliance with Other Bylaws

- 4.3.1 Nothing in this Bylaw shall exempt any person from complying with the requirements of *building* bylaw or any other bylaw in force within the *municipality* from obtaining any licence, permission, permit authority, or approval required by this or any other bylaw of the Corporation of the *City* of Courtenay.

Part 4 Additional Requirements

- 4.4.1 Parks, playgrounds and municipal utilities may be located in any zone.

DIVISION 5 AMENDMENT

Part 1

- 5.1.1 The procedure to amend this bylaw is included in the "*City of Courtenay Application Procedure Bylaw No. 1794, 1994*" and the application fees are listed in the "*City of Courtenay Fees and Charges Bylaw No. 1673, 1992*".

Part 2

- 5.2.1 A current list of zoning bylaws in effect, and permits, and zoning bylaws given first reading shall be kept and made available for public inspection in accordance with the Local Government Act.

DIVISION 6 GENERAL REGULATIONS

Part 1 Number and Location of Principal Buildings on a Lot

- 6.1.1 No residential use *building* shall be located on the same *lot* as any other *building*, except as otherwise provided for in this Bylaw.
- 6.1.2 No *principal building* or *structure* shall be located in any required front, side or *rear yard*.

Part 2 Accessory Buildings and Structures

- 6.2.1 Buildings and structures *accessory* to the *permitted use* of a *parcel* are permitted in each zone, unless otherwise specified, provided that:
- (i) the *principal use* is being performed on the *parcel*; or
 - (ii) a *building* for the purpose of the *principal use* has been constructed on the *parcel*; or
 - (iii) a *building* for the purpose of the *principal use* is in the process of being constructed on the *parcel*.
- 6.2.2 No *accessory building* or *accessory structure*, including swimming pools shall be located otherwise than provided for in this Bylaw.

An *accessory building* shall not be used as a dwelling except as otherwise provided in this Bylaw.

2563 6.2.3 *Building and Structure Height Exemptions*

The following types of buildings, *accessory* structures, or structural parts shall not be subject to the *building height* requirements of this bylaw:

water towers as a utility use provided that no such structure shall cover more than 20 percent of the lot;

church spires, fire and hose towers, transmission towers, rooftop cooling towers, and ham radio towers provided that no such *structure* shall exceed 1.2 times the maximum permitted height of a building in that zone, and no such structure shall cover more than 20 percent of the lot, or if located on a *building*, not more than 10 percent of the roof area of the *building* on which the structure is located.

Part 3 Home Occupation

- 3024 6.3.1 The following *home occupations*, are permitted subject to all conditions of the Bylaw:
- (i) office (general)
 - (ii) personal service
 - (iii) home crafts (hobby and related crafts)
 - (iv) music, dancing and related lessons providing that the number of pupils on the premises at any one time are five (5) or less
 - (v) small appliance repairs where appliances serviced have a maximum volume of 23m²
 - (vi) schools or kindergartens for five (5) children or less
 - (vii) day care pursuant to the *Community Care and Assisted Living Act*
 - (viii) photography
 - 3025 (ix) produce sale stand

- 6.3.2 The *home occupation* must be carried on only by a person residing in the *dwelling unit* in question, with no outside assistance.
- 6.3.3 The premises must not be used for *manufacturing*, welding or any other light industrial use, and the *home occupation* carried on therein shall not produce noise, vibration, smoke, dust, odour, litter, or heat, other than normally associated with a dwelling, nor shall it create or cause a fire hazard, glare, electrical interference or traffic congestion on the *street*.
- 6.3.4 Such *home occupation* shall not involve the use of mechanical equipment save as is similar to that ordinarily employed in purely private domestic and household use or for recreational hobbies.
- 3025 6.3.5 No part of the premises shall be used as a warehouse or *retail* outlet except in the case of a produce sales stand.
- 3024 6.3.6 No *home occupation* shall occupy more than 50m² or 50% of the dwelling unit whichever is the lesser.
- 6.3.7 The premises must give no exterior indication of the *home occupation* either by stored materials, displays, floodlighting, or otherwise, or by any variation from the residential character of the *dwelling unit*. However, a *home occupation* may have one un-illuminated fascia sign not exceeding 0.5 m² which includes the name of the *home occupation* as well as that of the license holder.
- 6.3.8 The *home occupation* must be carried on wholly within the *dwelling unit*, **except:**
- (i) That in the case of day nurseries, schools and kindergartens, the *rear yard* of the property can be used as a play area;
 - (ii) And in the case of home crafts, to a maximum *floor area* of 30 m², which may be located in an *accessory building*.
- 6.3.9 Provides for the off-*street* parking of all vehicles associated with the *residence* and business under the requirements of Division 7. The *front yard* shall not be considered as constituting the required *parking spaces* to be provided.
- 6.3.10 Materials and commodities shall not be delivered to or from the *residence* in such bulk or quantity as to require regular or frequent delivery by commercial vehicle or trailer.
- 6.3.11 Any person intending to carry on a *home occupation* shall apply for an application for a business license pursuant to the regulations of the *City* of Courtenay Business License Bylaw.
- 6.3.12 Bed and breakfast accommodation may be allowed in any residential dwelling, subject to the following requirements:
- (i) Not more than two bedrooms are used for transient accommodation.
 - (ii) Principle use of the building shall be for occupation by a single family.
 - (iii) That the family or a member of it shall be alone engaged in the operation of the transient accommodation business.
 - (iv) No meals shall be provided to the customers of the operation other than breakfast.
 - (v) No liquor shall be supplied to customers.
 - (vi) At least one automobile parking space shall be provided on the same lot for each room available for transient accommodation, in addition to the parking

requirements for the residence, but parking spaces may be behind other parking spaces on the same lot.

2779 6.3.13 *Medical Marihuana Production Facility* is prohibited as a *home occupation*.

2563 **Part 4 Garage Sales**

6.4.1 Garage Sales (including yard, moving and other similar types of sales) are permitted as an accessory use in residential zones, subject to the following requirements:

- (i) A garage sale may not occur on more than 4 days in a calendar year;
- (ii) A garage sale may occupy no more than 100m² in area;
- (iii) A garage sale may not involve the sale of new goods.

Part 5 Siting of Development Adjacent to or on Watercourses

6.5.1 Floodplain construction specifications are established in "The *City of Courtenay* Floodplain Management Bylaw No. 1743, 1994"

6.5.2 No houseboat, float camp or other *building, structure* or vessel used or intended to be used for temporary or permanent *residence* shall be located on any *watercourse*.

6.5.3 The following *setbacks* are required for any development adjacent to a *watercourse*. Where more than one *setback* is applicable, the greater distance shall be required:

- i) 30 m from the *natural boundary* of the Puntledge River, Tsolum River and Courtenay River;
- ii) 15 m from the *natural boundary* of Morrison Creek, Piercy Creek, Milliard Creek and any other *watercourse*;
- iii) 15 m from the *natural boundary* of the ocean;
- iv) 7.5 m from the *natural boundary* of a lake, marsh or pond.

Part 6 Siting Exceptions

3135 6.6.1 Where chimneys, cornices, leaders, gutters, pilasters, sills, decks, posts, landings or similar features project beyond the face of a building, the minimum distance to an abutting lot line as permitted elsewhere in the Bylaw may be reduced by not more than 0.6 m providing that such reduction shall apply only to the projecting feature and except for a zero-lot line in which case no feature shall project over the lot line.

6.6.2 Freestanding lighting poles, warning devices, utility poles, wires, and flagpoles may be sited on any portion of a *lot*.

Part 7 Sight Triangle

- 6.7.1 On any *corner lot*, except for the second and subsequent stories of a *building* in the Commercial One Zone (C-1), nothing shall be erected, placed, planted or allowed to grow in such a manner as to impede vision between a *height* of 1.0 m and 3.0 m above the centre line grade of the intersecting *street* in the area bounded by the property lines of such *corner lots* and a line joining points along said property lines 6.0 m from the point of the *street* intersection as illustrated in Figure 5.




Figure 5: Sight Triangle

Part 8 Fences

- 6.8.1 In the residential zones the maximum *height* for a *fence* in or along the *front yard* shall be 1.25 m and in or along the side or *rear yards* shall be 2.0 m.
- 6.8.2 In all zones other than residential zones the maximum *height* for a *fence* shall be 2.0 m except where provided for in other parts of this Bylaw.
- 6.8.3 Fences erected on *corner lots* are subject to Section 6.7.1 of this Bylaw.
- 6.8.4 The *height* of a *fence* or wall shall be determined by measurement from the ground level at the average grade level within 1.0 m of both sides of such *fence*, wall or hedge.
- 6.8.5 The installation of electrical, barbed or razor wire fencing is prohibited in all Residential and Multi Residential zones.
- 6.8.6 Every *private swimming pool* whether existing or proposed shall be enclosed with a sturdy, non-climbable *fence* not less than 1.5 m in *height* and no openings greater than 0.1 m in their least dimension. This *fence* may enclose the pool itself or any portion of the premises on which the pool is situated.
- 6.8.7 Where only the pool area is fenced, the fencing shall be such that the pool is open to full view through the *fence*. Such *fence* will be continuous except for points of access which shall be equipped with a self-closing gate, so designed as to cause the gate to return to a locked position when not in use, and secured by a spring located not less than 1.0 m above grade and which can only be opened from the swimming pool side of the *fence*.
- 6.8.8 Every gate in every *fence* which provides access to a *private swimming pool* shall be kept in a lock-closed position while any water remains in the swimming pool and shall only be opened for the purpose of access to or egress from the said pool during such period.

- 6.8.9 Every *fence* enclosing a *private swimming pool* shall be maintained by the owner or occupier of real property on which the same is situated, in good order and repair and adequate to perform its intended function and in addition all sagging gates, loose parts, worn latches and locks and all broken or binding members shall be promptly and adequately replaced or repaired.
- 6.8.10 The siting of *private swimming pools* shall be in accordance with the applicable zoning regulations for *accessory* structures.

Part 9 Use of Mobile Homes and Trailers

- 6.9.1 It shall be unlawful to use or occupy a *mobile home* or trailer as a *dwelling unit* or living or sleeping quarters anywhere in the *City* save and except where such *mobile home* or trailer is located within a *MH-1* or *MH-2 Zone*.

Part 10 Prefabricated, Modular or Factory Made Dwelling Units

- 6.10.1 Prefabricated, modular or factory made *dwelling units* that are certified under CSA Z-240 or A-277 are permitted: provided that such a *dwelling unit* is a minimum of 6.5 m in width, exclusive of carports, verandas, cabanas, porches, stairways, or any other extension whatsoever to the original prefabricated, modular, or factory made *dwelling unit*. Individual single-wide *dwelling units* including those certified under CSA Z-240 are not permitted, except in a *MH-1* or *MH-2 Zone*.

Part 11 Parking and Storage of Commercial or Derelict Vehicles or Refuse

- 6.11.1 Unless specifically permitted, no *parcel* shall be used for the wrecking or storage of derelict vehicles or refuse or as a *junk yard*.
- 6.11.2 Any vehicle which has not been licensed for over a period of one (1) year and which is not housed in a *garage* or carport shall be deemed to be a derelict vehicle or junk.
- 6.11.3 Only the following shall be parked or stored, on any Residential or *Mobile home* Zoned property:
- one commercial vehicle not exceeding 907 kg rate capacity;
 - trucks, commercial vehicles or equipment required for the construction, repair, servicing or maintenance of the premises;
 - recreational boats, trailers, and vehicles for the personal use of the occupants of the property.

Part 12 Signs

- 6.12.1 Signs are permitted only in accordance with and subject to the provisions of the Sign Bylaw of the *City* and amendments thereto.

Part 13 Subdivision for Relative

- 6.13.1 No *subdivision* shall be permitted pursuant to Section 946 of the Local Government Act, on lands not within Agricultural Land Reserve, unless the parent *parcel* is a minimum of 10 hectares in size. Any *parcel* created by *subdivision* under this section shall be not less than 1 hectare.

Part 14 Landscaping Requirements

- 6.14.1 A landscape plan prepared by a Landscape Architect is required to be submitted as part of a development permit application and the provisions of this bylaw will apply in addition to the applicable development permit guidelines.
- 6.14.2 Wherever possible, *landscaping* and screening areas will retain existing trees and natural vegetation and add planting that enhances the natural environment.
- 6.14.3 Any part of a *lot* not used for *building*, parking, loading facilities or outdoor recreation shall be fully and properly landscaped and maintained and separated from the paved areas by a concrete curb or other barrier to the satisfaction of the *City*.
- 6.14.4 Where a *lot* adjoins the Agricultural Land Reserve a *fence* and landscape buffer of 10 m in width shall be provided inside the property line.
- 6.14.5 *Landscaping* for each *building* and the surrounding area shall be completed within six (6) months of the date of issuance of the occupancy permit for such *building* by the *City*.

Part 15 Bed and Breakfast Accommodation

- 6.15.1 Bed and breakfast accommodation are permitted in any single residential dwelling located in any residential or multi residential zone, subject to the following requirements:
 - (a) Not more than two bedrooms are used for transient accommodation.
 - (b) Principle use of the *building* shall be *single residential*.
 - (c) That the residents of the dwelling shall be alone engaged in the operation of the transient accommodation business.
 - (d) No meals shall be provided to the customers of the operation other than breakfast.
 - (e) No liquor shall be supplied to customers.
- 6.15.2 At least one automobile parking space shall be provided on the same lot for each room available for transient accommodation, in addition to the parking requirements for the residence, but parking spaces may be behind other parking spaces on the same lot.

Part 16 Lot Size and Lot Frontage Exceptions

- 2551 6.16.1 Despite the requirements in respect of minimum lot frontage and minimum lot size set out in this Bylaw, a lot may be created if:
 - (a) the existing lot is lawfully non-complying with respect to the lot size or lot frontage or both; and
 - (b) the lot thereby created improves the existing situation and has a lot size and lot frontage greater than that of the existing non-conforming size and frontage of the existing parcel; and
 - (c) the creation of the non-conforming parcel thereby does not cause to create non-conforming siting, size, or frontage of the adjacent lots; and
 - (d) no additional lots are being created.

Part 17 Prohibited Uses in All Zones

- 2839 6.17.1 Unless specifically permitted in this Bylaw, the use of land, water, buildings or structures for the following purpose is prohibited:
- (a) *Medical Marihuana Production Facility*: with the exception of lands that are located within the Agricultural Land Reserve.
 - (b) A *Medical Marihuana Production Facility* is permitted on land located within the Agricultural Land Reserve if:
 - 2935 (i) the operation of medical marihuana is contained wholly within licensed facilities permitted by the Access to Cannabis for Medical Purposes Regulations (ACMPR).
 - (ii) The minimum setback for all structures associated with medical marihuana production is 30.0 metres from all property lines.
 - 2935 (c) Storefront cannabis retailer except as approved through rezoning.
 - 2959 (d) The bottling of water except where the source of the water is the municipal water supply, supplied directly to the property on which the bottling is taking place.

3025 Part 18 Urban Agriculture

- 6.18.1 *Urban Agriculture* is allowed as an accessory use to any single residential dwelling, subject to the following:
- (a) *Urban agriculture* activity shall not generate odour, waste, noise, smoke, glare, fire hazard, visual impact, or any other hazard or nuisance, in excess of that which is characteristic of the zone in which it is located under normal circumstances wherein no urban agriculture exists.
 - (b) A *produce sales stand* is permitted on all lots allowing *urban agriculture* for the sale of *urban agriculture* products grown on the lot subject to the following:
 - i. a *produce sales stand* is considered an accessory structure subject to the requirements of the applicable zone that:
 - i. the *produce sales stand* shall have a *floor area* of not more than 5.0m²;
 - ii. the *produce sales stand* shall not exceed a height of 2.5m;
 - iii. the *produce sales stand* must be located entirely on the lot in which the produce is grown; and,
 - iv. a *produce sales stand* may be located within the *front yard*
 - ii. a *produce stand* must only sell produce grown on the lot where it is located;
 - iii. sales are only permitted between 7am and 7pm daily;
 - iv. a *produce sales stand* must be removed seasonally when not in use; and,
 - v. there shall only be one non-illuminated sign, which shall not exceed 0.4 m² in area.
 - (c) Beekeeping is permitted on all lots allowing *urban agriculture* subject to the following:
 - i. lots have a minimum width of 15.0m;
 - ii. lots have a minimum *lot area* of 550.0m²;

- iii. hives shall be located at least 6.0m from all property lines;
- iv. hives shall be registered with the Provincial authority, BC Ministry of Agriculture and Lands;
- v. only two hives with colonies shall be permitted on each lot; and
- vi. honey production is for personal consumption only.

3038

- (d) The keeping of hens is permitted on all lots allowing *urban agriculture* subject to the following:
 - i. A hen coop is considered an *accessory structure* subject to the requirements of the applicable zone except that a coop shall only be permitted in the rear yard;
 - ii. the maximum number of hens shall be six (6) per lot;
 - iii. roosters are not permitted;
 - iv. the sale of eggs, manure and other products associated with the keeping of hens is prohibited,
 - v. coops and runs shall be maintained in a clean condition and the coop shall be kept free of obnoxious odours, substances and vermin;
 - vi. stored manure shall be kept in an enclosed structure such as a compost bin and no more than 3.0m³ shall be stored at any one time; and,
 - vii. home slaughter of hens is prohibited and any deceased hens shall be disposed of at a livestock disposal facility or through the services of a veterinarian.

3135

6.19.1. The following conditions shall apply to Secondary Suites and Accessory Dwelling Units:

- (i) Not more than one (1) Secondary Suite and one (1) Accessory Dwelling Unit shall be permitted as accessory to a dwelling on a lot where such principal uses are permitted, subject to all other regulations in this Bylaw, and as may be governed by the development regulations of a particular zone.
- (ii) No subdivision of a Secondary Suite or Accessory Dwelling Unit shall be permitted.
- (iii) The minimum floor area of a Secondary Suite or Accessory Dwelling Unit shall not be less than:
 - (a) 30 m² for a studio unit;
 - (b) 45 m² for a one-bedroom unit;
 - (c) 65 m² for a two-bedroom unit;
 - (d) 85 m² for a three-bedroom unit.
- (iv) An Accessory Dwelling Unit shall not exceed the lesser of 6.5 m in height or the height of the principal residence, unless otherwise specified in the development regulations of a particular zone. Where the width of a dormer or dormers exceeds 50% of the width of the roof on which they are located, the height of the building will be measured to the top of the dormer or to the top of the main roof, whichever is greater.
- (v) Parking shall be in conformance with the regulations of this Bylaw.

- (vi) Where a Secondary Suite or Accessory Dwelling Unit is permitted, a minimum area of 20 m² of private amenity space shall be provided per dwelling unit. The private amenity space shall have a direct connection to the habitable space and be defined and screened through the use of landscaping such as: plantings, architectural elements such as a trellis, low fences, planters or changes in elevation.
- (vii) A lighted pathway is required from the on-site Secondary Suite or Accessory Dwelling Unit parking stall(s) to the entrance door of the Secondary Suite or Accessory Dwelling Unit, provided that the lighting does not shine directly on adjoining properties or interfere with the effectiveness of any traffic control device.

DIVISION 7 OFF-STREET PARKING AND LOADING SPACES

Part 1 Off-Street Parking space Requirements

7.1.1 Location

Where the provisions of the bylaw require allowance for the *off-street parking spaces* and loading spaces, every owner of land shall, upon the *lot* in question, provide and maintain *off-street parking spaces* and loading spaces in conformance with the minimum standards set out in this Division. Where vehicular access is required on a controlled access highway listed below, the BC Ministry of Transportation and Highways access approval is also required prior to the approval by the *City*;

-Island Highway (Highway 19A from 29th Street to Ryan Road)

-Ryan Road (from Highway 19A to Anderton Road)

-South Inland Island Highway Connector (29th Street from Piercy Road to Highway 19A)

7.1.2 General Requirements

- (1) The minimum number of *off-street parking spaces* shall be provided in accordance with Schedule 7A of this Bylaw.
- (2) If a use is not listed in Schedule 7A, the number of spaces shall be calculated on the basis of a similar use that is listed as determined by the *City*.
- (3) If more than one use is located on a *parcel* or involves collective parking for more than one *building* or use, the total number of spaces shall be the sum of the various classes of uses calculated separately, and a space required for one use or a loading space shall not be included in calculations for any other use. However, parking and loading space requirements for churches/places of worship and associated assembly halls or classrooms shall be the greater of the requirements for the two uses calculated separately, provided the two are not used concurrently.
- (4) Where the calculation of total required spaces results in a fractional number, the nearest whole number above that calculation shall be taken.
- (5) *Off-street* vehicle loading space required by this Bylaw shall not be credited as required *off-street parking space*.
- (6) *Parking spaces* required in accordance with this Bylaw shall not include any *parking spaces* used or intended to be used for the storage of goods or parking of vehicles for rent or gain, display or sale.
- (7) *Parking spaces* required in accordance with this Bylaw shall be constructed and available for use at the time of issuance of an Occupancy Permit.

7.1.3 Stall and Aisle Dimensions

All *off-street parking spaces* and aisles shall be developed in accordance with Schedule 7B of this Bylaw.

2612

7.1.4 Access

All parking areas shall have access to a public thoroughfare, such access to be not less than 4.57 m not more than 9.14 m in width. The location of all points of access and egress from a public road to a parking area and all of the traffic patterns within the parking area shall be subject to the approval of the Municipal Engineer.

7.1.5 Vertical Clearance

The minimum vertical clearance of parking stalls and aisles shall be 2.25 m.

7.1.6 Specifications

- (1) Every off-*street* motor vehicle parking area required by this Bylaw to accommodate two or more vehicles shall be surfaced with a bituminous or other dust-free surface.
- (2) Every off-*street* motor vehicle parking area required by this Bylaw shall have:
 - (i) the individual *parking spaces*, manoeuvring aisles, entrances and exits clearly marked by curbs or fences, lines and signs.
 - (ii) fences and curbs to prevent the crossing of sidewalks and boulevards except at authorized exits or entrances.
- (3) All parking and loading spaces shall have a maximum gradient and cross slope of 6%.
- (4) Any lighting used to illuminate any parking area shall be so arranged that all direct rays of light fall upon the parking area and not on any adjoining premises and every off-*street* motor vehicle parking area required by this Bylaw shall adequately lighted.
- (5) No off-*street parking spaces* shall be permitted to overhang any public sidewalk. Where a sidewalk is required along a highway, the minimum distance between the off-*street* parking and the property line shall be a landscaped strip of 1.5 m.
- (6) Visitor *parking spaces* shall be clearly marked by signs or by painting markings on the pavement.
- (7) Where a *parking space* or manoeuvring aisle abuts a wall or *building*, the width of the *parking space* or manoeuvring aisle as determined by Schedule 7B shall be increased by an additional 0.6 m.
- (8) The minimum distance from the face of a *garage* or carport to a property line or private internal access road excluding a public lane must be 6.0 m.

7.1.7 Off-Site Parking

- (1) An owner of land may provide and maintain off-*street* motor vehicle *parking spaces* when required by the Bylaw off the site of the development if:
 - (i) the minimum number *parking spaces* required by this Bylaw of the particular use as set out in Schedule 7A can be provided on another site within 225.0 m of the site containing the development.
 - (ii) the owner of the site to be used for parking enters into covenant in the form of Schedule 7C attached hereto with the *City*. The covenant is registered as a first charge against the parking property in the British Columbia Land Registry *Office* in Victoria.
- (2) Within the C-1 - Central Commercial Zone an owner may, at his option in lieu of supplying an individual parking site or *structure* on the same site as the *principal*

use, or otherwise, pay to the *City* of Courtenay a sum of money per *parking space* so required. The sum of money per *parking space* shall be six thousand five hundred dollars (\$6,500.00). All such monies paid to the *City* shall be placed in a Special Reserve Fund which shall be committed to the purchase of public off-*street* parking sites and structures within or immediately adjacent to the downtown as the *City* may see fit.

7.1.8 Spaces for People with Disabilities

- (1) When any development, *building* or use requires or provides more than 20 off-*street parking spaces*, one *parking space* shall be provided for the use of persons with a physical disability, together with one additional space for a person with a disability for each additional 75 off-*street parking spaces* required or provided.
- (2) Each space for a person with a disability shall be a minimum of 4.0 m in width.
- (3) Each space for a person with a disability shall be marked with the International Symbol of Accessibility for people with a disability as specified in Schedule 7D of this Bylaw.
- (4) Each space for a person with a disability shall be located within convenient access of the development, *building* or use that it is intended to serve, and with minimum changes in level.

7.1.9 Existing Buildings and Structures

Nothing in this Bylaw shall be construed to require off-*street parking spaces* for a *building* or structures existing at the effective date of this Bylaw, so long as the *building* or *structure* continues to be put to a use that does not require more parking or loading spaces than were required for the use existing at the time the bylaw came into force. Where a change in use results in additional parking or loading spaces being required then the number of spaces to be provided will be the difference between the *parking space* requirements for the previous use and the present use.

7.1.10 Small Car Parking

- (1) Every off-*street* motor vehicle parking area required by this bylaw to accommodate twenty (20) or more vehicles, may provide up to 10% of the total number of parking stalls for small cars.
- (2) Every small car parking stall shall be a minimum of 2.5 m in width and 4.6 m in length.
- (3) Aisle dimensions shall be developed in accordance with Schedule 7B of this bylaw.
- (4) All designated small car stalls shall be clearly marked.

7.1.11 Parking Amenity (Multi Residential Dwellings)

The following provisions are applicable to multi residential dwellings as specified below for:

- Apartments 1 to 3 inclusive
- Townhouses 2 and 3

Where *parking spaces* are provided within a principle *building* an amount may be added to the *floor area ratio* (FAR) equal to .20 multiplied by the percentage of the total *parking spaces* which are provided in this manner.

Where the parking requirement is reduced from 1.5 to 1.25 spaces per unit, a landscaped area in the location and with materials satisfactory to the *municipality* in addition to all other requirements including required *yards* of this bylaw shall be provided equivalent to:

2685 $7.5\text{m}^2 \times \text{the number } \textit{parking spaces} \text{ reduced} \times 2$

Where: $15\text{m}^2 = \text{area of } \textit{parking space}$

Within the area shown on Schedule 7E, attached hereto and forming part of this bylaw, parking can be reduced to 1 space per unit for all multi residential developments. Where this option is utilized the *landscaping* requirement would be provided equivalent to:

$15\text{m}^2 \times \text{the number of } \textit{parking spaces} \text{ reduced}$

Within the Commercial One Zone (C-1), 1.0 *parking space* per residential *apartment* unit.

7.1.12 Standards for the Installation and Maintenance of Signs and Lines in *Parking lots* and Access Roads

(1) Curbs – painting colours

- a) Yellow indicates no parking is allowed
- b) Red indicates no stopping at any time as the curb protects a bus stop location
- c) White indicates special parking or stopping provisions, e.g., commercial vehicle

Areas delineated by white paint should be qualified by signs. It is also recommended that yellow curbs have qualifying signage, e.g. No Parking, No Stopping, Fire Lane.

(2) Medians

The nose at each end of the median may be painted yellow. It is not necessary to paint the entire median curb. A divider sign to indicate the median and the traffic flow direction around the median is required.

(3) Dividing Island

Where the traffic flows in the same direction on each side of the island, it may have the curbs painted white.

(4) Parking Stall Lines

Should be painted with white paint in accordance with the *City's* parking requirements in the zoning bylaw.

(5) Stop Signs

If stop signs are installed in order to control traffic movements, stop bars may be provided and painted white. If the stop bars are installed on two-way roads or

parking areas then a yellow delineating line is also required leading up to the stop bar.

(6) Crosswalks

If they are installed at 90° to the traffic flow at a stop bar then the crosswalk is to be two parallel white lines.

If the crosswalk is not at a stop sign area then it is to be zebra crosswalk painted white.

(7) Speed Bumps

If installed should be painted with yellow paint. It is recommended that speed bumps are also signed to alert the public to the change in road profile.

(8) Stop or Yield Traffic Areas

If it is intended to have one or more lanes of traffic yield to another lane(s), the yield signs are to be installed.

If multi-way stops are intended then Stop signs are to be installed with the appropriate tab sign.

(9) Directional Arrows

Painted directional arrows on road surfaces should be white and of standard size.

(10) Public Access

Public access, landing and drop-off areas shall be painted with yellow diagonal lines.

7.1.13 Parking Reductions within the Walkable Areas

- (1) Properties zoned Residential Small-Scale Multi-Unit Housing (R-SSMUH) within the estimated walking distance shown on *Schedule 7F* may have the total amount of parking required on a property reduced by one space.

Part 2 Off-Street Loading Space Requirements

7.2.1 Every owner of land which is the site of a *structure* or *yard* involved in the receipt or delivery of goods or materials by vehicles shall, on the *lot* in question, provide and maintain off-*street* loading spaces which shall conform to the following minimum standards:

- (1) All off-*street* loading spaces shall be a minimum of 9.0 m in length 3.0 m in width and 4.0 m for vertical clearance.
- (2) Adequate provision shall be made for access by vehicles to all off-*street* loading spaces by means of a 6.0 m manoeuvring aisle and shall be located so that each separate use within a development has access to a space.
- (3) One off-*street* loading space shall be provided for:
 - (i) Every 1,850 m² of floor space or fraction thereof, of structures involved in the receipt or delivery of goods or materials by vehicles; and for
 - (ii) Every 1,850 m², or fraction thereof, of *yard* involved in the receipt or delivery of goods or materials by vehicle.
- (4) Off *street* loading spaces for schools and colleges shall be provided as follows:

- 1 space 500m^2 of *building floor area*
- 2 spaces: $500\text{m}^2 - 2000\text{m}^2$ of *building floor area*
- 3 spaces: $2000\text{m}^2 - 3500\text{m}^2$ of *building floor area*
- 1 additional space for every 5000m^2 or part thereof greater than 3500m^2

7.2.2 Off-street motor vehicle *parking space* required by this Bylaw shall not be credited as required off-street loading space.

7.2.3 All off-street loading spaces shall be clearly marked with the words "LOADING SPACE ONLY" on the pavement or wall facing.

Part 3 Bicycle Parking Requirements

7.3.1 Minimum Required Number of Bicycle Parking Spaces

A minimum number of off-street parking spaces shall be provided in accordance with the following table, unless otherwise stated within a specific zone:

USE	MINIMUM REQUIRED BICYCLE PARKING SPACES
1) RESIDENTIAL	
Multi-residential	<ul style="list-style-type: none"> - Class II Bicycle Parking Spaces per dwelling unit – 2 - Class I Bicycle Parking Spaces – calculated as 10% of the minimum number of Class II spaces required

7.3.2 Bicycle Parking Specifications

General:

- 1) Each standard bicycle parking space shall be a minimum of 1.8 metres (length) by 0.6 metres (width) by 2.1 metres (height).
- 2) 10% of minimum required bicycle parking spaces shall be designed for oversized bicycle parking spaces with the following minimum dimensions: 3.0 metres (length) by 0.9 metres (width) by 2.1 metres (height).
- 3) Each bicycle parking space must be independently accessible from a sturdy rack designed for frame, not wheel-only, support.
- 4) Racks shall be of a design such that the user is able to lock a bicycle frame and one wheel to the rack with a u-shaped lock.
- 5) Racks shall be securely anchored to the ground or a wall to prevent removal.
- 6) Access shall be provided from each bicycle space to a street, excluding a lane.

Specific to Class I:

- 7) Racks shall be located at ground level, within 15.0 metres of the main entrance of the principal building.

- 8) The first 12 parking spaces, and 50% of all remaining spaces, shall include overhead shelter with a vertical clearance of a minimum of 2.1 metres (height) to protect bicycles from weather.
- 9) A minimum of 20% of spaces shall have access to an electrified 110V outlet.
- 10) A minimum of 50% of oversized bicycle parking spaces shall have access to an electrified 110V outlet.
- 11) Rack locations should allow for a high degree of visual surveillance by building occupants or from streets that abut the parcel.
- 12) Racks shall be illuminated with metal halide type lighting, consisting of either full cut off/flat lens pole lighting or fully shielded all lighting.

Specific to Class II:

- 13) A minimum of 100% of spaces shall have access to an electrified 110V outlet.

14) Bicycle Rooms:

- a. Shall be completely enclosed within the principal or an accessory building; interior walls may be comprised of chain link fencing.
- b. Shall be illuminated and lighting shall be enclosed in a tamper-proof housing.
- c. No more than 20 bicycles shall be provided in each bicycle room. However, larger bicycle rooms may be used if the room is compartmentalized into smaller rooms using chain link fencing with lockable chain link doors. If a larger room is utilized, each compartment shall provide no more than 20 bicycle parking spaces.
- d. Where pedestrian aisles are provided, they shall be a minimum of 1.5m in width.
- e. The whole room shall generally be visible from the entry door.
- f. There shall be a separate security lock and key for each room and compartment. Security locks shall consist of a minimum one-inch throw dead bolt.
- g. Entry doors shall be hinged on the inside unless tamper-proof hinges are used, and shall be constructed of chain link fencing, or steel with a security window that allows permanent visibility and that is constructed of a laminate of tempered glass and polycarbonate in a steel frame.
- h. If directly accessible from the outside, access shall be located in a visible location and illuminated with metal halide type lighting.

15) Bicycle Lockers

- a. Each bicycle locker shall count as one bicycle parking space.
- b. The minimum inside dimensions of each bicycle locker shall be:
 - i. Width at the door end – 0.6 metres
 - ii. Width at opposite end – 0.22 metres
 - iii. Length – 1.8 metres (unless oversized parking space which shall be 3.0 metres)
 - iv. Height – 1.2 metres

- c. Shall be securely anchored to the ground, floor, or a wall to prevent removal.
- d. There shall be a separate security lock and key for each locker. The security lock shall consist of a minimum one-inch throw dead bolt.
- e. Bicycle lockers shall be made of materials that are solid, sturdy, opaque, and weather proof, and constructed in such a manner as to be highly resistant to bicycle theft. Bicycle lockers need not be enclosed within a building.
- f. All fasteners shall be internal, unless the locker is completely set within a building wall.
- g. Entry doors shall be constructed out of steel and hinged on the inside unless tamper-proof hinges are used.
- h. If directly accessible from the outside, access shall be located in a visible location and illuminated with metal halide type lighting.

3135 7.13.1. Parking Reductions within the Walkable Areas

(1) Properties zoned Residential Small-Scale Multi-Unit (R-SSMUH) within the estimated walking distance shown on Schedule 7F may have the total amount of parking required on a property reduced by one space.

Schedule 7A – Required Number of Off-Street Parking spaces

This schedule contains the following sections:

A. Residential B. Institutional C. Recreational D. Commercial E. Industrial

The minimum number of off-street parking spaces shall be provided in accordance with the following table:


USE	REQUIRED <i>PARKING SPACE</i>
A. RESIDENTIAL	
3135 Bed and breakfast	1 space per <i>dwelling unit</i> and 1 space for each sleeping use used for Bed and Breakfast
<i>Boarding</i>	1 per 3 residents
3074 Multi residential dwellings	1.2 per <i>dwelling unit</i> with 10% of the required spaces being provided and retained for visitor parking. Note: See 7.1.11 for Amenity Incentives for parking in Multi Residential zones
3135 <i>Accessory Dwelling Unit</i>	1 space per <i>dwelling unit</i>
<i>Care facility</i>	0.5 per unit
Single <i>dwelling unit</i> or <i>duplex</i>	2 per <i>dwelling unit</i>
3135 R-SSMUH	1 space per <i>dwelling unit</i>
B. INSTITUTIONAL	
<i>Assembly hall</i>	1 space per 10m ² <u>or</u> 1 space per 4 seats whichever is greater
Church	1 space per 4 seats
<i>Care facility</i>	1 space per 3 beds
<i>Community service</i>	1 space per 37.5m ²
<i>Day care</i>	1 space per employee
<i>Funeral home</i>	1 space per 4 seats
Hospital	1 space per 2 employees <u>plus</u> 1 space per 5 beds
Library	1 space/35m ²
<i>Medical clinic</i>	5 spaces per doctor, <i>office</i> for 2 doctors or less-3 parking spaces per doctor

Police station	1 space per 2 employees <u>plus</u> 1 space for every company vehicle located therein
Schools	1 <i>parking space</i> per employee for Elementary & Junior Secondary 1 <i>parking space</i> per employee plus 1 per ten students for Secondary School
Universities, colleges and institutes	1 space per employee <u>plus</u> 1 per 5 students
C. RECREATION	
<i>Assembly hall</i> and theatre	1 space per 10m ² or 1 space per 5 persons to capacity
<i>Indoor entertainment facility</i>	3 spaces per lane
Bingo hall	1 space per 10m ² or 1 space per 4 seats whichever is greater
<i>Campground</i>	3 spaces plus 1 space per employee
<i>Golf course</i> - 9 hole 18 hole	40 spaces 75 spaces
Golf driving range	2 spaces per tee
<i>Fitness facility</i>	1 space per 10m ² or 1 per 5 persons to capacity
Marina	1 space per 2 boat berths plus 1 space per 2 employees
D. COMMERCIAL-GENERAL	
Fast food restaurant	8 spaces plus 1 per 6 seats
Restaurant	1 space per 6 seats
<i>Financial institution</i>	1 space per 25m ²
Real estate offices	1 space per 25m ²
<i>Gasoline service station</i>	1 space per 2 employees plus 2 per service bay
<i>Hotel</i> or resort condominium	1 space per 2 units plus 1 per 2 employees plus 1 per 6 seats for <i>accessory</i> uses, otherwise, as required for other uses
Hostel	1 space for every 4 guests and 2 spaces for use of manager/staff
<i>Motel</i>	1 space per unit <u>plus</u> 1 space for each vehicle required for the operation plus 1 space per 6 seats for <i>accessory</i> uses, otherwise, as required for other uses

2935

<i>Laundromat</i>	1 space per 3 washing machines
Laundry and <i>dry cleaning</i> establishment	1 space per 2 employees
Neighbourhood pub	1 space per 6 seats
<i>Nightclub</i>	1 space per 4 seats
<i>Office</i> (single or multiple tenant)	1 space per 37.5 m ²
<i>Veterinary clinic</i>	3 spaces per veterinarian plus one space per employee
COMMERCIAL - RETAIL	
<i>Auction centres</i>	1 space per 10m ² or 1 space per 4 seats whichever is greater
Automobile, boat, machinery sales & service	1 space per 70m ² sales <i>floor area</i> plus 1 per service bay plus 1 per 2 employees
Automobile service uses (<i>service stations</i>)	1 space per 2 employees plus 2 spaces per service bay
<i>Building supply store</i>	1 space per 90m ² of warehouse area and 1 space per 2 employees and 1 space per 35m ² of <i>retail area</i> and 1 space for each company vehicle located therein
Convenience stores, <i>retail stores</i> , <i>storefront cannabis retailer</i>	1 space per 35m ² of <i>floor area</i>
<i>Grocery store</i>	1 space per 35m ²
<i>Liquor store</i>	1 space per 12m ² of <i>retail floor area</i> plus 1 space per 20m ² of warehouse area
<i>Shopping centre</i>	1 space per 22.5m ²
E. INDUSTRIAL	
Taxi stands	1 space per taxi operating from taxi <i>office</i>
<i>Transportation depot</i>	1 space per 10m ² of waiting room <u>plus</u> 1 space per 2 employees
Storage <i>building</i> , <i>yards</i> or similar uses (not covered in "Commercial")	1 space per 90m ² <u>and</u> 1 space per 2 employees <u>and</u> one space for each company vehicle located therein
All other industrial uses including <i>Utility facility</i>	1 space per 3 employees and 1 space for each company vehicle located therein

Schedule 7B – Parking Stall and Aisle Dimensions



Vehicle *parking spaces* shall measure 2.75m x 5.50m and aisle widths shall be in accordance with the standards below.

Parking Angle	Minimum Aisle Width
0°	3.0 m
30°	3.5 m
45°	4.5 m
60°	5.5 m
90	7.2 m

Schedule 7C – Parking Covenant

THIS INDENTURE made this day of 20

BETWEEN:

JOHN DOE of Courtenay in the Province of British Columbia
(hereinafter called "the Grantor")

OF THE FIRST PART

AND **THE CORPORATION OF THE CITY OF COURTENAY**
830 Cliffe Avenue
in the *City* of Courtenay
in the Province of British Columbia
(hereinafter called "the Grantee")

OF THE SECOND PART

WHEREAS John Doe is the registered owner of certain property within the *City* of Courtenay and Province of British Columbia and being more particularly known and described as:

"Legal Description"
(hereinafter called the "Business Property")

AND WHEREAS John Doe is desirous of constructing and/or using a *building* on the business property for the following purposes:

"List of Purposes"

AND WHEREAS John Doe would otherwise be required pursuant to the provisions of the Zoning Bylaw No.2500 and amendments thereto to provide "X" number of *parking spaces* to accommodate the said *building* to be constructed and/or used on the business property;

AND WHEREAS John Doe desires to provide off-site parking in lieu of providing on-site parking;

AND WHEREAS the Grantor is also the registered owner of certain lands and premises in the *City* of Courtenay and Province of British Columbia more particularly known and described as:

"Legal Description"
(hereinafter called "the parking property")

which it is intended will be used to satisfy the parking requirements of the Zoning Bylaw No. 2500 and amendments thereto as hereinbefore described;

NOW THEREFORE THIS INDENTURE WITNESSETH that in consideration of the sum of One Dollar (\$1.00) (receipt of which is hereby acknowledged by the Grantor) and in consideration of the *City* agreeing to the provision of off-site parking in lieu of on-site parking for the business property owned by John Doe as hereinbefore related, the Grantor hereby covenants and agrees with the Grantee as follows:

1. The Grantor herein hereby agrees that the parking property shall:
 - a) Be used only for the parking of motor vehicles in connection with the business carried on at the *building* situate on the business property and shall not be used for any other purpose or in any other particular manner.
 - b) Not be built upon except for such *landscaping*, paving and other improvements necessary to provide the said parking facilities.
 - c) Be used to satisfy the parking requirements according to the *City* of Courtenay Zoning Bylaw No. 2500, 2007 and amendments thereto.

THIS AGREEMENT shall pursuant to Section 219 of the *Land Titles Act*. R.S.B.C. 1996 Chapter 250 and all amendments thereto be construed as a covenant running with the land hereinbefore described in Paragraph 1 and no part of the fee of the land shall be vested in the Grantee by these presents.

THIS AGREEMENT shall be binding upon and ensure to the benefit of the parties hereto and their respective successors, executors, administrators and assigns.

IN WITNESS whereof the parties hereto have set their hands and seals on the day and year first above mentioned.

SIGNED, SEALED AND DELIVERED
in the presence of

The Corporate Seal of the Corporation of the *City* of Courtenay was hereunto affixed in the presence of:

MAYOR


MANAGER OF CORPORATE
ADMINISTRATION

Schedule 7D – Designation for Parking Stalls for People with a Disability

Minimum Size


Wall facing or sign - 0.3 m in width and 0.3 m in *height*

Pavement marking - 1.0 m in width




International Symbol of Accessibility for the Handicapped

Schedule 7D – Standards for Parking Stalls for People with a Disability




(a) 60 – Degree Parking




(b) 90 – Degree Parking

Schedule 7E – Downtown Amenities Incentive Area



Schedule 7F Walkable Areas



*Zoning Bylaw Number 2500, 2007
Schedule 7F Walkable Areas*

DIVISION 8 CLASSIFICATION OF ZONES

Introduction

For purposes of this Bylaw, the area incorporated into the Corporation of the City of Courtenay is hereby divided into zones designated and described by the following classification and their short title equivalents:

Zone Classification	Short Title	Lot Size	Description
Residential Small-Scale Multi-Unit	R-SSMUH	300 m ²	Single Residential, Duplex, Townhouse.
Residential One A	R-1A	1 ha	Single Residential
Residential Three Residential Three A Residential Three B	R-3 R-3A R-3B	1250 m ² 1250 m ² 1250 m ²	Low Density Multi Residential
Residential Four Residential Four A Residential Four B	R-4 R-4A R-4B	1250 m ² 1250 m ² 650 m ²	Medium and High Density Multi Residential
Residential Five	R-5	850 m ²	Low Density Multi Residential
<i>Mobile home subdivision</i>	MH-1	465 m ²	Mobile Home Residential
<i>Mobile home park</i>	MH-2	1.2 ha	
Multiple Use One Multiple Use Two Multiple Use Three Multiple Use Four Multiple Use Five	MU-1 MU-2 MU-3 MU-4 MU-5	650 m ² 850 m ² 650 m ² 1250 m ² 2900 m ²	Low and Medium Density Mixed Residential/Commercial

Zone Classification	Short Title	Lot Size	Description
Commercial One	C-1	500 m ²	Central Commercial
Commercial One A	C-1A	2 ha	
Commercial Two	C-2	1250 m ²	Service Commercial
Commercial Two A	C-2A	2500 m ²	Community service Commercial
Commercial Three	C-3	1250 m ²	Neighbourhood Convenience Store
Commercial Four	C-4	1800 m ²	Office Commercial
Commercial Five	C-5	420 m ²	Heritage Character
Industrial One	I-1	2500 m ²	Heavy Industrial
Industrial Two	I-2	1250 m ²	Light Industrial
Industrial Three	I-3	8 ha	Railway
Public Use and Assembly	PA-1	2500 m ²	Cemetery, Churches, Hospitals
Public Use and Assembly	PA-2	N/A	Parks, Community Centres
Public Use and Assembly	PA-3	2500 m ²	Schools
Agricultural One	A-1	8 ha	Agriculture Land Reserve
Agricultural Two	A-2	8 ha	
Comprehensive Dev. One	CD-1	Varies	Block 72 – Crown Isle
Comprehensive Dev. Three	CD-3	550 m ²	St. Andrews & Idiens Way
Comprehensive Dev. Four	CD-4	N/A	31 st Street
Comprehensive Dev. Six	CD-6	Varies	18 th and Burgess
Comprehensive Dev. Seven	CD-7	450 m ²	Marsland Residential Development
Comprehensive Dev. Eight	CD-8	2 ha	29 th Street/Anfield Road
Comprehensive Dev. Nine	CD-9	1100 m ²	2 nd Street/Duncan Avenue
Comprehensive Dev. Ten	CD-10	1580 m ²	Lerwick Road – Church
Comprehensive Dev. Eleven	CD-11	1100 m ²	Glacier View Lodge
Comprehensive Dev. Twelve	CD-12	1525 m ²	Muir Road/Caledon Crescent
Comprehensive Dev. Fourteen	CD-14	3.5 ha	Creekside Commons Co-housing
Comprehensive Dev. Fifteen	CD-15	450 m ²	Robert Lang/1 st
Comprehensive Dev. Sixteen	CD-16	1250 m ²	Idiens/Lerwick – Multi-Residential
Comprehensive Dev. Seventeen	CD-17	470 m ²	190 Powerhouse Rd
Comprehensive Dev. Nineteen	CD-19	Varies	1360, 1470, 1480 Arden Rd
Comprehensive Dev. Twenty-One	CD-21	Varies	Buckstone Rd
Comprehensive Dev. Twenty-Two	CD-22	450 m ²	2880 Arden Rd
Comprehensive Dev. Twenty-Three	CD-23	SFD 500m ² Duplex 900m ²	1923, 1993 Arden Rd & 2459 Cumberland Rd
Comprehensive Dev. Twenty-Four	CD-24	2000 m ²	2525 Mission Rd
Comprehensive Dev. Twenty-Five	CD-25	Varies	2368, 2498, 2650 Arden Rd
Comprehensive Dev. Twenty-Six	CD-26	1.0 ha	3040 & 3070 Kilpatrick Ave
Comprehensive Dev. Twenty-Seven	CD-27	.55 ha	1025 Ryan Rd
Comprehensive Dev. Twenty-Eight	CD-28	2,792 m ²	2355 Mansfield Dr
Comprehensive Dev. Twenty-Nine	CD-29	2274 m ²	1375 Piercy Ave
Comprehensive Dev. Thirty-One	CD-31	7,320 m ²	310 Hunt Rd
Comprehensive Dev. Thirty-Four	CD-34	1,200 m ²	1679 McPhee Ave

Extent

1. The extent of each zone is shown on Schedule '8'
2. Where a zone boundary is designated as following a highway or a *watercourse*, the centerline of the highway or the *natural boundary* of the *watercourse* or the centerline of a creek shall be the zone boundary.
3. Where a zone boundary does not follow a legally defined line, and where distances are not specifically indicated, the location of the boundary shall be determined by scaling from Schedule '8'
4. If a *lot* is divided by one or more zone boundaries, each of the *lot* portions enclosed by the *lot* boundaries and the zone boundaries must be considered as a separate *lot* for the purposes of determining the requirement of this bylaw in respect of *subdivision*, *setbacks* and lot coverage.
5. *Site area* requirements do not apply to an unattended utility facility and such uses are permitted in each zone.

Part 1 - Residential Small-Scale Multi-Unit Housing (R-SSMUH)

8.1.1 Permitted Uses

The R-SSMUH zone is intended to provide appropriate zoning for residential uses including small-scale multiple unit housing and infill development on serviced lots.

8.1.2 Permitted Uses

In the R-SSMUH Zone, the following uses are permitted, and all other uses are prohibited except as otherwise noted in this bylaw:

Principal Uses

- (1) *Single residential dwelling*
- (2) *Duplex*
- (3) *Townhouse dwelling*

Secondary Uses

- (4) *Secondary suite*
- (5) *Accessory buildings and structures*
- (6) *Home Occupation*
- (7) *Accessory Dwelling Unit*

8.1.3 Density

A maximum of four dwelling units per lot is permitted subject to the development regulations in this zone, and the provisions of Section 6.19.1. General Regulations for Secondary Suites and Accessory Dwelling Units

8.1.4 Minimum Lot Dimensions

(1) Lot Size

- i. A lot shall have an area of not less than 300 m² for a single residential dwelling or duplex.
- ii. Where a lot is developed with a multiple unit form and being subdivided along a party wall, the minimum lot area for a fee simple party wall subdivision is 270 m². Where a fourplex is being created by party wall subdivision, no additional secondary dwelling units are permitted.

(2) Lot Frontage

- i. A lot shall have a frontage of not less than 10 m except for a corner lot, where the frontage shall be not less than 13 m. In the case of a lot fronting the bulb of a cul-de-sac, the frontage shall be measured at the front yard setback line.
- ii. Where lots are being subdivided along a party wall, the minimum lot frontage shall be 9 m.

(3) Lot Depth

- i. A lot shall have a depth of not less than 30 m, measured from the front lot line to the rear lot line.

8.1.5 Lot Coverage

The maximum lot coverage for buildings, structures and impermeable surfaces is 60%.

8.1.6 Setbacks

- (1) Except where otherwise specified in this Bylaw, the following minimum building setbacks shall apply:
 - i. Front yard: 4.0 m except that the minimum front yard setback for garages or carports shall be 6.0 m.
 - ii. Rear Yard: 5.0 m
 - iii. Side Yard: 1.5 m except that
 - (a) Where a side yard flanks a street, excluding a lane, the minimum side yard shall be 3.0 m, and
 - (b) Where a secondary residence or accessory dwelling unit located behind the principal building lacks side or rear lane access, the minimum side yard setback distance for the principal building on one side shall be 3.0 m.
 - (c) Where units are separated by a party wall subdivision, the side yard setback along the party wall shall be 0 m.

8.1.7 Height of Buildings

- (1) The height of a principal building shall not exceed 11.0 m.
- (2) The height of a secondary residence or accessory dwelling unit shall not exceed 6.5 m.

8.1.8. Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in height
- (2) Shall be permitted in the side and rear yard provided they shall conform to all relevant siting regulations of this bylaw
- (3) Shall be permitted at the front of a principal residence provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall not be located within 1.5 m from the side and rear lot line except where the side or rear yard flanks a street, excluding a lane, in which case the minimum yard distance shall be 3.0 m.

8.1.9. Off-Street Parking

- (1) Except as provided in this section, off-*street* parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.
- (2) Where more than one access point to a property is available, such as a front street and laneway, required parking stalls must be distributed in such a manner as to prevent a continuous row of parking stalls .

8.1.10. Landscaping and Screening

- (1) In addition to the Landscape Requirements identified in Division 6, Part 14 of this bylaw, a vegetated buffer or screen fence not more than 1.5 m high shall be provided along rear or side property lines adjoining other properties.

8.1.11. Conditions of Use

- (1) Despite the permitted use regulations in this zone, no more than one (1) Secondary Suite or one (1) Accessory Dwelling Unit shall be permitted as accessory to a single family or duplex dwelling on a lot that is not connected to community water or sewer services.

Part 2 - Residential One A Zone (R-1A)

8.1.8 Permitted Uses

In the R-1A zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

3071

- (1) *Single residential dwelling*
- (2) *Secondary suite*
- (3) *Accessory building* and structures
- (4) *Home occupation*
- (5) Agricultural use on a *lot* over 4,000m²

8.1.9 Minimum Lot Size

A *lot* shall have an area of not less than 1 ha.

8.1.10 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 30.0 m.

8.1.11 Minimum Lot Depth

A *lot* shall have a depth of not less than 35.0 m.

8.1.12 Lot Coverage

A *lot* shall not be covered by *building* and *accessory* buildings to a greater extent than 25% of the total area of the *lot*.

8.1.13 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front yard:* 7.5 m
- (2) *Rear yard:* 9.0 m
- (3) *Side yard:* The *side yard setbacks* shall be 3.5 m except where a *side yard* flanks a *street*, in which case, the minimum distance shall be 4.5 m

8.1.14 Height of Buildings

The *height* of a *principal building* shall not exceed 9.0 m.

8.1.15 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a total *building area* not exceeding 50 m² or 10% of the *rear yard* whichever is greater
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall be permitted at the front of a principal *residence* provided they shall conform to all relevant siting regulations of this bylaw
- (5) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.1.16 Off-Street Parking

Off-*street* parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

Part 3 - Residential Three Zone (R-3)

8.3.1 Permitted Uses

In the R-3 Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

3071

- (1) *Single residential dwellings*
- (2) *Secondary suite*
- (3) *Duplex dwellings*
- (4) *Multi residential dwellings*
- (5) *Accessory buildings and structures*
- (6) *Facility for adults with a disability*
- (7) *Home occupation*
- (8) *Care facility* for parcels with a *site area* of 0.4 ha or greater
- (9) “Notwithstanding any provision of this bylaw, one triplex containing no more than three residential *dwelling units* is a *permitted use* on Lots 1-3, District Lot 118, Comox District, Plan SP4146 (2175 Arlington Place).

8.3.2 Minimum Lot Size

A *lot* shall have an area of not less than 1,250 m².

8.3.3 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 30.0 m.

8.3.4 Floor Area Ratio

Providing all other applicable size, shape and siting conditions are met the maximum *floor area ratio* shall not exceed in the case of multi residential dwellings:

- (1) apartments - .60 *floor area ratio*
- (2) all other residential - .40 *floor area ratio*
- (3) The density allowed on Lot 2, Section 67, Comox District, Plan 31530 shall not exceed 27.5 units per ha of which a maximum of 24 *dwelling units* of the total units permitted can be within an *apartment building*.

8.3.5 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front yard*: 7.5 m
- (2) *Rear yard*: 7.5 m except for apartments which shall be:
 - (a) 9.0 m for the 2nd *storey*
 - (b) 10.0 m for the 3rd *storey*
- (3) *Side yard*: The *side yard setbacks* shall total 4.5 m with a minimum *side yard setback* on one side of 1.5 m except where a *side yard* flanks a *street* in which case the minimum distance shall be 4.5 m.

And further, where the back of a *building* is adjacent to or faces a side *lot line* the minimum *side yard setback* shall be 6.0 m.

8.3.6 Height of Buildings

The *height* of a *principal building* shall not exceed 10 m.

8.3.7 Useable Open Space

Useable open space shall be provided on a *lot* in the amount of 30.0 m² for each one bedroom *dwelling unit* and 50.0 m² for each *dwelling unit* with two or more bedroom. However, usable open space shall be provided at 10.0 m² per unit for care facilities.

8.3.8 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a total *building area* not exceeding 50.0 m² or 10% of the *rear yard*, whichever is greater, except where the *structure* is used to cover parking, in which case, the *floor area* shall not exceed 20% of the *rear yard*, and shall not extend for more than 2/3 of the length of any property line or 30.0 m, whichever is less.
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall not be permitted at the front of a principal *residence*
- (5) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.3.9 Off-Street Parking and Loading

Off-*street* parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.3.10 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) A landscaped screen, *fence* or a combination thereof of not less than 3.0 m in *height* and width shall be provided and maintained to the satisfaction of the *City* on all property lines adjoining all other adjoining properties.
- (2) Where a *lot* adjoins 17th *Street*, 29th *Street*, Cliffe Avenue, Cumberland Road, Island Highway, Lerwick Road or Ryan Road a landscaped area of at least 7.5 m in width extending along the entire frontage of the property shall be provided inside the property line. Where a *lot* in this zone adjoins any other *street*, a landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.

Part 3 - Residential Three A Zone (R-3A)

8.3.11 Permitted Uses

In the R-3A Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) *Single residential* dwellings
- (2) *Duplex* dwellings
- (3) *Townhouse* dwellings
- (4) *Accessory* buildings and structures
- (5) *Home Occupation*

2513

8.3.12 Minimum Lot Size

A *lot* shall have an area of not less than 1,250 m².

8.3.13 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 30.0 m.

8.3.14 Floor Area Ratio

Providing all other applicable size, shape and siting conditions are met the maximum *floor area ratio* shall not exceed 0.50.

8.3.15 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front yard:* 7.5 m
- (2) *Rear yard:* 7.5 m
- (3) *Side yard:* 4.5 m except where the back of a *building* is adjacent to or faces a *side lot line* the minimum *side yard setback* shall be 6.0 m.

8.3.16 Height of Buildings

The *height* of a *principal building* shall not exceed 5.0 m.

8.3.17 Useable Open Space

Useable open space shall be provided on a *lot* in the amount of 20.0 m² per *dwelling unit*.

8.3.18 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a total *building area* not exceeding 50.0 m², except where the *structure* is used to cover parking, in which case, the *floor area* shall not exceed 20% of the *rear yard*, and shall not extend for more than 2/3 of the length of any property line or 30.0 m, whichever is less.
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall be permitted at the front of a principal *residence*, provided they shall conform to all relevant siting regulations of this bylaw
- (5) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.3.19 Off-Street Parking

Off-*street* parking shall be provided and maintained in accordance with the requirements of Division 7 of this Bylaw, with the following exceptions:

The minimum number of off-*street parking spaces* shall be provided as follows:

- (1) one (1) *parking space* per *dwelling unit* for a *single residential* dwelling or *duplex*;
- (2) one (1) *parking space* per *dwelling unit* for a *townhouse* dwelling plus one (1) additional *parking space* for every three (3) *dwelling units* or portion thereof, plus one (1) additional *parking space* for each *dwelling unit* containing three (3) or more bedroom.

8.3.20 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (3) A landscaped screen, *fence* or a combination thereof of not less than 3.0 m in *height* and width shall be provided and maintained to the satisfaction of the *City* on all property lines adjoining all other adjoining properties.
- (1) Where a *lot* adjoins 17th *Street*, 29th *Street*, Cliffe Avenue, Cumberland Road, Island Highway, Lerwick Road or Ryan Road a landscaped area of at least 7.5 m in width extending along the entire frontage of the property shall be provided inside the property line. Where a *lot* in this zone adjoins any other *street*, a landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.

Part 3 - Residential Three B Zone (R-3B)

8.3.21 Permitted Uses

In the R-3B Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) *Single residential dwellings*
- (2) *Duplex dwellings*
- (3) *Multi residential dwellings*
- (4) *Accessory buildings and structures*
- (5) *Home occupation*

8.3.22 Minimum Lot Size

A *lot* shall have an area of not less than 1,250 m².

8.3.23 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 25.0 m.

8.3.24 Floor Area Ratio

Providing all other applicable size, shape and siting conditions are met the maximum *floor area ratio* shall not exceed 0.4.

8.3.25 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front yard:* 7.5 m
- (2) *Rear yard:* 7.5 m
- (3) *Side yard:* 4.5 m for a one *storey building*
7.5 m for a two *storey building*

And further, where the back of a *building* is adjacent to or faces a side *lot line* the minimum *side yard setback* shall be 6.0 m.

8.3.26 Height of Buildings

On any one *lot* having four or more *dwelling units* a maximum of 70% of the *dwelling units* shall have a *building height* not exceeding 8.0 m, and the remainder of the *dwelling units* shall have a *building height* not exceeding 4.5 m.

8.3.27 Useable Open Space

Useable open space shall be provided on a *lot* in the amount of 30.0 m² for each one bedroom *dwelling unit* and 50.0 m² for each *dwelling unit* with two or more bedroom.

8.3.28 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a total *building area* not exceeding 50.0 m², except where the *structure* is used to cover parking, in which case, the *floor area* shall not exceed 20% of the *rear yard*, and shall not extend for more than 2/3 of the length of any property line or 30 m, whichever is less
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall not be permitted at the front of a principal *residence*
- (5) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.3.29 Off-Street Parking and Loading

Off-*street* parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this Bylaw.

8.3.30 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (4) A landscaped screen, *fence* or a combination thereof of not less than 3.0 m in *height* and width shall be provided and maintained to the satisfaction of the *City* on all property lines adjoining all other adjoining properties.
- (1) Where a *lot* adjoins 17th Street, 29th Street, Cliffe Avenue, Cumberland Road, Island Highway, Lerwick Road or Ryan Road a landscaped area of at least 7.5 m in width extending along the entire frontage of the property shall be provided inside the property line. Where a *lot* in this zone adjoins any other *street*, a landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.

Part 4 - Residential Four Zone (R-4)

8.4.1 Permitted Uses

In the R-4 Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) *Single residential dwellings*
- (2) *Duplex dwellings*
- (3) *Multi residential dwellings*
- (4) *Accessory buildings and structures*
- (5) *Facility for adults with a disability*
- (6) *Home occupation*
- (7) *Daycare*

8.4.2 Minimum Lot Size

A *lot* shall have an area of not less than 1,250 m².

8.4.3 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 30.0 m.

8.4.4 Floor Area Ratio

Providing all other applicable size, shape and siting conditions are met the maximum *floor area ratio* for multi residential dwellings shall not exceed:

- (1) *Apartments - 1.2 floor area ratio*
- (2) *All other residential - .70 floor area ratio*

8.4.5 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front yard:* 7.5 m
- (2) *Rear yard:* 9.0 m, except for apartments where the following is required:
 - 9.0 m - 2nd *storey*
 - 10.0 m - 3rd *storey*
 - 13.5 m - 4th *storey*
- (3) *Side yard:*
 - 4.5 m - 2 or less *storeys*
 - 6.0 m - 3rd *storey*
 - 7.5 m - 4th *storey*

And further, where the back of a *building* is adjacent to or faces a side *lot line* the minimum *side yard setback* shall be 6.0 m.

8.4.6 Height of Building

The *height* of a *building* shall not exceed 14.0 m for an *apartment building*, not exceed 9.0 m for townhouses, *single residential dwellings* and duplexes.

8.4.7 Useable Open Space

Useable open space shall be provided on a *lot* in the amount of:

- (1) 20.0 m² per *dwelling unit* within an *apartment building*; or
- (2) 30.0 m² per one bedroom *dwelling unit* and 50.0 m² per *dwelling unit* with two or more bedroom.

8.4.8 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a total *building area* not exceeding 50.0 m² or 10% of the *rear yard*, whichever is greater, except where the *structure* is used to cover parking, in which case, the *floor area* shall not exceed 20% of the *rear yard*, and shall not extend for more than 2/3 of the length of any property line or 30.0 m, whichever is less
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall not be permitted at the front of a principal *residence*
- (5) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.4.9 Off-Street Parking and Loading

Off-*street* parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this Bylaw.

8.4.10 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

2585

- (1) A landscaped screen, *fence* or a combination thereof of not less than 3.0 m in *height* and width shall be provided and maintained to the satisfaction of the *City* on all property lines adjoining all other adjoining properties except for building or development of a *single residential dwelling* or *duplex*.
- (2) Where a *lot* adjoins 17th *Street*, 29th *Street*, Cliffe Avenue, Cumberland Road, Island Highway, Lerwick Road or Ryan Road a landscaped area of at least 7.5 m in width extending along the entire frontage of the property shall be provided inside the property line. Where a *lot* in this zone adjoins any other *street*, a landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.

Part 4 - Residential Four A Zone (R-4A)

8.4.11 Permitted Uses

In the R-4A Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) *Single residential dwellings*
- (2) *Duplex dwellings*
- (3) *Multi residential dwellings*
- (4) *Accessory buildings and structures*
- (5) *Home occupation*
- (6) *Daycare*
- 2870 (7) *Care Facility*
- 2870 (8) *Accessory commercial services for the personal care and convenience of onsite residents*
- 2870 (9) *Community Service limited to adult daycare*

8.4.12 Minimum Lot Size

A *lot* shall have an area of not less than 1,250 m².

8.4.13 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 30.0 m.

8.4.14 Floor Area Ratio

Providing all other applicable size, shape and siting conditions are met the maximum *floor area ratio* for multi residential dwellings shall not exceed:

- (1) *Apartments - 1.33 floor area ratio*
- (2) *All other residential - .85 floor area ratio*
- 2870 (3) *Care Facility – 1.0 floor area ratio*

8.4.15 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front yard:* 6.0 m
- (2) *Rear yard:* 6.0 m
- (3) *Side yard* 3.0 m
4.5 m - 4th *storey* or where *side yard* flanks a *street*

And further, where the back of a *building* is adjacent to or faces a *side lot line* the minimum *side yard setback* shall be 6.0 m.

Notwithstanding the *setback* requirements above, the following minimum *building setbacks* shall apply on Lots 8, 9 & 10, Block 1, Section 67, Comox District, Plan 9900:

- (1) *Front yard:* 6.0 m
- (2) *Rear yard:* 6.0 m
3.0 m
4.5 m - 4th *storey* or where *side yard* flanks a *street*
- (3) Exterior *Side yard* adjacent to Cliffe Avenue 7.5 m
- (4) *Side yard* Adjacent to Comox Logging Right of Way 4.5 m
6.0 m for 3rd *Storey*
7.5 m for 4th *Storey*

8.4.16 Height of Building

The *height* of a *building* shall not exceed 14.0 m for an *apartment building* and not to exceed 9.0 m for townhouse dwellings.

8.4.17 Useable Open Space

Usable open space shall be provided on a *lot* in the amount of:

- (1) 20.0 m² per *dwelling unit* within an *apartment building*; or
- (2) 30.0 m² per one bedroom *dwelling unit* and 50.0 m² per *dwelling unit* with two or more bedroom.

8.4.18 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a total *building area* not exceeding 50.0 m², except where the *structure* is used to cover parking, in which case, the *floor area* shall not exceed 20% of the *rear yard*, and shall not extend for more than 2/3 of the length of any property line or 30.0 m, whichever is less
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall not be permitted at the front of a principal *residence*
- (5) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.4.19 Off-Street Parking

Off-*street* parking shall be provided and maintained in accordance with the requirements of Division 7.

A lane may be used as the required aisle width as set out in Schedule 7B of Division 7 of this bylaw provided that the developer constructs the lane to meet all *City* standards regarding paving and drainage.

8.4.20 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) A landscaped screen, *fence* or a combination thereof of not less than 3.0 m in *height* and width shall be provided and maintained to the satisfaction of the *City* on all property lines adjoining all other adjoining properties.
- (2) Where a *lot* adjoins 17th Street, 29th Street, Cliffe Avenue, Cumberland Road, Island Highway, Lerwick Road or Ryan Road a landscaped area of at least 7.5 m in width extending along the entire frontage of the property shall be provided inside the property line. Where a *lot* in this zone adjoins any other *street*, a landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.

Part 4 - Residential Four B Zone (R-4B)

8.4.21 Permitted Uses

In the R-4B Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) *Single residential dwellings*
- (2) *Secondary suite*
- (3) *Duplex dwellings*
- (4) *Multi residential dwellings*
- (5) *Accessory buildings and structures*
- (6) *Day care*
- 2513 (7) *Home Occupation*

8.4.22 Minimum Lot Size

A lot shall have an area of not less than 650 m².

- 2842 (a) notwithstanding the above, a minimum lot size of 300 m² is permitted on Amended Lot 110 (DD43420N), Section 61, Comox District, Plan 472A, Except that Part Lying to the South East of a Boundary Parallel to the South Easterly Boundary of Said Lot and Perpendicularly Distant 10 Feet North Westerly Therefrom (344 3rd Street) and Lot 1, Block 72, Section 61, Comox District, Plan 472 Except that Part Lying to the South East of a Boundary Parallel to the South Easterly Boundary of Said Lot and Perpendicularly Distant 10 Feet North Westerly Therefrom (356 3rd Street).

8.4.23 Minimum Lot Frontage

A lot shall have a frontage of not less than 12.0 m.

- 2842 (a) notwithstanding the above, a minimum frontage of 10 metres is permitted on Amended Lot 110 (DD43420N), Section 61, Comox District, Plan 472A, Except that Part Lying to the South East of a Boundary Parallel to the South Easterly Boundary of Said Lot and Perpendicularly Distant 10 Feet North Westerly Therefrom (344 3rd Street).
- 2842 (b) notwithstanding the above, a minimum frontage of 11 metres is permitted on Lot 1, Block 72, Section 61, Comox District, Plan 472 Except that Part Lying to the South East of a Boundary Parallel to the South Easterly Boundary of Said Lot and Perpendicularly Distant 10 Feet North Westerly Therefrom (356 3rd Street).

8.4.24 Floor Area Ratio

Providing all other applicable size, shape and siting conditions are met the maximum floor area ratio for multi residential shall not exceed:

- (1) Apartments - 1.0 *floor area ratio* except where parking is provided within a principle *building* in which case an amount may be added to the floor space ratio equal to 0.2 multiplied by the percentage of the total *parking spaces* which are provided in this manner.
- (2) All other residential - 0.7 *floor area ratio*

8.4.25 Setbacks

Except where otherwise specified in this bylaw, the following requirements shall apply:

- (1) *Front yard*: 15% of *lot depth**
- (2) *Rear yard*: 20% of *lot depth**
- (3) *Side yard*: 12% of *lot width* for each side except where the *side yard* flanks a *street*, in which case the minimum shall be 3.5 m along the subject property line*

*all *setbacks* are based on averages with the following minimum:

- (1) *Front yard*: 3.5 m
- (2) *Rear yard*: 6.0 m
- (3) *Side yard*: 2.0 m (3.5 m where it flanks a *street*)

8.4.26 Height

- (1) 13.71 m for apartments with *underground parking*
- (2) 10.0 m for apartments otherwise
- (3) 9.15 m for all other buildings

8.4.27 Useable Open Space

Usable open space shall be provided on a *lot* in the amount of :

- (1) 20.0 m² per *dwelling unit* within an *apartment building*; or
- (2) 30.0 m² per one bedroom *dwelling unit* and 50.0 m² per *dwelling unit* with two or more bedroom.

8.4.28 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a *building area* not exceeding 50.0 m², except where the *structure* is used to cover parking, in which case, the *floor area* shall not exceed 50% of the *rear yard*, and shall not extend for more than 2/3 the length of any property line or 30.0 m, whichever is less
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall not be permitted at the front of a principal *residence*

- (5) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.4.29 Off-Street Parking

Off-*street* parking shall be provided and maintained in accordance with the requirements of Division 7.

2685

Off-*street* parking shall be provided at the rate of one space per residential unit within the Residential Four B Zone (R-4B).

A lane may be used as the required aisle width a set out in Schedule 7B of Division 7 of this bylaw provided that the developer constructs the lane to meet all *City* standards regarding paving and drainage.

8.4.30 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

2720

- (1) Where a *lot* adjoins 17th *Street*, 29th *Street*, Cliffe Avenue, Cumberland Road, Island Highway, Lerwick Road or Ryan Road a landscaped area of at least 7.5 m in width extending along the entire frontage of the property shall be provided inside the property line. Where a *lot* in this zone adjoins any other *street*, a landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.

Part 5 - Residential Five Zone (R-5)

8.5.1 Permitted Uses

In the R-5 Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) *Single residential* dwellings
- (2) *Duplex* dwellings
- (3) Multi residential dwellings
- (4) One recreation *building* which shall be solely for the use of tenants and their guests
- (5) *Accessory* buildings and structures

8.5.2 Minimum Lot Size

A *lot* shall have an area of not less than 850 m².

8.5.3 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 32.0 m.

8.5.4 Floor Area Ratio

Providing all other applicable size, shape and siting conditions are met the maximum *floor area ratio* for multi residential buildings shall not exceed:

- | | |
|---------------------------|-----------------------------|
| (1) Apartments | .90 <i>floor area ratio</i> |
| (2) All other residential | .60 <i>floor area ratio</i> |

8.5.5 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- | | |
|------------------------|--------------------|
| (1) <i>Front yard:</i> | 7.5 m |
| (2) <i>Rear yard:</i> | 7.5 m |
| (3) <i>Side yard:</i> | 4.5 m |
| | 6.0 m – 3rd storey |

And further, where the back of a *building* is adjacent to or faces a side *lot line* the minimum *side yard setback* shall be 6.0 m.

8.5.6 Height of Buildings

The *height* of a *building* shall not exceed 9.0 m in *height*.

8.5.7 Useable Open Space

Usable open space shall be provided on the *lot* at the rate of not less than 15.0 m² for each one-bedroom unit and not less than 20.0 m² for each two-bedroom unit contained in a *building* used as a multi residential dwelling.

8.5.8 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a *building area* not exceeding 50.0 m², except where the *structure* is used to cover parking, in which case, the *floor area* shall not exceed 20% of the *rear yard*, and shall not extend for more than 2/3 of the length of any property line or 30.0 m, whichever is less
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall not be permitted at the front of a principal *residence*
- (5) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.5.9 Off-Street Parking and Loading

Notwithstanding Schedule 7A a minimum of one (1) *parking space* shall be provided for every three *dwelling units* within the overall development plus a minimum of one (1) *parking space* for every 50.0 m² of *floor area* within the recreation *building*.

8.5.10 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) A landscaped screen, *fence* or a combination thereof of not less than 3.0 m in *height* and width shall be provided and maintained to the satisfaction of the *City* on all property lines adjoining all other adjoining properties.
- (2) Where a *lot* adjoins 17th *Street*, 29th *Street*, Cliffe Avenue, Cumberland Road, Island Highway, Lerwick Road or Ryan Road a landscaped area of at least 7.5 m in width extending along the entire frontage of the property shall be provided inside the property line. Where a *lot* in this zone adjoins any other *street*, a landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.

Part 6 - Mobile Home Residential Subdivision Zone (MH-1)

8.11.1 Permitted Uses

In the MH-1 Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) *Mobile homes*
- (2) *Single residential dwelling*, must be one *storey* with no basement
- (3) *Accessory buildings and structures*
- (4) Notwithstanding the provisions of this bylaw a secondary suite is permitted on the property legally described as Lot 64, District Lot 159, Comox District, Plan 30921 (446 Qualicum Avenue).

8.11.2 Minimum Lot Size

A *lot* in a *mobile home subdivision* shall have an area of not less than 465 m² and 550 m² for a *corner lot*.

8.11.3 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 14.0 m except for a *corner lot* in which case the minimum frontage shall be 15.5 m.

8.11.4 Minimum Lot Coverage

A *lot* shall not be covered by buildings to a greater extent than 40% of the total lot area.

8.11.5 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front yard:* 4.5 m
6.0 m for a *garage*
- (2) *Rear yard:* 3.0 m
- (3) *Side yard:* 1.5 m on one side and 3.0 m on the other side and 4.5 m where the *side yard* flanks a *street*

8.11.6 Foundation

Any *mobile home* shall be placed on a permanent perimeter concrete foundation.

8.11.7 Height of Building or Structure

No *building* or *structure* shall be greater in *height* than 4.5 m.

8.11.8 Additions

All additions to a *mobile home* located in a *mobile home subdivision* including carports, shelters, porches, vestibules, and room shall be constructed in compliance with the current

B.C. *Building Code*.

8.11.9 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a *floor area* not exceeding 45.0 m² or 10% of the *rear yard* whichever is greater
- (3) Shall be permitted in the side and rear boundary of the *mobile home* space provided they are within 1.5 m from the side and rear boundary of the *mobile home* space except where the side boundary flanks a *street*, excluding a lane, in which case the minimum distance shall be 4.5 m
- (4) Shall be permitted in the front of the principal *residence* provided they shall conform to all relevant siting regulations of this bylaw

8.11.10 Off-Street Parking

Off-*street* parking shall be provided and maintain in accordance with the requirements of Division 7 of this bylaw.

Part 7 - Mobile Home Park Residential Zone (MH-2)

8.12.1 Permitted Uses

In the MH-2 Zone, the following uses are permitted and shall conform to this bylaw and amendments thereto and all other uses are prohibited:

- (1) *Mobile home* and their *accessory* buildings and structures; and
- (2) Service buildings and structures, recreational buildings and structures, or a combination thereof, *accessory* to the *mobile home* use.

8.12.2 General Provisions

- (1) A copy of the approved Development Permit, *mobile home park* plans and a copy of this bylaw shall be posted prominently and permanently in the *mobile home park office* for the reference of the residents.
- (2) No *mobile home* in a *mobile home park* may be occupied as a dwelling or installed unless it:
 - (a) meets the Canadian Standards Association Standards Z-240 or A-277 or British Columbia *Building Code* Standards;
 - (b) is connected water, sanitary sewer, storm drainage and electrical services in accordance with the British Columbia *Building Code*, Plumbing Code and Electrical Code;
 - (c) is located on a *mobile home pad* and is supported on a foundation in accordance with the British Columbia *Building Code* or the *Mobile home*, C.S.A. foundation standards approved by the *Building Inspector*; and
 - (d) is located on an approved *mobile home lot*.
- (3) The plumbing, electrical and *building* in any *mobile home park* including additions and alterations shall comply with all *City* of Courtenay bylaws and regulations and the British Columbia *Building Code*, Plumbing Code and Electrical Code.
- (4) The *City* may require the applicant to provide additional relevant information, inspections and tests including but not limited to topographic and soil condition data.
- (5) No person shall dispose of garbage or refuse or any sort of waste except in accordance with the arrangements made by the owner of the *mobile home park*, as approved by the *City*.

8.12.3 Site Area

The minimum *site area* for the *mobile home park* shall be 2 ha.

8.12.4 Density

The maximum density for a *mobile home park* shall be 20 *mobile home* units per hectare.

8.12.5 Frontage

A *mobile home park* shall have a minimum frontage of 30.0 m on to the highway from which access is obtained, with such access being for the sole purpose of allowing entry to and egress from the *mobile home park*.

8.12.6 Mobile Home Space

- (1) The minimum area for a *mobile home space* shall be 325 m² for an internal *lot* and 360 m² for a *corner lot*.
- (2) The minimum frontage of each *mobile home space* abutting a roadway shall be 12.0 m and 13.5 m for a *corner lot*.
- (3) Each *mobile home space* shall be clearly and permanently marked in a format outlined on a plan registerable at the Land Title Office as prepared by a BC Land Surveyor.
- (4) All *mobile home spaces* shall:
 - (a) be clearly numbered; and
 - (b) have access only from an internal roadway and not directly from a highway.

8.12.7 Lot Coverage

A *mobile home space* shall not be covered by buildings to a greater extent than 40% of the area of the *mobile home space*.

8.12.8 Setbacks

Except where otherwise specified in this bylaw, the following minimum *building setbacks* shall apply. *Mobile homes* and additions shall be located on each *mobile home space* in a *mobile home park* so that there will be not less than the following *setbacks*:

- (1) *Front yard*: 4.5 m
 6.0 m for a *garage* or carport
- (2) *Rear yard*: 3.0 m
- (3) *Side yard*: 1.5 m on one side and 3.0 m on the other side and 4.5 m where the *side yard* flanks a *street*

8.12.9 Height of Building or Structure

No *building* or *structure* shall be greater in *height* than 4.5 m except for a service, storage or recreation *building* which shall not be greater than 6.0 m.

8.12.10 Mobile homes per Space/Lot

No more than one *mobile home* shall be located on a *mobile home space*.

8.12.11 Skirtings

No *mobile home* in a *mobile home park* may be occupied as a dwelling unless:

- (1) skirtings are installed within 60 days of installation of the *mobile home* on a *mobile home pad* which shall have two easily removable access panels of a minimum width of 1.2 m, one providing direct access to the area enclosed by the skirting for inspection or servicing the service connections to the *mobile home*, and the other providing access to the area enclosed by the skirting for storage;
- (2) skirtings installed are factory prefabricated or of equivalent quality and painted or prefinished so that the design and construction compliment the main *structure*; and
- (3) skirtings installed have ventilation openings that conform to the requirements of the British Columbia *Building Code* and the ground cover of the crawl space shall conform to the requirements of the British Columbia *Building Code*.

8.12.12 Permissible Additions

- (1) All additions or *accessory* structures to a *mobile home* located in a *mobile home park* including carports, garages, shelters, porches, vestibules, and room shall require a *building* permit and be constructed in compliance with the current British Columbia *Building Code*.
- (2) All attached or *accessory* structures such as porches, sun room, additions and storage facilities shall be factory prefabricated units or an equivalent quality and shall be painted or prefinished so that the design and construction shall compliment the main *structure*.

8.12.13 Buffer Strip

Every *mobile home park* shall have immediately within its boundaries, a buffer area of a minimum of 7.5 m in depth, within which:

- (1) No recreation, amenity or service areas may be located;
- (2) No *mobile home* space or an owner's residential plot may be located;
- (3) No *building* or *structure* may be erected or located;
- (4) No garbage disposal area shall be located;
- (5) Except where danger is involved no plant material may be removed nor may any substance of which land is composed be deposited or removed, except as part of a recognizable beautification scheme approved by the authority having jurisdiction; and
- (6) No roads except those which cross it as close to right angles as practical to connect the roadway to the highway.

8.12.14 Owner's/Manager's Residential Plot

- (1) An owner's/manager's residential plot shall be permitted within a *mobile home park* if the area of the plot is not less than 465 m² with a frontage of 20.0 m.
- (2) An owner's/manager's residential plot shall include sufficient area to provide two off-street *parking spaces* for owner's/manager's use and a minimum of 2 *parking spaces* for visitors and customers.

8.12.15 Parking

- (1) Two *parking spaces* measuring a minimum of 2.75 x 5.5 m shall be provided within each *mobile home pad*. In addition, for every 4 *mobile homes*, on additional *parking space* shall be provided within the *mobile home park*.
- (2) *Parking spaces* shall be graded for proper drainage and be paved and dust free.

8.12.16 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*;
- (2) Shall have a *floor area* not exceeding 45.0 m² or 10% of the *rear yard* whichever is greater;
- (3) Shall be permitted in the side and rear boundary of the *mobile home* space provided they are within 1.5 m from the side and rear boundary of the *mobile home* space except where the side boundary flanks a *street* in which case the minimum distance shall be 4.5 m; and
- (4) Shall be permitted in the front of the principal *residence* provided they shall conform to all relevant siting regulations of this bylaw.

8.12.17 Tenant Storage

- (1) One or more separate storage compounds shall be provided within a *mobile home park* for the storage of boats, trailers, recreation vehicles, or other large item owned by the tenants that are not appropriate to store on a *mobile home lot*.
- (2) The storage compound shall be securely fenced, gated and lighted for security reasons and shall be screened from public view by fencing or *landscaping* approved by the *City*.
- (3) Only communal buildings owned by the owner of the *mobile home park* shall be constructed in the storage compound for the sole use of the residents of the *mobile home park*.
- (4) No outdoor portion of a *mobile home park* shall be used for or permitted to be used for the wrecking or storage of derelict automobiles, trucks, tractors, machinery, lumber, flammable debris or other unused item or equipment that the *City* considers being a public nuisance or junk.

8.12.18 Recreation and Landscaped Areas

- (1) Not less than 20.0 m² per *mobile home* space shall be devoted to tenant's recreational uses, and shall be provided in a convenient and accessible location. For the purpose of calculating recreational space requirements, any indoor recreational space provided shall be counted as double its actual area.
- (2) The recreation areas shall not include buffer areas, *accessory* buildings, *mobile home* spaces, roadways and storage areas.
- (3) Recreation areas shall be provided with suitable equipment, the safety of design and construction of which shall be subject to the approval of the *City*.
- (4) All recreation areas and other areas in the *mobile home park*, other than *mobile home pads*, roadways and parking areas shall be suitably landscaped and maintained subject to the approval of the *City*.
- (5) Recreational areas and open spaces shall be connected to the internal *street* and walkway system of the development and such areas and spaces shall be provided in one or more convenient and accessible locations.

8.12.19 Access, Roadways and Walkways

(1) Access

- (a) No *mobile home park* shall be established or extended unless the highway access to the *mobile home park* is approved by the *City*.
- (b) A second access from a public highway separated by at least 60.0 m from the first access shall be provided to each *mobile home park* containing 50 or more *mobile home* spaces.

(2) Roadways

- (a) All *mobile home* spaces, owner's residential plot, storage areas and service buildings as well as other facilities where access is required shall have access by roadways.
- (b) Minimum roadway width requirements shall be as follows:
 - (i) with parking on one side shall have a minimum paved width of 9.0 m and a right-of-way of 12 m.
 - (ii) with no parking shall have a minimum paved width of 7.2 m and right-of-way of 12 m.
 - (iii) one way minor roads shall not exceed 150 m in length unless connected to a secondary road access, and cul-de-sacs shall not exceed 60.0 m in length as measured from the centre line of a connecting roadway to the centre of the cul-de-sac turn around.
 - (iv) Cul-de-sacs shall have a minimum turning circle right-of-way radius of 14.0 m and a minimum pavement radius of 12.5 m.
 - (v) All streets and roadways in the *mobile home park* shall be designed, constructed and paved in accordance with the *City* of Courtenay Engineering Design Standards and Specifications and certified by a Professional Engineer registered in BC.

- (vi) Adequate *street* lighting shall be designed by a Professional Engineer to the city's standards and policies and installed and energized prior to the issuance of any occupancy permit(s) by the *City*. Such lighting shall meet the *City* of Courtenay Engineering Design Standards and Specifications and maintained to adequately illuminate the traveled portion of the roadway including all intersections, the turning circle of cul-de-sacs, any point at which an internal roadway changes direction 30 degrees or more, and any off-*street* visitor parking areas and storage areas in accordance with the "TAC Guide for Design of Roadway Lighting"

(3) Walkways and Sidewalks

- (a) A hard-surfaced walkway of minimum 1.5 m in width shall be provided to facilitate access from or within the *mobile home park* to any public open space, recreation areas, neighbourhood or public school.
- (b) A walkway or sidewalk shall be provided on at least one side of a main distributor road within the *mobile home park*.
- (c) Walkways may be required for direct access to recreation or multi-purpose service centres if roadways are not direct.
- (d) Cul-de-sacs having more than 10 lots including the *corner lots* shall be provided with a sidewalk.

8.12.20 Water Supply

- (1) The owner of a *mobile home park* shall provide a water supply system that is connected directly to the municipal water supply system. The water system shall be designed by a Professional Engineer in accordance with engineering requirements, specifications and bylaw, regulations of the *municipality* and Regional Public Health Engineer.
- (2) Water service shall be distributed to:
 - (a) each service *building*
 - (b) each *mobile home* space
 - (c) fire hydrants
- (3) Water shall not be distributed to any terminal from which the water would not be intercepted by an approved sewage fixture, nor to any space that is not provided with an approved *mobile home* drain terminal connected to a sewer as required.
- (4) Each water distribution branch line servicing a *mobile home* space for the use of a *mobile home*, shall have a minimum diameter of 19 mm.
- (5) The water terminal on each *mobile home* space shall conform to the engineering standards and specifications required by the *City*.
- (6) Hydrants for fire protection shall be provided and located within 90.0 m of each manufactured home *lot*, as measured along the *street* frontage. Hydrants shall not be located more than 200 m apart and shall be installed in accordance with the requirements of the *City*.
- (7) Upon completion of construction, the owner of the *mobile home park* shall provide to the *City* as-built drawings of the water system, certifying the constructed quality of the works, signed and sealed by a Professional Engineer.
- (8) Meter boxes are required to be installed at the property line or back of roadway for all *mobile home* lots for the subsequent installation of water meter in accordance with *City* standards.

8.12.21 Sanitary Sewerage and Waste Water Disposal System

- (1) The owner of a *mobile home park* shall provide for the disposal of all waste water and of all body wastes that are generated within the *mobile home park* by providing a sewer system connected to all plumbing fittings and sewage laterals in the *mobile home pads*. The sewer system shall be connected directly into the municipal sewage disposal system and shall be designed and constructed by a Professional Engineer in accordance with the engineering requirements, specifications, bylaw and regulations of the *City* and the BC Plumbing Code.
- (2) The sewer terminal on each *mobile home* space shall conform to the engineering standards and specifications required by the *City*.
- (3) Upon completion of construction, the owner of the *mobile home* development shall provide to the *City* as-built drawings of the sewage and wastewater disposal system with the construction quality of works certified by a Professional Engineer.

8.12.22 Garbage Disposal

The owner of a *mobile home park* shall dispose of garbage or refuse in accordance with the *City* of Courtenay Refuse Collection and Removal Bylaw No. 2244, 2002 and revisions thereto.

8.12.23 Supervision and Reporting

- (1) Every *mobile home park* shall be kept free of flammable debris and rubbish at all time.
- (2) The owner shall report the installation or replacement of *mobile homes* and additions in the *mobile home park*, with the exception of skirting, to the *City*.

8.12.24 Occupancy

No person shall cause or permit a *mobile home park* to be occupied by manufactured homes until advised in writing by the *Building Inspector* that authorization to do so is given.

Part 8 - Multiple Use One Zone (MU-1)

8.13.1 Permitted Uses

In the MU-1 Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- | (1) Residential | (2) Non-Residential | (3) Combined Uses |
|--|--|---|
| (a) <i>Single residential dwelling</i> | (a) <i>Accessory buildings</i> | Combined residential - non-residential uses are permitted within the same <i>building</i> in this zone. |
| (b) <i>Duplex dwelling</i> | (b) <i>Care facility</i> | |
| (c) <i>Boarding</i> | (c) <i>Day care</i> | |
| (d) <i>Home occupation</i> | (d) <i>Facility for adults with a disability</i> | |
| | (e) <i>Medical clinic</i> | |
| | (f) <i>Office</i> | |
| | (g) <i>Parking lot</i> | |
| | (h) <i>School</i> | |

- 2784 (4) Notwithstanding items 1-3 a mixed use building containing multi-family residential dwelling units is permitted and medical clinic, parking lot and school are prohibited on the property legally described as Lot 19, Section 41, Comox District, Plan 9230 (1465 Grieve Avenue).

8.13.2 Minimum Lot Size

A *lot* shall have an area of not less than 650 m².

8.13.3 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 20.0 m.

8.13.4 Lot Coverage

A *lot* shall not be covered by buildings and *accessory* buildings to a greater extent than 40% of the total area of the *lot*

8.13.5 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- | | |
|------------------------|---|
| (1) <i>Front yard:</i> | 7.5 m except where the area between a <i>building</i> and a front <i>lot line</i> is landscaped and not used for off- <i>street</i> parking, the <i>setback</i> may be reduced to 4.5 m |
| (2) <i>Rear yard:</i> | 7.5 m |
| (3) <i>Side yard:</i> | 1.5 m except where the <i>side yard</i> flanks a <i>street</i> in which case 4.5 m |

8.13.6 Height of Buildings

The *height* of a *principal building* shall not exceed 8.0 m.

8.13.7 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a *floor area* not exceeding 50.0 m² or 10% of the *rear yard* whichever is greater
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all siting regulations of this bylaw
- (4) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.13.8 Off-Street Parking and Loading

Off-*street* parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this Bylaw.

8.13.9 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where a *lot* adjoins a residential or institutional use or adjoins 17th *Street*, 29th *Street*, Cliffe Avenue, Cumberland Road, Island Highway, Lerwick Road, Mission Road or Ryan Road a landscaped area of at least 7.5 m in width extending along the entire frontage of the property shall be provided inside the property line. Where a *lot* in this zone adjoins any other *street*, a landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.
- (2) To separate parking, internal roads, services or storage areas from adjacent properties, a landscaped buffer area of at least 2.0 m in width and 2.0 m in *height* shall be provided along the inside of all property lines.
- (3) Loading areas, garbage and recycling containers shall be screened and gated to a minimum *height* of 2 m by a *landscaping* screen or solid decorative *fence* or a combination thereof.

Part 9 - Multiple Use Two Zone (MU-2)

8.14.1 Permitted Uses

In the MU-2 Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- | | | |
|--|---|---|
| <p>(1) Residential</p> <ul style="list-style-type: none">(a) <i>Single residential dwelling</i>(b) <i>Duplex dwelling</i>(c) <i>Multi residential dwelling</i>(d) <i>Boarding</i>(e) <i>Home occupation</i> | <p>(2) Commercial</p> <ul style="list-style-type: none">(a) <i>Accessory buildings</i>(b) <i>Ambulance service</i>(c) <i>Bakery and deli</i>(d) <i>Barber shop and beauty salon</i>(e) <i>Day care</i>(f) <i>Facility for adults with a disability</i>(g) <i>Funeral home</i>(h) <i>Fitness facility</i>(i) <i>Hotel and motel</i>(j) <i>Laundromat and drycleaner</i>(k) <i>Licensed premise</i>(l) <i>Medical clinic</i>(m) <i>Micro-brewing limited to 400 m² and including the accessory retail sale of goods produced on site</i>(n) <i>Nightclub</i>(o) <i>Office</i>(p) <i>Parking lot, school and studio</i>(q) <i>Restaurant</i>(r) <i>Retail stores limited to 375 m²</i>(s) <i>Theatre</i>(t) <i>Veterinary clinic</i> | <p>(3) Combined Commercial Residential Uses</p> <p>Residential units contained within a dual - use <i>building</i> shall be located above <i>storeys</i> used for commercial purposes and no <i>storey</i> can be used for both commercial and residential purposes. The zone regulations set out for the MU-2 Zone pertaining to multi residential dwellings will apply to a combined commercial-residential use.</p> |
|--|---|---|
- (u) Notwithstanding the above a bed and breakfast accommodation is permitted as a commercial use subject to the following conditions:
- (i) Not more than two bedrooms are used for transient accommodation.
 - (ii) Principle use of the *building* shall be *single residential*.
 - (iii) That a resident of the dwelling shall be alone engaged in the operation of the transient accommodation business.
 - (iv) No meals shall be provided to the customers of the operation other than breakfast.

- (v) Notwithstanding the above a *Liquor store* is permitted only on the following properties:
 - (i) Lot A, Plan VIP68799 (1590 Cliffe Avenue)
 - (ii) Lot A, Plan VIS4836 (1001 Ryan Road)

8.14.2 Minimum Lot Size

A *lot* shall have an area of not less than 850 m².

8.14.3 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 20.0 m.

8.14.4 Lot Coverage

A *lot* shall not be covered by buildings and *accessory* buildings to a greater extent than 40% of the total area of the *lot*.

8.14.5 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:


- (1) *Front yard:* 7.5 m
- (2) *Rear yard:* 7.5 m
- (3) *Side yard:* 4.5 m except where the *side yard* flanks a *street* in which case 7.5 m
- (4) *Side yard* adjacent to Comox Logging Right of Way Walkway:
 - 6.0 m
 - 7.5 m for 2nd storey
 - 9.0 m for 3rd storey

And further, where the back of a *building* is adjacent to or faces a *side lot line* the minimum *side yard setback* shall be 6.0 m

8.14.6 Height of Building

Maximum *height* of *building* shall not exceed 10.0 m in *height*.

Notwithstanding any provision of this bylaw, for the property shown in bold outline on Figure 7 the maximum height of a building shall be 14 metres (not to exceed a maximum of 4 storeys).



8.14.7 Useable Open Space

Useable open space shall be provided on a *lot* in the amount of:

- (1) 20.0 m² per *dwelling unit* within an *apartment building*; or
- (2) 30.0 m² per one-bedroom *dwelling unit* and 50.0 m² per *dwelling unit* with two or more bedroom.

8.14.8 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a *floor area* not exceeding 50.0 m² or 10% of the *rear yard*, whichever is greater
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall not be permitted at the front of a *principal building*
- (5) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.14.9 Off-Street Parking and Loading

Off-*street* parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.14.10 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where a *lot* adjoins a residential or institutional use or adjoins 17th *Street*, 29th *Street*, Cliffe Avenue, Cumberland Road, Island Highway, Lerwick Road, Mission Road or Ryan Road a landscaped area of at least 7.5 m in width extending along the entire frontage of the property shall be provided inside the property line. Where a *lot* in this zone adjoins any other *street*, a landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.
- (2) To separate parking, internal roads, services or storage areas from adjacent properties, a landscaped buffer area of at least 2.0 m in width and 2.0 m in *height* shall be provided along the inside of all property lines.
- (3) Loading areas, garbage and recycling containers shall be screened and gated to a minimum *height* of 2 m by a *landscaping* screen or solid decorative *fence* or a combination thereof.

Part 10 - Multiple Use Three Zone (MU-3)

8.15.1 Permitted Uses

In the MU-3 zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- | | | |
|---|---|---|
| (1) Residential | (2) Commercial | (3) Combined Commercial Residential Uses |
| (a) <i>Single residential dwelling</i> | (a) <i>Accessory buildings and uses</i> | Residential units contained within a dual-use <i>building</i> shall be located above <i>storeys</i> used for commercial purposes and no <i>storey</i> can be used for both commercial and residential purposes. |
| (b) <i>Duplex dwellings</i> | (b) <i>Bakery and Deli</i> | |
| (c) <i>Multi residential dwellings</i> | (c) <i>Care facility</i> | |
| (d) <i>Accessory buildings and structures</i> | (d) <i>Community service</i> | |
| (e) <i>Boarding</i> | (e) <i>Day care</i> | |
| (f) <i>Home occupation</i> | (f) <i>Facility for adults with a disability</i> | |
| | (g) <i>Fitness facility</i> | |
| | (h) <i>Financial institution</i> | |
| | (i) <i>Laundromat</i> | |
| | (j) <i>Medical clinic</i> | |
| | (k) <i>Micro-brewing limited to 400 m² and including the accessory retail sale of goods produced on site</i> | |
| | (l) <i>Office</i> | |
| | (m) <i>Personal Service</i> | |
| | (n) <i>Printing and Publishing</i> | |
| | (o) <i>Restaurant</i> | |
| | (p) <i>Retail store</i> | |
| | (q) <i>Second hand store</i> | |
| | (r) <i>School and studio</i> | |
| | (s) <i>Small item sales, service, repair and rental</i> | |
| | (t) <i>Veterinary clinic</i> | |

The sale of drug paraphernalia is expressly prohibited in this zone.

8.15.2 Minimum Lot Size

A *lot* shall have an area of not less than 650 m² except for multi residential dwellings wherein the minimum *lot* size shall be not less than 1,250 m².

8.15.3 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 20.0 m.

8.15.4 Density

The maximum density shall not exceed a *floor area ratio* of 0.6. However, where parking is provided within the principle *building* the *floor area ratio* can be increased by 0.2 multiplied by the percentage of the total *parking spaces* which are provided within the principle *building*.

8.15.5 Lot Coverage

A *lot* shall not be covered by buildings and *accessory* buildings to a greater extent than 40% of the total area of the *lot*.

8.15.6 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front yard:* 7.5 m
- (2) *Rear yard:* 7.5 m
- (3) *Side yard:* 7.5 m
9.0 m for 3rd storey

8.15.7 Height of Buildings

The *height* of a *building* shall not exceed 9.5 m.

8.15.8 Useable Open Space

Usable open space shall be provided on a *lot* in the amount of :

- (1) 20.0 m² per *dwelling unit* within an *apartment building*; or
- (2) 30.0 m² per one bedroom *dwelling unit* and 50.0 m² per *dwelling unit* with two or more bedroom.

8.15.9 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a *floor area* not exceeding 50.0 m² or 10% of the *rear yard*, whichever is greater, except where the *structure* is used to cover parking, in which case, the *floor area* shall not exceed 20% of the *rear yard*, and shall not extend for more than 2/3 of the length of any property line or 30.0 m, whichever is less
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall not be permitted at the front of a principal *residence*
- (5) Shall not be located within 4.5 m from the side and rear *lot line*
- (6) Shall not be situated closer than 3.0 m from the *principal building* which the *accessory building* serves

8.15.10 Off-Street Parking and Loading

Off-*street* parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.15.11 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where a *lot* adjoins a residential or institutional use or adjoins 17th *Street*, 29th *Street*, Cliffe Avenue, Cumberland Road, Island Highway, Lerwick Road, Mission Road or Ryan Road a landscaped area of at least 7.5 m in width extending along the entire frontage of the property shall be provided inside the property line. Where a *lot* in this zone adjoins any other *street*, a landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.
- (2) To separate parking, internal roads, services or storage areas from adjacent properties, a landscaped buffer area of at least 2.0 m in width and 2.0 m in *height* shall be provided along the inside of all property lines.
- (3) Loading areas, garbage and recycling containers shall be screened and gated to a minimum *height* of 2 m by a *landscaping* screen or solid decorative *fence* or a combination thereof.

8.15.12 Special Regulations

- (1) Garbage containers and passive recycling containers shall not be located within any required *setback* adjacent any residential *lot*.
- (2) The outdoor storage or display of any goods, materials or supplies is specifically prohibited, notwithstanding any other provision in this Part.
- (3) A *Day care* shall be located on the *lot* such that these centres have direct access to an open space and play area within the *lot*.

Part 11 - Multiple Use Four Zone (MU-4)

8.16.1 Permitted Uses

In the MU-4 zone, the following uses are permitted and all other uses are prohibited, except as otherwise noted in this bylaw:

- | | | |
|--|---|---|
| <p>(1) Residential</p> <ul style="list-style-type: none">(a) <i>Single residential dwelling</i>(b) <i>Duplex dwelling</i>(c) <i>Multi residential dwelling</i>(d) <i>Accessory buildings and structures</i>(e) <i>Home occupation</i> | <p>(2) Commercial</p> <ul style="list-style-type: none">(a) <i>Bakery and deli</i>(b) <i>Care facility</i>(c) <i>Community services</i>(d) <i>Craft industry with wholesale and accessory retail sales</i>(e) <i>Day care</i>(f) <i>Electrical and plumbing sales and service</i>(g) <i>Enclosed storage facilities</i>(h) <i>Fitness facility</i>(i) <i>Florist</i>(j) <i>Manufacturing</i>(k) <i>Office</i>(l) <i>Laundromat and dry cleaning</i>(m) <i>Medical clinic</i>(n) <i>Micro-brewing limited to 400 m² and including the accessory retail sale of goods produced on site</i>(o) <i>Parking lot</i>(p) <i>Personal Service</i>(q) <i>Printers and publishers</i>(r) <i>Utility facility</i>(s) <i>Restaurant</i>(t) <i>Retail stores limited to 275 m²</i>(u) <i>Small item sales, service, rental and repair</i>(v) <i>School and studio</i>(w) <i>Veterinary clinic</i> | <p>(3) Combined Commercial Residential Uses</p> <p>Residential units contained within a dual-use <i>building</i> shall be located above <i>storeys</i> used for commercial purposes and no <i>storey</i> can be used for both commercial and residential purposes.</p> |
|--|---|---|

2513

8.16.2 Minimum Lot Size

A *lot* shall have an area of not less than 1250 m².

8.16.3 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 20.0 m.

8.16.4 Floor area ratio

Providing all other applicable size, shape and siting conditions are met, the maximum *floor area ratio* shall not exceed 0.6.

8.16.5 Lot Coverage

A *lot* shall not be covered by buildings and *accessory* buildings to a greater extent than 40% of the total area of the *lot*.

8.16.6 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front yard:* 7.5 m
- (2) *Rear yard:* 7.5 m
- (3) *Side yard:* 3.0 m

And further, where the back of a *building* is adjacent to or faces a side *lot line* the minimum *side yard setback* shall be 6.0 m

8.16.7 Height of Buildings

The *height* of a *building* shall not exceed 9.5 m.

8.16.8 Useable Open Space

Useable open space shall be provided on a *lot* in the amount of:

- (1) 20.0 m² per *dwelling unit* within an *apartment building*; or
- (2) 30.0 m² per one-bedroom *dwelling unit* and 50.0 m² per *dwelling unit* with two or more bedroom.

8.16.9 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a *floor area* not exceeding 50.0 m² or 10% of the *rear yard*, whichever is greater, except where the *structure* is used to covered parking, in which case, the *floor area* shall not exceed 20% of the applicable *yard*, and shall not extend for more than 2/3 of the length of any property line or 30.0 m, whichever is less
- (3) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m
- (4) Shall not be situated closer than 3.0 m from the *principal building* that the *accessory building* serves

8.16.10 Off-Street Parking and Loading

Off-*street* parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.16.11 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where a *lot* adjoins a residential or institutional use or adjoins 17th *Street*, 29th *Street*, Cliffe Avenue, Cumberland Road, Island Highway, Lerwick Road, Mission Road or Ryan Road a landscaped area of at least 7.5 m in width extending along the entire frontage of the property shall be provided inside the property line. Where a *lot* in this zone adjoins any other *street*, a landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.
- (2) To separate parking, internal roads, services or storage areas from adjacent properties, a landscaped buffer area of at least 2.0 m in width and 2.0 m in *height* shall be provided along the inside of all property lines.
- (3) Loading areas, garbage and recycling containers shall be screened and gated to a minimum *height* of 2 m by a *landscaping* screen or solid decorative *fence* or a combination thereof.

8.16.12 Special Regulations

- (1) Garbage containers and passive recycling containers shall not be located within any required *setback* adjacent any residential *lot*.
- (2) The outdoor storage or display of any goods, materials or supplies is specifically prohibited, notwithstanding any other provision in this Part.
- (3) *Day care* shall be located on the *lot* such that these centres have direct access to an open space and play area within the *lot*.

Part 12 - Multiple Use Five Zone (MU-5)

8.17.1 Permitted Uses

In the MU-5 zone, the following uses are permitted and all other uses are prohibited, except as otherwise noted in this bylaw:

- | (2) Residential | (2) Commercial | (3) Industrial |
|--|---|--|
| (a) <i>Accessory residential dwelling or caretaker's suite, meaning a dwelling unit:</i> | (a) <i>Accessory buildings and uses</i> | (a) <i>Accessory buildings and uses</i> |
| a. having a total floor space of not more than 90m ² in area; | (b) <i>Bakery and deli</i> | (b) <i>Commercial Laundry</i> |
| b. located within a principal building of commercial or industrial occupancy; | (c) <i>Car washing establishment</i> | (c) <i>Enclosed storage facilities including warehousing</i> |
| c. a maximum of 1 <i>accessory dwelling unit</i> is permitted per parcel. | (d) <i>Community services</i> | (d) <i>Manufacturing</i> |
| (b) <i>Home occupation</i> | (e) <i>Craft industry with wholesale and accessory retail sales</i> | (e) <i>Micro-brewing including the accessory retail sale of goods produced on site</i> |
| | (f) <i>Fitness facility</i> | (f) <i>Printers and publishers</i> |
| | (g) <i>Florist or Garden Store</i> | (g) <i>Transportation depot</i> |
| | (h) <i>General Service</i> | (h) <i>Utility Facility</i> |
| | (i) <i>Laundromat and dry cleaning</i> | (i) <i>Small item sales, service, rental and repair</i> |
| | (j) <i>Licensed Premises</i> | (j) <i>Wholesaling</i> |
| | (k) <i>Medical clinic</i> | |
| | (l) <i>Office</i> | |
| | (m) <i>Outdoor sales</i> | |
| | (n) <i>Personal Service</i> | |
| | (o) <i>Restaurant</i> | |
| | (p) <i>Retail stores limited to 275 m²</i> | |
| | (q) <i>School</i> | |
| | (r) <i>Service and repairs</i> | |
| | (s) <i>Service Station</i> | |
| | (t) <i>Studio</i> | |
| | (q) <i>Veterinary clinic</i> | |

8.17.2 Minimum Lot Size

For the purpose of subdivision, a *lot* shall have an area of not less than 2900 m².

8.17.3 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 30.0 m.

8.17.4 Floor area ratio

Providing all other applicable size, shape and siting conditions are met, the maximum *floor area ratio* shall not exceed 0.6.

8.17.5 Lot Coverage

A *lot* shall not be covered by buildings and *accessory* buildings to a greater extent than 40% of the total area of the *lot*.

8.17.6 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front yard:* 7.5 m
- (2) *Rear yard:* 7.5 m
- (3) *Side yard:* 6.0 m

8.17.7 Height of Buildings

The *height* of a *building* shall not exceed two stories or 9.5 m.

8.17.8 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a *floor area* not exceeding 50.0 m² or 10% of the *rear yard*, whichever is greater, except where the *structure* is used to covered parking, in which case, the *floor area* shall not exceed 20% of the applicable *yard*, and shall not extend for more than 2/3 of the length of any property line or 30.0 m, whichever is less
- (3) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m
- (4) Shall not be situated closer than 3.0 m from the *principal building* that the *accessory building* serves

8.17.9 Off-Street Parking and Loading

Off-*street* parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.17.10 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where a *lot* adjoins a residential or institutional use or adjoins 17th *Street*, 29th *Street*, Cliffe Avenue, Cumberland Road, Island Highway, Lerwick Road, Mission Road or Ryan Road a landscaped area of at least 7.5 m in width extending along the entire frontage of the property shall be provided inside the property line. Where a *lot* in this zone adjoins any other *street*, a landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.
- (2) To separate parking, internal roads, services or storage areas from adjacent properties, a landscaped buffer area of at least 2.0 m in width and 2.0 m in *height* shall be provided along the inside of all property lines.
- (3) Loading areas, garbage and recycling containers shall be screened and gated to a minimum *height* of 2 m by a *landscaping* screen or solid decorative *fence* or a combination thereof.

8.17.11 Special Regulations

- (1) Garbage containers and passive recycling containers shall not be located within any required *setback* adjacent any residential *lot*.
- (2) The outdoor storage of any goods, materials or supplies is to be setback from any property line adjacent to a *street*.
- (3) *Day care* shall be located on the *lot* such that these centres have direct access to an open space and play area within the *lot*.

Part 13 - Commercial One Zone (C-1)

8.18.1 Permitted Uses

In the C-1 zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- 2803 (1) *Accessory buildings and structures*
- (2) *Assembly hall*
- (3) *Bakery and deli*
- (4) *Barber shop and beauty salon*
- 2803 (5) *Care facility*
- 2803 (6) *Carriage house*
- (7) *Church, including one (1) dwelling unit for each lot*
- (8) *Community service*
- 2803 (9) *Cultural facility*
- (10) *Day care*
- 2803 (11) *Duplex dwelling*
- (12) *Facility for adults with a disability*
- 2803 (13) *Farmer's Market*
- (14) *Fitness facility*
- (15) *Funeral home*
- (16) *General service*
- 2803 (17) *Granny flat*
- (18) *Grocery store and shopping centre*
- (19) *Hotel*
- (20) *Indoor entertainment facility*
- (21) *Laundromat and dry cleaning*
- (22) *Licensed premises*
- (23) *Liquor store*
- (24) *Meat and fish market*
- (25) *Medical clinic*
- (26) *Micro-brewing, distilling and U-brew/U-Vin limited to 400 m² and including accessory sales*
- 2803 (27) *Multi residential dwellings*
- 2501 (28) *Nightclub, provided that in this C-1 Zone live entertainment, shows and exhibitions are excluded unless the performers are clothed in opaque garments covering breast, buttocks and genitalia*
- (29) *Office, financial institution, and personal service*
- (30) *Parking lot*
- (31) *Printing shop*
- (32) *Restaurant*
- (33) *Retail stores*
- (34) *Second-hand store, within an enclosed building*
- 2803 (35) *Secondary Suite*
- (36) *School*
- 2803 (37) *Single residential dwelling*
- (38) *Small item sales, service, rental and repair*
- (39) *Studio*
- (40) *Theatre*

- 2803 (41) *Transportation depot*
- 2803 (42) Combined commercial/residential uses are permitted within the same building or in separate buildings on the same property
- (43) Notwithstanding any provision of this bylaw, an enclosed storage facility is allowed on Lot 7, Section 61, Comox District, Plan 311, except the easterly 18 feet (120 – 5th Street).
- 2949 (44) Notwithstanding any provision of this bylaw, a storefront cannabis retailer is a permitted use on Lot 63, Section 61, Comox District, Plan 311 (143 5th Street).
- 2950 (45) Notwithstanding any provision of this bylaw, a storefront cannabis retailer is a permitted use on Lots 1 and 2 both of Block 3, Section 61, Comox District, Plan 2068 (605/625 Cliffe Avenue).
- 2958 (46) Notwithstanding any provision of this bylaw, a storefront cannabis retailer is a permitted use on That Part of Lot 92, Section 61, Comox District, Plan 311 Lying to the South East of the South Easterly Boundary of Plan 1621-R (Unit #101-576 England Avenue)

8.18.2 Minimum Lot Size

A *lot* shall have an area of not less than 500 m².

8.18.3 Minimum Lot Frontage

N/A

8.18.4 Lot Coverage

N/A

8.18.5 Minimum Floor area

N/A

8.18.6 Setbacks

- 2803 Except where otherwise specified in this Bylaw there are no setback requirements in the C-1 Zone.

8.18.7 Height of Buildings

No *building* in this zone shall exceed 13.5 m.

- 2803 **8.18.8 Off-Street Parking and Loading**

Notwithstanding any other provision of this bylaw, parking and loading spaces as a requirement under Division 7, shall be deemed not to apply to properties zoned Commercial One (C-1) except that one parking space is required for each residential unit.

8.18.9 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where a *lot* adjoins a residential or institutional use a landscaped area of at least 3.0 m in width extending along the entire frontage of the property shall be provided inside the property line
- (2) Where a *lot* adjoins 17th *Street*, Anderton Avenue, Cumberland Road, Fitzgerald Avenue or Cliffe Avenue south of 8th *Street* a landscaped area of at least 4.5 m in width extending along the entire frontage of the property shall be provided inside the property line.
- (3) Loading areas, garbage and recycling containers, utilities, service kiosks, meters, elevator housing, exhaust elements, satellite dishes, etc. shall be screened to a minimum *height* of 2.0 m by a *landscaping* screen or solid decorative *fence* or a combination thereof.
- (4) To separate parking, internal roads, service or storage areas, a landscaped area of at least 2.0 m in width and 2.0 m in *height* shall be provided along the inside of all affected property lines.

Part 13 - Commercial One A (C-1A)

8.18.10 Permitted Uses

In the C-1A zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this Bylaw:

- (1) *Accessory buildings*
- (2) *Building supply store*
- (3) *Garden store*
- 2633 (4) *Liquor store* permitted only on the following property:
Lot A, Section 66 & 67, Comox District, Plan 44811 Except Parts in Plans 49234, VIP66865, and VIP68598 (the Driftwood Mall)
- (5) *Service station*
- (6) *Shopping centre* including *retail store, personal service, medical clinic, restaurant, office, fitness facility, studio* and school.
- (7) *Theatre*
- 2944 (8) Notwithstanding any provision of this bylaw, a *storefront cannabis retailer* is a permitted use on Lot A, Section 66 & 67, Comox District, Plan 44811 Except Parts in Plans 49234, VIP66865 and VIP68598 (Unit #1400- 2701 Cliffe Avenue)
- 2946 (9) Notwithstanding any provision of this bylaw, a *storefront cannabis retailer* is a permitted use on Lot 2, Section 14, Comox District, Plan VIP53727 (#105-789 Ryan Road)

8.18.11 Conditions of Use

- (1) The operation of a *garden store* may be permitted outdoors provided that such outdoor area shall not exceed the net *floor area* of the *retail garden centre* operated within a *building*.

8.18.12 Minimum Lot Size

A *lot* shall have an area of not less than 2.0 ha.

8.18.13 Minimum Lot Frontage

N/A

8.18.14 Lot coverage

A *lot* shall not be covered by buildings and *accessory buildings* to a greater extent than 40% of the total area of the *lot*.

8.18.15 Setbacks

Except where otherwise specified in this bylaw, the following *setback* requirements shall apply:

- (1) *Front yard:* 15.0 m
- (2) *Rear yard:* 15.0 m
- (3) *Side yard:* 15.0 m

8.18.16 Height of Buildings

The *height* of a *building* shall not exceed 9.5 m.

8.18.17 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) A landscaped area of 7.5 m is required inside all property lines. Where a *building* greater than 4,500 m² this landscape area shall be increased to 15.0 m.
- (2) Where any use of a *lot* in this zone adjoins a *street* a landscaped area of at least 10.0 m in width extending the entire frontage of the property shall be provided along the inside of all affected property lines.
- (3) Loading areas and garbage and recycling containers shall be screened to a minimum *height* of 2.0 m by a *landscaping* screen or solid decorative *fence* or a combination thereof.
- (4) *Parking lots* shall include, at regular intervals, curbed planters containing trees and shrubs.

8.18.18 Off-Street Parking and Loading

Off-*street* parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw except that all required parking for uses within this zone must be on the same *lot* as the *principal use* and buildings and the area used for parking must be zoned C-1A

Part 14 - Commercial Two Zone (C-2)

8.19.1 Permitted Uses

In the C-2 zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) *Accessory building* and uses
- (2) *Assembly hall*
- (3) Bakery and deli
- (4) Barber shop and beauty salon
- (5) Bed and breakfast accommodation, subject to the following conditions:
 - (a) Not more than two bedrooms are used for transient accommodation;
 - (b) Principle use of the *building* shall be *single residential*;
 - (c) That a resident of the dwelling shall be alone engaged in the operation of the transient accommodation business
 - (d) No meals shall be provided to the customers of the operation other than breakfast
 - (e) At least one automobile *parking space* shall be provided on the same *lot* for each room available for transient accommodation, in addition to the parking requirements for the *residence*, but *parking spaces* may be behind other *parking spaces* on the same *lot*
- (6) *Building supply store*
- (7) Car washing establishment
- (8) *Day care*
- (9) Enclosed storage *building*, including warehouse, and *storage yard*
- (10) *Facility for adults with a disability*
- (11) *Fitness facility*
- (12) *General service*
- (13) *Grocery store*
- (14) *Hotel and motel*
- (15) *Indoor entertainment facility*
- (16) *Laundromat and dry cleaning*
- (17) *Licensed premises*
- (18) *Liquor store* permitted only on the following properties:
 - Lot B, Plan 28292 (2355 Mansfield Drive)
 - Lot 2, Section 41, Comox District, Plan VIP75100 (1599 Cliffe Avenue)
- (19) *Nursery and greenhouse*
- (20) *Medical clinic*
- (21) Micro-brewing limited to 400 m² and including *accessory retail* sale of goods produced on site
- (22) *Office and financial institution*
- (23) *Outdoor sales*
- (24) *Parking lot*
- (25) Printing and publishing

- (26) Restaurant
 - (27) *Retail* and wholesale stores
 - (28) School
 - (29) Second hand stores, within an enclosed *building*
 - (30) *Service and repairs*
 - (31) *Service station*
 - (32) *Small item sales, service, rental and repair*
 - (33) *Studio*
 - (34) *Transportation depot* and *taxi office*
 - (35) *Veterinary clinic*
- 2618 (36) Combined commercial-residential use subject to the commercial use being restricted to *retail*, restaurants, offices (including *financial institutions*) and studios. Residential units must be contained within a dual use *building* and shall be located above *storeys* used for commercial purposes, and no *storey* can be used for both commercial and residential purposes
- 2703 (37) Notwithstanding any provisions of this bylaw, an *auction centre* with a maximum *floor area* of 185 m² is permitted on Lot 2, District Lot 96, Comox District, Plan VIP53672 (1755 13th Street).
- (38) Notwithstanding any provisions of this bylaw, the following and no other is permitted on Lot K, Plan DD29186-N (4846 Headquarters Road) and Plan 870R (4860 Headquarters Road):
- (a) Mini storage
 - (b) *Single residential dwelling*
- Conditions of use:
- (a) No parking, loading or storage areas shall be located within 1.5 m of any property line
 - (b) All warehousing and storage shall be contained entirely within an enclosed *building*
- (39) Notwithstanding any provisions of this bylaw, furniture refinishing and *accessory uses* , and no other use, is permitted on Parcel A (DD 379448-I) of Lot 1, Section 18, Comox District, Plan 5466 (4785 Headquarters Road) subject to the following condition:
- (a) Sales of furniture refinished within the *building* on the subject property utilizing a *building area* of up to 25% of the permitted total *building area*.
 - (b) The display and catalogue sales of kitchen cabinets built and shipped from off-site utilizing no more than 25% of the permitted total *building area*.
- Condition of use:
- (c) No parking, loading or storage areas shall be located within 3.5 m to any property line.
 - (d) No outdoor storage or supply *yards* shall be permitted.
- (40) Notwithstanding any provisions of this bylaw, the following and no other is permitted on Lot A, Section 20, Plan VIP55701 (2855 Wentworth Road):
- (a) *Garden store* and *accessory* outdoor storage
 - (b) Agricultural use
 - (c) Residential use limited to one dwelling

Conditions of use:

- (a) No areas used for outdoor storage, display, parking or loading shall be located within 3.5 m of any *lot line*.
- (b) A landscaped buffer to a minimum depth of 3.5 m with natural vegetation consisting of a dense combination of shrubs, evergreen trees and plants to create a solid screen not less than 1.8 m in *height* where:
 - i. the adjacent or abutting *lot* is zoned Rural, Residential, or Rural Residential zone
 - ii. a *lot line* abuts a public road right-of-way
- (c) No *building* or *structure* shall be located within:
 - i. 7.5 m of that portion of a front *lot line*
 - ii. 3.5 m of a side *lot line* that does not abut a public road right-of-way
 - iii. 7.5 m of a rear *lot line*
- (d) The maximum permitted coverage of all buildings and structures shall not exceed 50% of the *site area*, excluding greenhouses used in garden nurseries or for agricultural uses.
- (e) Minimum *lot size* – 1.0 ha
- (f) Minimum *lot frontage* – 10% of the perimeter of the *lot*

2816

- (41) Notwithstanding the above, *Pet Day Care* is permitted on Strata Property VIS687 (241 Puntledge Road).

2957

- (42) Notwithstanding any provision of this bylaw, a storefront cannabis retailer is a permitted use on Lot A, Section 66, Comox District, Plan 34998, Except that Part in Plan 49713 (#103-2270 Cliffe Avenue).

8.19.2 Conditions of Use

All business, repair or servicing uses shall be conducted within a completely enclosed *building* except for permitted outdoor display, rental, sales or *storage yards*, parking and loading facilities and gasoline *service stations*.

8.19.3 Minimum Lot Size

A *lot* shall have an area of not less than 650 m² except for a combined commercial-residential use of a *lot*, in which case, an area of 1,250 m² is required.

8.19.4 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 20.0 m.

8.19.5 Floor Area Ratio and Lot Coverage

Provided all other applicable size, shape and siting conditions are met, the maximum *floor area ratio* and *lot coverage* shall not exceed in the case of:

- (1) Commercial use - lots shall not be covered by buildings and *accessory* buildings to a greater extent than fifty percent (50%) of total area of the *lot*.
- (2) Combined commercial/residential use - .60 *floor area ratio*.
- (3) A *building* used for *retail* use is limited to 4,500 m² per floor except for a *retail building supply store*.

8.19.6 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front yard:* 7.5 m
- (2) *Rear yard:* 4.5 m except where a *lot* adjoins a residential zone without the intervention of a *street* or lane, in which case, the minimum shall be:
 - (i) 6.0 m in the case of a *one-storey building*
 - (i) 7.5 m in the case of buildings exceeding *one-storey*.
- (3) *Side yard* No *side yard* shall be required except where a *lot* in this zone adjoins a residential zone without the intervention of a *street* or lane, in which case, a *side yard* shall be provided or not less than:
 - (i) 4.5 m in the case of a *one-storey building*
 - (ii) 6.0 m in the case of buildings exceeding *one-storey*
 - (iii) in the case of a combined commercial-residential use, *side yards* of 4.5 m are to be provided

Notwithstanding the above:

- (1) In case of a *Service station*, the following applies
 - (a) *buildings* and *accessory buildings* shall be at least 12.0 m from property lines.

8.19.7 Height of Buildings

No *building* in this zone shall exceed 9.5 m except for a combined commercial-residential *building*, in which case, the *height* of a *building* shall not exceed 13.5 m.

8.19.8 Useable Open Space

Useable open space shall be provided on a *lot* in the amount of 20.0 m² per *dwelling unit*.

8.19.9 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a *floor area* not exceeding 50.0 m² or 10% of the *rear yard*, whichever is greater
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall not be permitted at the front of a *principal building*
- (5) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m
- (6) Shall not be situated closer than 3.0 m from the *principal building* which the *accessory building* serves

8.19.10 Off-Street Parking and Loading

Off-*street* parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.19.11 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where a *lot* adjoins a residential or institutional use or adjoins 17th *Street*, 29th *Street*, Cliffe Avenue, Cumberland Road, Island Highway, Lerwick Road, Mission Road or Ryan Road a landscaped area of at least 7.5 m in width extending along the entire frontage of the property shall be provided inside the property line. Where a *lot* in this zone adjoins any other *street*, a landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.
- (2) To separate parking, internal roads, services or storage areas from adjacent properties, a landscaped buffer area of at least 2.0 m in width and 2.0 m in *height* shall be provided along the inside of all property lines.
- (3) Loading areas, garbage and recycling containers shall be screened and gated to a minimum *height* of 2 m by a *landscaping* screen or solid decorative *fence* or a combination thereof.

Part 14 - Commercial Two A Zone (C-2A)

8.19.12 Permitted Uses

In the C-2A zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in the bylaw:

- (1) *Assembly hall*
- (2) *Community service*
- (3) *Convenience store*
- (4) *Day care*
- (5) *General service*
- (6) *Grocery store*
- (7) *Government offices and facilities*
- (8) *Hotel and Motel*
- (9) *Indoor entertainment facility*
- (10) *Licensed premises*
- (11) *Medical clinic*
- (12) *Micro-brewing limited to 400 m² and including accessory retail sale of goods produced on site*
- (13) *Office and financial institution*
- (14) *Parking lot*
- (15) *Personal service*
- (16) *Restaurant*
- (17) *Retail stores*
- (18) *School*
- (19) *Shopping centre*
- (20) *Veterinary clinic*
- (21) Notwithstanding any provision of this bylaw, a *recycling facility* is permitted on Lot 3, Section 14, Plan 21329 (493 Puntledge Road)

2586

8.19.13 Minimum Lot Size

A *lot* shall have an area of not less than 2500 m².

8.19.14 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 20.0 m.

8.19.15 Density

The maximum density shall not exceed a *floor area ratio* of 0.6. However, where parking is provided within the principle *building* the floor space area ratio can be increased by 0.2 multiplied by the percentage of the total *parking spaces* which are provided in the *principal building*.

8.19.16 Lot Coverage

A *building* used for *retail* use is limited to 4,500 m² per floor except for a *retail building supply store*.

8.19.17 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front yard*: 7.5 m except where the area between a *building* and a *front lot line* is landscaped and not used for off-*street* parking, the *setback* may be reduced to 4.5 m
- (2) *Rear yard*: 4.5 m - one *storey*
7.5 m - two *storeys*
- (3) *Side yard*: No *side yard* shall be required except where a *lot* adjoins a residential zone in which case the following applies:
 - (i) 4.5 m - one *storey*
 - (ii) 7.5 m - two *storeys*

And further, where the *side yard* flanks a *street* a minimum *setback* of 4.5 m is required.

8.19.18 Height of Buildings

No *building* in this zone shall exceed 9.14 m.

8.19.19 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a *floor area* not exceeding 46.45 m²
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall not be permitted at the front of a *principal building*
- (5) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.19.20 Off-Street Parking and Loading

Off-*street* parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.19.21 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where a *lot* adjoins a residential or institutional use or adjoins 17th *Street*, 29th *Street*, Cliffe Avenue, Cumberland Road, Island Highway, Lerwick Road, Mission Road or Ryan Road a landscaped area of at least 7.5 m in width extending along the entire frontage of the property shall be provided inside the property line. Where a *lot* in this zone adjoins any other *street*, a landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.
- (2) To separate parking, internal roads, services or storage areas from adjacent properties, a landscaped buffer area of at least 2.0 m in width and 2.0 m in *height* shall be provided along the inside of all property lines.
- (3) Loading areas, garbage and recycling containers shall be screened and gated to a minimum *height* of 2 m by a *landscaping* screen or solid decorative *fence* or a combination thereof

Part 15 - Commercial Three Zone (C-3)

8.20.1 Permitted Uses

In the C-3 zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) *Accessory buildings*
- (2) *Grocery store*
- (3) *One dwelling unit* in conjunction with the above use

8.20.2 Minimum Lot Size

A *lot* shall have an area of not less than 1250 m².

8.20.3 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 20.0 m.

8.20.4 Lot Coverage

Provided that acceptable facilities for parking, loading, and *yard* requirements are provided in accordance with this bylaw, a *lot* may be covered by buildings and *accessory buildings* up to 45% of the total area of the *lot*, but in no event, shall the buildings and *accessory buildings* cover more than 375 m² of the *lot*.

8.20.5 Setbacks

Except where otherwise specified in this Bylaw, the following *setback* requirements shall apply:

- (1) *Front yard:* 7.5 m
- (2) *Rear yard:* 7.5 m
- (3) *Side yard:*
 - (i) 3.0 m for a one-storey *building* except when the *side yard* flanks a *street*, in which case, the minimum distance shall be 4.5 m.
 - (ii) 6.0 m for two-storey *building*.

8.20.6 Height of Building

No *building* shall exceed 4.5 m in *height* except where a *dwelling unit* is incorporated in the *building* constituting a second *storey*, in which case, the maximum *height* shall not exceed 9 m.

8.20.7 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a *floor area* not exceeding 10% of the *lot area* except where a *building* serves as a parking *structure*, in which case, the *floor area* shall not exceed 20% of the *lot area*
- (3) Shall be permitted in the side and *rear yard* only, provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or

rear yard flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.20.8 Off-Street Parking and Loading

Off-*street* parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.20.9 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where a *lot* adjoins a residential or institutional use or adjoins 17th *Street*, 29th *Street*, Cliffe Avenue, Cumberland Road, Island Highway, Lerwick Road, Mission Road or Ryan Road a landscaped area of at least 7.5 m in width extending along the entire frontage of the property shall be provided inside the property line. Where a *lot* in this zone adjoins any other *street*, a landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.
- (2) To separate parking, internal roads, services or storage areas from adjacent properties, a landscaped buffer area of at least 2.0 m in width and 2.0 m in *height* shall be provided along the inside of all property lines.
- (3) Loading areas, garbage and recycling containers shall be screened and gated to a minimum *height* of 2 m by a *landscaping* screen or solid decorative *fence* or a combination thereof

Part 16 - Commercial Four Zone (C-4)

8.21.1 Permitted Uses

In the C-4 zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) *Accessory buildings and uses*
- (2) *Bingo facility*
- (3) *Community service*
- (4) *Day care*
- (5) *Medical clinic*
- (6) *Office*
- (7) *School*
- (8) *Studio*
- (9) Notwithstanding any provisions of this bylaw, “slot machines” are allowed within the *bingo facility* on Lot A, Section 14, Comox District, VIP83482 (361 Hunt Place).
- (10) Notwithstanding any provisions of this bylaw, *bingo facility* is not a *permitted use* on Lot 1, District Lot 157, Comox District, Plan VIP59557 (2488 Idiens Way).

8.21.2 Minimum Lot Size

A *lot* shall have an area of not less than 1,800 m².

8.21.3 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 20.0 m.

8.21.4 Lot Coverage

A *lot* shall not be covered by buildings and *accessory buildings* to a greater extent than 35% of the total area of the *lot*.

8.21.5 Setbacks

Except where otherwise specified in this bylaw, the following *setback* requirements shall apply:

- (1) *Front yard:* 7.5 m except where a *lot* borders Ryan Road, in which case the minimum shall be 15 m.
- (2) *Rear yard:* 6.0 m except where a *lot* in this zone adjoins a residential zone without the intervention of a *street* or lane, in which case, a *rear yard* of 9.0 m shall be provided.
- (3) *Side yard:* 6.0 m except where a *lot* in this zone adjoins a *street* or lane, in which case, a *side yard* of 7.5 m shall be provided.
- (4) *Watercourse:* 15.0 m for all buildings, structures and *parking lots*.

8.21.6 Height of Buildings

The *height* of a *building* shall not exceed 9.5 m.

8.21.7 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a *floor area* not exceeding 50.0 m² or 10% of the *rear yard*, whichever is greater
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall not be permitted at the front of a *principal building*
- (5) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.21.8 Off-Street Parking and Loading

Off-*street* parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.21.9 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where a *lot* adjoins a residential or institutional use or adjoins 17th *Street*, 29th *Street*, Cliffe Avenue, Cumberland Road, Island Highway, Lerwick Road, or Mission Road landscaped area of at least 7.5 m in width, and in the case of along Ryan Road 15 m in width, extending along the entire frontage of the property shall be provided inside the property line. Where a *lot* in this zone adjoins any other *street*, a landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.
- (2) To separate parking, internal roads, services or storage areas from adjacent properties, a landscaped buffer area of at least 2.0 m in width and 2.0 m in *height* shall be provided along the inside of all property lines.
- (3) Loading areas, garbage and recycling containers shall be screened and gated to a minimum *height* of 2 m by a *landscaping* screen or solid decorative *fence* or a combination thereof

Part 17 - Commercial Five Zone (C-5)

8.22.1 Intent

This zone is intended to provide appropriate zoning for commercial uses in a heritage character neighbourhood.

8.22.2 Permitted Uses

In the C-5 zone, the following uses are permitted and all other uses are prohibited within the area identified on Schedule 8, Zoning Map, except as otherwise noted in this bylaw:

- (1) *Accessory* buildings and uses
- (2) Bed and Breakfast
- (3) *Day care*
- (4) *Home Occupation*
- (5) *Office*
- (6) *Personal Service*
- (7) *Retail* limited to 200 square metres
- (8) School
- (9) *Studio*
- (10) Combined commercial-residential uses provided that residential units are contained within a dual use building, and no storey can be used for both commercial and residential purposes.
- (11) Notwithstanding any provisions of this bylaw, a *Medical Clinic* is a permitted use on Parcel A (DD53537W) of Lot 114 Section 61, Comox District, Plan 472A, Parcel A (DD53537W) of Lot 115, Section 61, Comox District, Plan 472A and Amended Lot 111 (DD 43419N) Section 61, Comox District, Plan 472-A Except That Part Thereof Lying to the South East of a Boundary Parallel to and Perpendicularly Distant 10 Feet from the South Easterly Boundary of Said Lot (308, 320 and 332 3rd Street).

2871

8.22.3 Density

Providing all other conditions are met the maximum *floor area ratio* shall not exceed 0.50.

8.22.4 Lot Coverage

Maximum *lot coverage* shall not exceed 40%.

8.22.5 Minimum Lot Sizes

The minimum lot size is 420 square metres.

8.22.6 Frontages

A *lot* shall have a frontage of not less than 12 metres except for a *corner lot* where the frontage shall be not less than 13.5 metres.

8.22.7 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front yard*: 6.0 m
- (2) *Rear yard*: 6.0 m
- (3) *Side yard*: The *side yard setbacks* shall total 4.5 m with a minimum *side yard setback* on one side of 1.5 m except where a *side yard* flanks a *street* in which case the minimum distance shall be 4.5 m.

8.22.8 Maximum Height

The *height* of a *principal building* shall not exceed 10.0 m.

8.22.9 Accessory Buildings and Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a total *building area* not exceeding 50.0 m² or 10% of the *rear yard*, whichever is greater
- (3) Shall be permitted in the *side* and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.22.10 Off-Street Parking and Driveways

Except as provided in this section, off street parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.22.11 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

Where a *lot* in this zone adjoins a street, a landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the street shall be provided inside the property line.

Loading areas, garbage and recycling containers, utilities, service kiosks, metres, exhaust elements, satellite dishes, etc., shall be screened to a minimum *height* of 2.0 m by a landscape screen or solid decorative *fence* or a combination thereof.

Part 18 - Industrial One Zone (I-1)

8.23.1 Permitted Uses

In the I-1 zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) Saw mill
- (2) Boat works and storage
- (3) Heliport
- (4) *Manufacturing*

8.23.2 Conditions of Use

Uses which are noxious or otherwise undesirable because of smoke, noise, vibration, dirt, glare, odour, or electrical interference, or which are an offensive trade within the meaning of the Health Act shall not be permitted in this zone.

8.23.3 Minimum Lot Size

A *lot* shall have an area of not less than 2500 m².

8.23.4 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 30.0 m.

8.23.5 Lot Coverage

Lots shall not be covered by buildings and *accessory* buildings to a greater extent than sixty percent (60%) of the total area of the *lot*.

8.23.6 Setbacks

Except where otherwise specified in this bylaw, the following *setback* requirements shall apply:

- (1) *Front yard:* 7.5 m
- (2) *Rear yard:* 7.5 m except where a *lot* adjoins a residential zone without the intervention of a *street* or lane in which case the minimum shall be:
 - (i) 20.0 m in the case of a *one-storey building*
 - (ii) 30.0 m in the case of buildings exceeding one *storey*
- (3) *Side yard:* 4.5 m shall be required except where a *lot* in this zone adjoins a residential zone without the intervention of a *street* or lane, in which case a *side yard* shall be provided of not less than:
 - (i) 20.0 m in the case of a *one-storey building*
 - (ii) 30.0 m in the case of buildings exceeding one-*storey*.

Where a *lot* is not served by a rear lane, one *side yard* not obstructed and open to the sky and at least 10.0 m wide shall be provided. In the case of a *corner lot*, the *side yard* adjoining the flanking *street* shall not be less than 7.0 m wide.

8.23.7 Height of Buildings

No *building* shall exceed a *height* of 15.0 m.

8.23.8 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 6.0 m in *height*
- (2) Shall have a *floor area* not exceeding 50.0 m² or 10% of the *rear yard*, whichever is greater
- (3) Shall be permitted in the side and *rear yard*, provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall not be permitted at the front of a *principal building*
- (5) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.23.9 Off-Street Parking and Loading

Off-*street* parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this Bylaw.

8.23.10 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) A landscape area of 4.5 m shall be provided along the inside of all affected property lines. Where a *building* is greater than 4,500 m² a landscape area of 15 m shall be provided along the inside of all affected property lines.
- (2) Where a *lot* adjoins a residential or institutional use or adjoins 29th *Street*, Atlas Road, Anderton Road, Comox Road, Cumberland Road, Lerwick Road, Mission Road or Ryan Road a landscaped area of at least 10.0 m in width extending along the entire frontage of the property shall be provided inside the property line. Where a *lot* in this zone adjoins any other *street*, a landscaped area of at least 7.5 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.
- (3) To separate parking, internal roads, services or storage areas from adjacent properties, a landscaped buffer area of at least 2.0 m in width and 2.0 m in *height* shall be provided along the inside of all property lines.
- (4) Loading areas, garbage and recycling containers shall be screened and gated to a minimum *height* of 2 m by a *landscaping* screen or solid decorative *fence* or a combination thereof.

8.23.11 Living Quarters

Buildings on lots used for Industrial One purposes shall not be used as living quarters except for one employee of the industry whose *residence* on the premises is essential for reason of security of the principal land use concerned.

Part 19 - Industrial Two Zone (I-2)

8.24.1 Permitted Uses

In the I-2 zone, the following uses are permitted and other uses are prohibited except as otherwise noted in this bylaw;

- 2563
- (1) *Accessory* buildings, including up to two unstacked *containers*
 - (2) *Accessory office* to an industrial use
 - (3) Automobile *service and repairs* including automobile storage of wrecked vehicles but excluding automobile wrecking or the use of a property as a wrecking *yard*
 - (4) *Auction centre*
 - (5) *Building supply store*
 - (6) Commercial laundry
 - (7) Contractor's offices and equipment *storage yards*
- 2513
- (8) Enclosed Storage Facility
 - (9) Facility for adults with disabilities
 - (10) *Fitness facility*
 - (11) Heavy equipment sales and leasing
 - (12) *Indoor entertainment facility*
 - (13) *Manufacturing*
 - (14) Micro-brewing limited to 400 m² and including *accessory retail* sale of goods produced on site
 - (15) *Pet Day Care*
 - (16) Printers and publishers
 - (17) Radio station
 - (18) Restaurant
 - (19) *Small item sales, service, rental and repair*
 - (20) School
 - (21) Storage and sale of feed and fertilizer
 - (22) Truck and rail loading terminal
 - (23) *Utility facility*
 - (24) *Veterinary clinic*
 - (25) Two *dwelling units* for each *lot* provided that such dwelling(s) forms an integral part of the *principal building* and that residential units are located above stories used for industrial purposes and no *storey* can be used for both industrial and residential use.
 - (26) Notwithstanding any provisions of this bylaw, boat building, service, repair and *accessory office* is permitted on Lot 1, Section 18, Plan 4289 (4767 North Island Highway)
 - (27) Notwithstanding any provisions of this bylaw, a barber shop is a *permitted use* of Lot 1, D.L. 230, Plan 33435. (2260 Cousins Road).
 - (28) Notwithstanding any provisions of this bylaw, an *office* is a *permitted use* of Lot 23, Section 67, Comox District, Plan 35438. (801 30th Street).
 - (29) Notwithstanding any provisions of this bylaw, a warehouse is a *permitted use* of Lot 1, Plan 34318. (4660 Western Road).

- 2836 (30) Notwithstanding any provisions of this bylaw, a tattoo studio is a *permitted use* of Lot 2, District Lot 127, Comox District, Plan VIP53974. (911 McPhee Avenue).
- 2921 (31) Notwithstanding any provisions of this bylaw, a church and assembly hall is a *permitted use* on Lot A (DD EL132291), District lot 127, Comox District Plan 1464 Except Part In Plan VIP67475 (765 McPhee Avenue).
- 2948 (32) Notwithstanding any provision of this bylaw, “*day care*” and “*family development centre*” are permitted uses on Lot C, Section 41, Comox District, Plan 13660 and the Remainder of Lot 5, Section 41, Comox District, Plan VIP13075 (1625 and 1679 McPhee Avenue)
- 2992 (33) Notwithstanding any provision of this bylaw, “*office*” is a *permitted use* on Strata Lots 1-8, District Lot 230, Comox District, Plan VIS6538 (2459 Cousins Avenue).
- 3066 (34) Not withstanding any provisions of this bylaw, *food bank* is a *permitted use* on Lot 1, Block 15, Section 69, Comox District, Plan EPP123274 (1255 McPhee Avenue).
- 3095 (35) Notwithstanding any provisions of this bylaw, *day care* is a *permitted use* on Unit A, Strata Lot 5, District Lot 236, Comox District, Strata Plan VIS5235 (4655a Madrona Place).

8.24.2 Condition of Use

Uses which are noxious or otherwise undesirable because of smoke, noise, vibration, dirt, glare, odour or electrical interference, or which are an offensive trade within the meaning of the Health Act shall not be permitted in this zone.

8.24.3 Minimum Lot Size

A *lot* shall have an area of not less than 1250 m².

8.24.4 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 20.0 m.

8.24.5 Lot Coverage

Lots shall not be covered by buildings and *accessory* buildings to a greater extent than sixty percent (60%) of the total area of the *lot*.

8.24.6 Setbacks

- (1) *Front yard:* 7.5 m
- (2) *Rear yard:* 4.5 m except where a *lot* adjoins a residential zone without the intervention of a *street* or lane, in which case the minimum *rear yard* shall be:
 - (i) 9.0 m in the case of a *one-storey building*
 - (ii) 10.0 m in the case of buildings exceeding *one-storey*
- (3) *Side yard:* No *side yard* shall be required except where a *lot* adjoins a residential zone in which case the following applies:
 - (i) 6.0 m - *one storey*
 - (ii) 7.5 m - *two storeys*

and further, where the *side yard* flanks a *street* a minimum *setback* of 7.5 m is required.

8.24.7 Height of Buildings

No *building* shall exceed a *height* of 15.0 m.

8.24.8 Useable Open Space

Useable open space shall be provided on a *lot* in the amount of 20.0 m² per *dwelling unit*.

8.24.9 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 6.0 m in *height*
- (2) Shall have a *floor area* not exceeding 50.0 m²
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall not be permitted at the front of a *principal building*

8.24.10 Off-Street Parking and Loading

Off-street parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.24.11 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) A landscape area of 3.0 m shall be provided along the inside of all affected property lines. Where a *building* is greater than 4,500 m² a landscape area of 15.0 m shall be provided along the inside of all affected property lines.
- (2) Where a *lot* adjoins a residential or institutional use or adjoins 29th *Street*, Atlas Road, Anderton Road, Comox Road, Cumberland Road, Lerwick Road, Mission Road or Ryan Road a landscaped area of at least 7.5 m in width extending along the entire frontage of the property shall be provided inside the property line. Where a *lot* in this zone adjoins any other *street*, a landscaped area of at least 6.0 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.
- (3) To separate all *storage yards* from adjacent properties, a landscaped buffer area of at least 3.0 m in width and 2.0 m in *height* shall be provided along the inside of all property lines.
- (4) Loading areas, garbage and recycling containers shall be screened and gated to a minimum *height* of 2.0 m by a *landscaping* screen or solid decorative *fence* or a combination thereof.

Part 20 - Industrial Three Zone (I-3)

8.25.1 Permitted Uses

In the I-3 Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) Railway
- (2) Railway loading and unloading terminal
- (3) Railway passenger station
- (4) Transportation and facilities corridor

8.25.2 Minimum Lot Size

A *lot* shall have an area not less than 8.0 ha.

8.25.3 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 30.0 m.

8.25.4 Lot Coverage

A *lot* shall not be covered by buildings and structures to a greater extent than 10%.

8.25.5 Setbacks

Buildings and structures shall be sited in accordance with the following minimum *setbacks* except as otherwise specified in this bylaw:

- (1) *Front yard:* 10.0 m
- (2) *Rear yard:* 20.0 m
- (3) *Side yard:* 10.0 m

8.25.6 Height of Buildings

The *height* of a *principal building* shall not exceed 8.0 m.

8.25.7 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a *floor area* not exceeding 45.0 m²
- (3) Shall conform to all relevant siting regulations of this bylaw

8.25.8 Off-Street Parking

Off-street parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.25.9 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) A landscape area of 7.5 m shall be provided along the inside of all affected property lines. Where a *building* is greater than 4,500 m² a landscape area of 15.0 m shall be provided along the inside of all affected property lines.
- (2) Where a *lot* adjoins a *street*, a landscaped area of at least 10.0 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.
- (3) To separate parking, internal roads, services or storage areas from adjacent properties, a landscaped buffer area of at least 2.0 m in width and 2.0 m in *height* shall be provided along the inside of all property lines.
- (4) Loading areas, garbage and recycling containers shall be screened and gated to a minimum *height* of 2.0 m by a *landscaping* screen or solid decorative *fence* or a combination thereof.

Part 21 - Public Use and Assembly One Zone (PA-1)

8.26.1 Permitted Uses

In the PA-1 zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) *Assembly hall*
- (2) *Care facility*
- (3) *Cemetery*
- (4) *Church and religious centre, including one (1) accessory residential use and accessory day care*
- (5) *Facility for adults with a disability*
- (6) *Government office and facility*
- (7) *Hospital and related facility*
- (8) *Utility facility*
- (9) *School*
- (10) Notwithstanding the provisions of this bylaw, a short-term *care facility* is permitted on Lot 2, D.L. 127, Comox District, Plan VIP62286 (632 Pidcock Avenue) providing the following conditions are met:
 - 2684 (a) operated by a non-profit society either licensed or under permit from the Provincial Ministry of Human Resources for the purposes of providing short term emergency care;
 - 2932 (1) Notwithstanding the provisions of this bylaw a care facility, with meal services, 24/7 support and staffing services for individuals who are homeless or are at risk of homelessness is permitted on the property legally described as Lot 1, District Lot 127, Comox District, Plan EPP81814 (988 8th Street).
 - 2984 (2) Notwithstanding any provision of this bylaw, two (2) accessory residential uses are permitted on Lot 16, Section 16, Comox District, Plan 7037 Except That Part in Plan 44368 (1581 Dingwall Road).

8.26.2 Minimum Lot Size

A lot shall have an area of not less than 2,500 m².

8.26.3 Minimum Lot Frontage

A lot shall have a frontage of not less than 45.0 m.

8.26.4 Lot Coverage

A lot shall not be covered by buildings and *accessory* buildings to a greater extent than forty percent (40%) of the total area of the lot.

8.26.5 Setbacks

Except as otherwise specified in this bylaw, the following minimum *setback* requirements shall apply:

- (1) *Front yard*: 7.5 m
- (2) *Rear yard*: 10.0 m
- (3) *Side yard*: 9.0 m

8.26.6 Height of Buildings

No *building* shall exceed a *height* of 12.0 m.

8.26.7 Usable Open Space

Usable open space shall be provided for a *care facility* at 10.0 m² per unit.

8.26.8 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a *floor area* not exceeding 50.0 m²
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall not be permitted at the front of a *principal building*

8.26.9 Off-Street Parking and Loading

Off-street parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.26.10 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where a *lot* adjoins a residential zone, a landscaped area of at least 7.5 m shall be provided along the inside of all affected property lines.
- (2) Where a *lot* adjoins a *street*, a landscaped area of at least 6.0 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.
- (3) Notwithstanding the above, where a property is 2.0 ha or larger, a minimum 7.5 m landscaped area shall be provided along all property lines. Retention of existing natural vegetation, including mature trees, is required and any trees which are removed or destroyed shall be replaced, provided however that a public access trail may be constructed within this buffer area.

Part 22 - Public Use and Assembly Two Zone (PA-2)

8.27.1 Permitted Uses

In the PA-2 zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) *Accessory* residential use
- (2) *Assembly hall*
- (3) *Community service*
- (4) Parks and playground
- (5) Recreation facility

8.27.2 Lot Coverage

A *lot* shall not be covered by buildings and *accessory* buildings to a greater extent than ten percent (10%) of the total area of the *lot*.

8.27.3 Setbacks

Except as otherwise specified in this bylaw, the following minimum requirements shall apply:

- (1) *Front yard:* 7.5 m
- (2) *Rear yard:* 7.5 m except where a *lot* adjoins a residential zone without the intervention of a *street* or lane, in which case, the minimum shall be 15 m.
- (3) *Side yard:* 7.5 m shall be required except where a *lot* in this zone adjoins a residential zone without the intervention of a *street* or lane, in which case, a *side yard* shall be provided of not less than 15 m.

8.27.4 Height of Buildings

No *building* shall exceed a *height* of 12.0 m.

8.27.5 Off-Street Parking and Loading

Off-*street* parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.27.6 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where a *lot* adjoins a residential zone, a landscaped area of at least 2.0 m shall be provided along the inside of all affected property lines.
- (2) Where a *lot* adjoins a *street*, a landscaped area of at least 3.0 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.

- (3) Notwithstanding the above, where a property is 2.0 ha or larger, a minimum 7.5 m landscaped area shall be provided along all property lines. Retention of existing natural vegetation, including mature trees, is required and any trees which are removed or destroyed shall be replaced, provided however that a public access trail may be constructed within this buffer area.

Part 23 - Public Use and Assembly Three Zone (PA-3)

8.28.1 Permitted Uses

In the PA-3 zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this Bylaw:

- (1) Recreation facility
- (2) Schools including *accessory day care*

2875

For certainty, *pay parking operation* is not a permitted use in the PA-3 zone.

8.28.2 Minimum Lot Size

A *lot* shall have an area of not less than 2,500 m².

8.28.3 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 45.0 m.

8.28.4 Lot Coverage

A *lot* shall not be covered by buildings and *accessory* buildings to a greater extent than twenty percent (20%) of the total area of the *lot*.

8.28.5 Setbacks

Except as otherwise specified in this bylaw, the following minimum *setback* requirements shall apply:

- (1) *Front yard*: 7.5 m
- (2) *Rear yard*: 7.5 m except where a *lot* adjoins a residential zone without the intervention of a *street* or lane, in which case, the minimum shall be 15.0 m.
- (3) *Side yard*: 7.5 m shall be required except where a *lot* in this zone adjoins a residential zone without the intervention of a *street* or lane, in which case, a *side yard* shall be provided of not less than 15.0 m.

8.28.6 Height of Buildings

No *building* shall exceed a *height* of 12.0 m.

8.28.7 Off-Street Parking and Loading

Off-street parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.28.8 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where a *lot* adjoins a residential zone, a landscaped area of at least 2.0 m in *height* and 7.5 m in width shall be provided along the inside of all affected property lines.
- (2) Where a *lot* adjoins a *street*, a landscaped area of at least 7.5 m in width extending along the entire frontage of the property on the *street* shall be provided inside the property line.
- (3) Notwithstanding the above, where a property is 2.0 ha or larger, a minimum 7.5 m landscaped area shall be provided along all property lines. Retention of existing natural vegetation, including mature trees, is required and any trees which are removed or destroyed shall be replaced, provided however that a public access trail may be constructed within this buffer area.

**Part 24 - Public Use and Assembly Four Zone (PA-4)
for VIHA/NIC Hospital Site**

8.29.1 Permitted Uses

In the PA-4 zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this Bylaw:

- (1) Hospital and related uses
- (2) *Care facilities*
- (3) Hospital related commercial uses including but not limited to gift shop, confectionary store, coffee shop, pharmacy.
- (4) Medical related education and training facilities
- (5) Parkade
- (6) Helipad

2875

For certainty, *pay parking operation* is not a permitted use in the PA-4 zone.

8.29.2 Minimum Lot Size

A *lot* shall have an area of not less than 2,500 m².

8.29.3 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 45.0 m.

8.29.4 Lot Coverage

A *lot* shall not be covered by buildings and *accessory* buildings to a greater extent than forty percent (40%) of the total area of the *lot*.

8.29.5 Setbacks

Except as otherwise noted in this bylaw, the following minimum *setback* requirements shall apply:

- (1) *Front yard:* 7.5 m
- (2) *Rear yard:* 10.0 m
- (3) *Side yard:* 9.0 m

8.29.6 Height of Buildings

No *building* shall exceed a *height* of 40.0 m.

8.29.7 Usable Open Space

Usable open space shall be provided for a *care facility* at 10.0 m² per unit.

8.29.8 Off-Street Parking and Loading

Off-street parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.29.9 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where a *lot* adjoins a residential zone, a landscaped area of at least 7.5 m in width shall be provided along the inside of all affected property lines.
- (2) Where a *lot* adjoins a *street*, a landscaped area of at least 7.5 m in width extending along the entire frontage of the property on the street shall be provided inside the property line.
- (3) Where a property is 2.0 ha. or larger, an average setback of 7.5 m landscaped area shall be provided along all property lines which are not adjacent to a street or residential zone, but in no case shall the landscape area be less than 3.5m. Retention of existing natural vegetation, including mature trees, is required and any trees which are removed or destroyed shall be replaced, provided however that a public access trail may be constructed within this buffer area.

Part 25 - Agricultural One Zone (A-1)

8.30.1 Permitted Uses

In the A-1 zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) *Accessory building and structure*
- (2) *Agricultural use*
- (3) *Agricultural business*
- (4) *Home occupation*
- (5) *Mobile home*
- (6) *Single residential dwelling*
- (7) *Secondary suite*
- (8) Notwithstanding any provisions of this bylaw, a *golf course* and clubhouse is permitted on Parcel A (DD 585411), Section 22, Comox District, except part in Plan VIP70553 (4985 Cotton Road).

3071

8.30.2 Prohibited Uses

Notwithstanding the *Permitted uses* listed above, any use designated or permitted pursuant to Section 2 of the *Agricultural Land Reserve Use, Subdivision and Procedure Regulation* or farm use permitted by the Ministry of *Agriculture, Food and Fisheries*, except the following:

- (1) Commercial composting facility
- (2) *Intensive agriculture* including feedlots and stockyards
- (3) Kennels
- (4) Slaughterhouse and abattoir

8.30.3 Minimum Lot Size

A *lot* shall have an area of not less than 8.0 ha.

8.30.4 Maximum Density

3071

Two *dwelling units*.

8.30.5 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 150 m.

8.30.6 Minimum Lot Depth

A *lot* shall have a depth of not less than 35.0 m.

8.30.7 Lot Coverage

A *lot* shall not be covered by buildings and structures to a greater extent than 10% of the total *lot*.

8.30.8 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front yard*: 15.0 m
- (2) *Rear yard*: 15.0 m
- (3) *Side yard*: 15.0 m

8.30.9 Height of Buildings

- (1) The *height* of a *dwelling unit* shall not exceed 9.0 m.
- (2) The *height* of buildings and structures used for the purpose of farming shall not exceed 10.0 m.

8.30.10 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a *floor area* not exceeding 46.45 m²
- (3) Shall be permitted in front of a principal *residence* provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.30.11 Off-Street Parking

Off-*street* parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.30.12 General Regulations

- (1) The Minimum *Setback* of all buildings or structures housing livestock or manure from all *lot lines* and/or watercourses shall be 30.0 m.
- (2) Despite any regulation in this Bylaw, land established as "Agricultural Land Reserve" pursuant to the *Agricultural Land Reserve Act* is subject to the *Agricultural Land Reserve Act and Regulations*, and applicable orders of the Land Reserve Commission.

Part 26 - Agricultural Two Zone (A-2)

8.31.1 Permitted Uses

In the A-2 zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) Agricultural use
- (2) *Assembly hall*
- (3) Fairgrounds
- (4) *Utility facility*
- (5) Recreation facility and *accessory* temporary accommodation
- (6) *Accessory* uses:
 - (a) Residential use limited to one *dwelling unit*
 - (b) On any *lot* containing fairgrounds:
 - (i) Camping directly related to a sanctioned event occurring on the same lands
 - (ii) Camping limited to a maximum period of 72 hours.

8.31.2 Minimum Lot Size

A *lot* shall have an area of not less than 8.0 ha.

8.31.3 Maximum Density

Two *dwelling units* provided one *dwelling unit* is a *mobile home*.

8.31.4 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 150 m.

8.31.5 Minimum Lot Depth

A *lot* shall have a depth of not less than 40.0 m.

8.31.6 Lot Coverage

A *lot* shall not be covered by buildings and structures to a greater extent than 35% of the total *lot*.

8.31.7 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front yard:* 15.0 m
- (2) *Rear yard:* 15.0 m
- (3) *Side yard:* 15.0 m

8.31.8 Height of Buildings

- (1) The *height* of a *dwelling unit* shall not exceed 9.0 m.
- (2) The *height* of all other buildings shall not exceed 15.0 m.

8.31.9 Off-Street Parking

Off-*street* parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw

8.31.10 General Regulations

- (1) The minimum *setback* of all buildings or structures housing livestock or manure from all *lot lines* and/or watercourses shall be 30.0 m.
- (2) Despite any regulation in this Bylaw, land established as "Agricultural Land Reserve" pursuant to the *Agricultural Land Reserve Act* is subject to the *Agricultural Land Reserve Act and Regulations*, and applicable orders of the Land Reserve Commission.

Part 27 - Comprehensive Development One Zone (CD-1)

Crown Isle (Block 72)

8.32.1 Intent

This zone is intended to accommodate and to regulate the development of a mixture of uses on lands described as Block 72, Comox District, except parts outlined in red on Plan 1691R and 2117RW and except part in Plan 49168; *Lot A*, Block 72, Comox District, Plan 49168; and that part of Block 72, Comox District, shown outlined in red on Plan 1691R (collectively “Block 72”). Block 72 has been designated a Development Permit Area in “Official Community Plan Bylaw No. 2397, 2005” and accordingly, development must be consistent with the objectives and guidelines therein.

8.32.2 Permitted Uses

In the CD-1 Zone the following uses are permitted and other uses are prohibited except as otherwise noted in this bylaw:

- 3071
2618
- (1) Within that portion of Block 72 identified as Area A on the CD-1 Zone map:
 - (a) *Single residential dwellings*
 - (b) *Secondary suite*
 - (c) *Duplex dwellings*
 - (d) *Multi residential dwellings*
 - (e) *Accessory buildings and structures*
 - (f) *Boarding*
 - (g) *Home occupation*
 - (h) *Golf course* including *accessory* buildings

 - (2) Within that portion of Block 72 identified as Area B on the CD-1 Zone map:
 - (a) *Single residential dwellings*
 - (b) *Secondary suite*
 - (c) *Duplex dwellings*
 - (d) *Multi residential dwellings*
 - (e) *Accessory buildings and structures*
 - (f) *Boarding*
 - (g) *Care facility*
 - (h) *Home occupation*
 - (i) *Golf course*, including one clubhouse with *accessory* restaurants, *accessory* meeting room, *accessory* lounges and pro-shop, driving range, golf school, *golf course* maintenance and supply *yards* and buildings, car museum as part of a golf clubhouse
 - (j) *Motel* including single and *duplex* units on Lot 2, Plan VIP64932

 - (3) Within that portion of Block 72 identified as Area C on the CD-1 Zone map:
 - (a) *Car museum*
 - (b) *Hotel*

- 2597 (4) Within that portion of Block 72 identified as Area F on the CD-1 Zone map:
- (a) *Retail sales, personal services, offices, restaurants, licensed premises, entertainment (excluding amusement arcades), automobile service station uses and medical clinic*
 - (b) *Motel*
 - (c) *Liquor store*
 - (d) *Automobile sales and accessory repair shops*
 - (e) *Light manufacturing, excluding sawmills, provided the manufacturing operations take place in an enclosed principle building*
 - (f) *Family amusement centre including mini-golf, bumper boats, and children's arcade*
 - (g) *Building material sales*
 - (h) *Auto and truck repairs*
 - (i) *Printers and publishers*
 - (j) *Veterinary Clinic*
 - (k) *Communications, office and studio*
 - (l) *Enclosed storage building, including warehouse, and storage yard*
 - (m) *Wholesale sales outlets*
 - (n) *Residential quarters may be incorporated above a principal building*
 - (o) *Financial Institutions*
 - (p) *Parks*
 - (q) *Notwithstanding any provision of this bylaw, a storefront cannabis retailer is a permitted use on Lot 1, Block 72, Comox District, Plan VIP81206 (#301 & #302-444 Lerwick Rd)*
- 3010 (5) Within that portion of Block 72 identified as Area G on the CD-1 Zone map:
- (a) *Single residential dwellings*
 - (b) *Secondary suite*
 - (c) *Duplex dwellings*
 - (d) *Townhouse dwellings*
 - (e) *Accessory buildings and structures*
 - (f) *Boarding*
 - (g) *Home occupation*
 - (h) *Golf course including accessory buildings*
 - (i) *Park*
- 3071 (6) Within that portion of Block 72 identified as Area H on the CD-1 Zone map:
- (a) *Single residential dwellings*
 - (b) *Secondary suite*
 - (c) *Multi residential dwellings*
 - (d) *Accessory buildings and structures*
 - (e) *Boarding*
 - (f) *Home occupation*
 - (g) *Golf course, including accessory buildings*
- 2748 (7) Within that portion of Block 72 identified as Area I on the CD-1 Zone map:
- (a) *Single residential dwelling*
 - (b) *Secondary suite*
 - (c) *Multi residential dwellings*
 - (d) *Accessory buildings and structures*
 - (e) *Boarding*
 - (f) *Home occupation*
- 3071

8.32.3 Densities

Land uses within the various areas defined on the CD-1 Zone map shall not exceed the following maximum densities:

- 2597 &
2763
- (1) Within Area A:
- (a) *Single residential* dwellings: 477 *dwelling units* within 42.88 ha
 - (b) *Single residential, duplex* and multi residential dwellings: 190 *dwelling units* within 7.7 ha
 - (c) Park: 2.4 ha
 - (d) *Golf course*, including one clubhouse, *accessory* restaurants, lounges and pro-shop, *golf course* maintenance and supply *building*, not exceeding a cumulative *floor area* of 1,000 m² within 11.46 ha
- 2748
- (2) Within Area B:
- (a) *Single residential* dwellings: 1008 *dwelling units* within 89.2 ha
 - (b) *Single residential, duplex* and multi residential dwellings: 670 *dwelling units* within 16.38 ha
 - (c) *Golf course*, including a clubhouse, *accessory* restaurants, lounges and pro-shop, car museum as part of a golf clubhouse, driving range: 2,787 m² of *floor area* within 72.6 ha
 - (d) *Motel* including single and *duplex* units on Lot 2, Plan VIP64932
 - (e) Commercial: 242 m² of *floor area* within 0.6 ha
 - (f) *Care facility* of 125 dwelling or sleeping units within 1.2 ha
- (3) Within Area C:
- (a) *Hotel*
 - (b) Car museum
- 2597
- (4) Within Area F:
- (a) Commercial: 124,486 m² of *floor area* within 32.54 ha
- (5) Within Area G:
- (a) *Single residential, duplex* and *townhouse* dwellings: 210 *dwelling units* within 18.82 ha
 - (b) *Townhouse* development shall not exceed 20 units per ha
- 2748
- (6) Within Area H:
- (a) Approximately 104 single family and *multi residential dwellings* within 16.3 ha
- 2763
- (7) Within Area I:
- (a) Approximately 30 single family and multi residential dwellings within 2.43 ha

8.32.4 Density – General Regulations

- 2597
- (1) A maximum of one *principal building* and one *accessory building* or *structure* may be constructed on a single residential lot.
 - (2) Notwithstanding paragraph (1) one clubhouse and any number of *accessory* buildings may be situated on a *golf course* in Area B.

2833

- (3) No *lot* occupied by a multi residential *building* containing more than 2 *dwelling units* shall have a *floor area ratio* exceeding 0.4 except for:
 - (a) Strata Plan VIS5490
 - (b) Lot 1, Plan VIP76675
 - (c) the property lying immediately to the east of Strata Plan VIS5490 and Lot1, Plan VIP76675 between the remainder of Lot A, Plan VIP722239 and Royal Vista Way containing 2 hectares.
 - (d) Properties within Area A
- (4) No *lot* occupied by a commercial or light industrial *building* shall have a *floor area ratio* exceeding 0.6.
- (5) No commercial *building* shall be situated on a *lot* less than 550 m² in area.
- (6) No *duplex* dwelling shall be situated on a *lot* less than 550 m² in area.
- (7) No *townhouse* dwelling shall be situated on a *lot* less than 1,100 m² in area, other than in Area B, where no *townhouse* may be situated on a *lot* less than 550 m² in area.
- (8) No *apartment* dwelling shall be situated on a *lot* less than 1,100 m² in area.
- (9) No *golf course* shall be situated on a *lot* less than 25 acres in area.
- (10) No *care facility* shall be situated on a *lot* less than 1,100 m² in area and no *care facility* shall exceed a *lot coverage* of 40%.
- (11) Lot 1, Block 72, Comox District, Plan VIP82600 shall have a lot area of not less than 0.157 ha. and be permitted one duplex.

8.32.5 Lot Coverage

Maximum *lot coverage* shall be as follows:

- (1) Single and *Duplex* Residential: 45%
- (2) Multi Residential: 40%

8.32.6 Minimum Lot Sizes

The minimum size of lots which may be created by *subdivision* within the CD-1 Zone are as follows:

- (1) Area A: 465 m²
- (2) Area B: 465 m²
- (3) Area C: 465 m²
- (4) Area E: 700 m²
- (5) Area F: 550 m²
- (6) Area G: 550 m² for *single residential*
900 m² for *duplex*
8,000 m² for *multi residential*
- 2748 (7) Area H: 465 m² for *single residential*
1600 m² for *multi residential*
- 2763 (8) Area I: 465 m² for *single residential*
1600 m² for *multi residential*

8.32.7 Minimum Lot Frontage

A minimum of 10% of the perimeter of every *lot* created by *subdivision* shall front on a highway, provided that this requirement may be reduced to a minimum of 2% in the discretion of the Approving Officer.

8.32.8 Useable Open Space

2618

Every *lot* occupied by multi residential dwellings shall include a minimum of 15.0 m² of useable open space for each dwelling unit on the lot. Every lot occupied by a care facility shall include 10.0 m² of useable open space for each unit on the lot.

8.32.9 Setbacks

(1) Minimum yards shall be provided in accordance with the following table:

	Type of Building	Front yard	Rear yard	Side yard	Exterior Side yard
	AREAS A				
	<i>Single residential lot</i>	6.0 m	7.5 m	1.5 m	3.0 m
	<i>Duplex lot</i>	6.0 m	7.5 m	1.5 m	3.0 m
	<i>Multi Residential</i>	7.5 m	7.5 m	4.5 m	4.5 m
2833	<i>Multi Residential adjacent to Residential Use</i>	See 8.32.9(2)	See 8.32.9(2)	See 8.32.9(2)	See 8.32.9(2)
2833	<i>Multi Residential adjacent to Commercial Use</i>	7.5 m	7.5 m	4.5 m	4.5 m
	AREAS B - F				
	<i>Single residential lot</i>	7.5 m	9.0 m	1.5 m	3.0 m
	<i>Duplex lot</i>	6.0 m	9.0 m	1.5 m	3.0 m
	<i>Townhouse dwelling</i>	7.5 m	7.5 m	4.5 m	4.5 m
	<i>Care Facility</i>	7.5 m	10.0 m	4.5 m	4.5 m
	<i>Multi Residential</i>	7.5 m	10.0 m	4.5 m	4.5 m
	<i>Commercial</i>	6.1 m	1.75 m	0	4.5 m
	<i>Light Industrial</i>	6.0 m	12.0 m	3.0 m	4.5 m
	<i>Clubhouse</i>	7.5 m	7.5 m	7.5 m	7.5 m
2748	AREA G				
	<i>Single residential lot</i>	6.0 m	7.5 m	1.5 m	3.0 m
	<i>Duplex lot</i>	6.0 m	7.5 m	1.5 m	3.0 m
	<i>Townhouse dwelling</i>	7.5 m	7.5 m	4.5 m	4.5 m
2763	AREAS H - I				
	<i>Single residential lot</i>	6.0 m	7.5 m	1.5 m	3.0 m
	<i>Multi Residential</i>	7.5 m	7.5 m	4.5 m	4.5 m

- 2618 (2) Notwithstanding paragraph (1):
- (a) where a *multi residential building* in Area A is adjacent to a *residential* use the setbacks to the adjoining property line are:
- 2597 i) Front yard: 7.5 m
- ii) Rear yard: 7.5 m – 2 or less storeys
 10.0 m – 3rd storey
 13.5 m – 4th storey
- iii) Side yard: 4.5 m – 2 or less storeys
 6.0 m – 3rd storey
 7.5 m – 4th storey
- (b) where a *multi residential dwelling* exceeds two *storeys* in *height*, 2.0 m shall be added to the minimum *rear yard setback* requirement for each *storey* in excess of 2 *storeys*
- (c) where a commercial *building* occupies a *lot* adjacent to a *lot* zoned to permit residential or institutional uses, the *yard* on each side of the *building* adjoining a residential or institutional *lot* shall be a minimum of 7.5 m
- (d) a minimum *front yard* of 12.0 m shall be provided for a principal automobile *service station building*
- (e) where a residential or commercial *building* occupies a *lot* adjacent to land used for agricultural purposes, a minimum *rear yard* of 15.0 m shall be provided for a *principal building*
- (f) Where the back of a *building* is adjacent to or faces a side *lot line* the minimum *side yard setback* shall be 6.0 m

8.32.10 Heights

- (1) *Principal buildings* shall not exceed the following *heights*:

- | | | |
|------|--|--------|
| 2597 | (a) <i>Single residential</i> | 8.0 m |
| | (b) <i>Duplex</i> | 8.0 m |
| | (c) <i>Townhouse dwelling</i> | 15.0 m |
| | (d) <i>Multi Residential</i> | 15.0 m |
| | (e) <i>Care facility</i> | 15.0 m |
| | (f) <i>Commercial</i> | 15.0 m |
| | Notwithstanding, where a commercial building occupies a lot adjacent to a lot zoned to permit residential use, institutional or park, principal buildings shall not exceed 9.15 m in height. | |
| | (g) <i>Golf Clubhouse</i> | 15.0 m |
| | (h) <i>Hotel</i> | 15.0 m |
| | (i) <i>Motel</i> | 9.15 m |

8.32.11 Off-Street Parking and Loading

Off-*street* parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.32.12 Accessory Buildings and Structures

Accessory buildings and structures shall conform to the following regulations:

If *accessory* to a *single residential dwelling, duplex dwelling, townhouse dwelling, apartment dwelling, commercial or industrial building*:

- (1) A maximum *height* of 4.5 m
- (2) A maximum *floor area* of the greater of 45.0 m² or 10% of the area of the required *rear yard*, for all *accessory* buildings combined
- (3) may be located in the required *rear yard*
- (4) shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

2685

8.32.13 Landscaping and Screening

All *landscaping* and screening shall conform to Part 14 of this bylaw.

Part 28 - Comprehensive Development Zone Three Zone (CD-3)
St. Andrews & Idiens Way

8.33.1 Intent

This zone is intended to accommodate and regulate the development of *single residential* and multi residential housing.

8.33.2 Permitted Uses and Development

In the CD-3 Zone, the following uses and development are permitted and all other uses are prohibited within the area identified on Schedule 8A, zoning map, except as otherwise noted in this bylaw:

- (1) *Single residential* dwelling
- (2) *Townhouse* dwelling
- (3) *Accessory building and structure*
- (4) *Home occupation*

8.33.3 Lot Coverage

Maximum *lot coverage* shall not exceed 40%

8.33.4 Minimum Lot Sizes and Frontages

The minimum size of lots which may be created by *subdivision* within the CD-3 zone area as follows:

	Minimum Lot Size	Minimum Frontage
<i>Single residential</i>	550.0 m ²	18.0 m
<i>Townhouse</i>	1,250 m ²	30.0 m

8.33.5 Useable Open Space Requirements

Every *lot* occupied by a multi residential dwelling shall include a minimum of 15 m² of *useable open space* for each *dwelling unit* on the *lot*.

8.33.6 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

Type of <i>Building</i>	Front	Rear	Side	Exterior Side
<i>Single residential</i>	4.5 m	7.5 m	1.5 m	4.5 m, 6.0 m for <i>garage</i> or <i>carport</i>
<i>Townhouse Dwelling</i>	7.5 m	9.0 m	4.5 m	4.5 m

and further, where the back of a *building* is adjacent to or faces a side *lot line* the minimum *side yard setback* shall be 6.0 m.

8.33.7 Height

No *building* or *structure* shall exceed 8.0 m in *height*.

8.33.8 Accessory Buildings and Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a total *floor area* not exceeding 45 m² or 10% of the area of the required *rear yard*, for all *accessory* buildings combined
- (3) Shall be permitted *rear yard* provided they shall conform to all relevant siting regulations of this bylaw.
- (4) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.33.9 Off-Street Parking and Loading

Shall be provided and maintained in accordance with the requirements of Division 7 of this Bylaw and further, no more than 50% of the *front yard* can be used for off-*street* parking.

8.33.10 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where a *lot* adjoins a residential or institutional use a landscaped area of at least 1.5 m in width and *height* extending along the entire frontage of the property shall be provided inside the property line
- (2) Where a *lot* adjoins a *street* a landscaped area of at least 3.0 m in width extending along the entire frontage of the property shall be provided inside the property line.

Part 29 - Comprehensive Development Zone Four Zone (CD-4)
31st Street

8.34.1 Intent

This zone is intended to accommodate and regulate the development of *single residential* and *duplex* use on Lots 12 and 13, Section 67, Comox District, Plan VIP55151.

8.34.2 Permitted Uses and Development

In the CD-4 Zone, the following uses and development are permitted and all other uses are prohibited within the area identified on Schedule 8A, zoning map, except as otherwise noted in this bylaw:

- (1) *Single residential* and *duplex* dwellings
- (2) *Accessory* buildings and structures

8.34.3 Density

Maximum number of *dwelling units* shall not exceed 27 of which 4 *dwelling units* can be within *duplex* dwellings, provided all the applicable conditions are met.

8.34.4 Lot Coverage

Maximum *lot coverage* shall not exceed 45%

8.34.5 Minimum Lot Sizes and Frontages

The minimum *lot* sizes and frontages which may be created by *subdivision* within the CD-4 zone area as follows:

	Minimum Lot Size	Minimum Frontage
<i>Single residential</i> Dwelling	250 m ²	8.5 m
<i>Duplex</i> Dwelling	250 m ² /unit	15.0 m

8.34.6 Useable Open Space Requirements

The *building* site shall incorporate a recreation area of not less than 350.0 m² which is specifically designed and equipped for the residents of the development.

8.34.7 Setbacks

	Front	Rear	Side
Parent Parcel	4.5 m (Cliffe Avenue)	4.5 m	1.5 m
Single residential Dwelling	4.5 m	4.5 m (external) 3.02 m (internal)	1.5 m
Duplex Dwelling	4.5 m	0 m	1.5 m

8.34.8 Maximum Height

Principle buildings shall not exceed the following *heights*:

Single residential 9.5 m

Duplex dwelling 5.5 m

8.34.9 Accessory Buildings and Structures

- (1) A maximum *height* of 4.5 m
- (2) A maximum *floor area* of the 45.0 m² for all *accessory* buildings combined on a *lot*
- (3) May be located in the required side or *rear yard*
- (4) Shall not be located within 1.0 m from the side and rear property line

8.34.10 Off-Street Parking

Shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.34.11 Landscaping and Screening

All *landscaping* shall conform to Part 14 of this bylaw.

**Part 30 - Comprehensive Development Zone Six Zone (CD-6)
13th and Burgess**

8.35.1 Intent

The purpose of this zone is to provide for the siting and development of *single residential* buildings at 13th Street and Burgess Road.

8.35.2 Permitted Uses

In the CD-6 Zone, the following uses and development are permitted and all other uses are prohibited within the area identified on Schedule 8A, Zoning Map, unless otherwise noted in this bylaw.

3071
2927

- (1) *Single residential* dwellings
- (2) *Secondary suite*
- (3) *Accessory* buildings
- (4) *Home occupation*
- (5) Notwithstanding any provision of this bylaw, *Multi residential dwellings* are a permitted use on Lot 4, District Lot 96, Comox District, Plan 32210, Except Part in Plan VIP68472 and VIP76687 (2048 – 13th Street).

8.35.3 Density

The maximum number of *dwelling units* shall not exceed 66.

8.35.4 Lot Coverage

The maximum *lot coverage* of all buildings shall not exceed 35%

8.35.5 Floor Area Ratio

Providing all other applicable siting conditions are met, the maximum *floor area ratio* shall not exceed 0.5.

8.35.6 Minimum Lot Size

For the purposes of *subdivision*, the minimum *lot size* shall be 550.0 m² provided however that the density may be increased to a maximum of 66 lots as follows:

<u>Parcel Size</u>	<u>Percentage</u>
375 m ² to 465 m ²	<50%
>465 m ² to 550 m ²	<30%
>550 m ²	>20%

And further, the amount of area designated for park purposes shall exceed 5% of the *lot area* to reflect the percentage of the added density pursuant to Section 904 of the *Local Government Act*.

8.35.7 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 13.5 m for an internal *lot* and 15.0 m for a *corner lot* and where a *lot* is located on a curve or cul-de-sac, a minimum frontage of 11.0 m with an average width of 13.5 m shall be maintained.

8.35.8 Setbacks

Except where otherwise specified in this bylaw the following *setback* requirements shall apply.

- (1) *Front yard*: 4.5 m for a *single residential* dwelling and 6.0 m for a *garage* or carport
- (2) *Rear yard*: 7.5 m
- (3) *Side yard*: The *side yard setbacks* shall total 4.5 m with a minimum *side yard setback* on one side of 1.5 m except where a *side yard* flanks a *street* in which case the minimum distance shall be 4.5 m.

8.35.9 Height

The *height* of a *principal building* shall not exceed 7.5 m.

8.35.10 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a *floor area* not exceeding 50.0 m².
- (3) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.35.11 Off-Street Parking

Off-*street* parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw and in addition, not more than 50% of the *front yard* shall be used for off *street* parking

8.35.12 Landscaping and Screening

All *landscaping* shall conform to Part 14 of this bylaw.

Part 31 - Comprehensive Development Zone Seven Zone (CD-7)

Marsland Residential Development

8.36.1 Intent

The purpose of this zone is to provide for the siting and development of *single residential, duplex*, and multi residential buildings on *Lot B*, Sections 6 and 8, Comox District, Plan 35008.

8.36.2 Permitted Uses

In the CD-7 Zone, the following uses and development are permitted and all other uses are prohibited within the area identified on Schedule 8A, Zoning Map, unless otherwise noted in this bylaw.

8.36.3 Area CD-7A

Permitted uses:

- (1) *Single residential dwelling*
- (2) *Accessory building and structure*
- (3) *Home occupation*

Minimum Lot Size:

A *lot* shall have an area of not less than 450.0 m²

Minimum Lot Frontage:

A *lot* shall have a frontage of not less than 15.0 m

Lot Coverage:

A *lot* shall not be covered by buildings to a greater extent than 40% of the total area of a *lot*.

Setbacks:

Except as otherwise specified in this bylaw, the following minimum *setback* requirements shall apply:

- | | |
|--------|--|
| Front: | 2 m from <i>principal building</i> and 4 m from front of a <i>garage</i> or carport with a minimum of 6 m from front of <i>garage</i> or carport to back of sidewalk or curb |
| Rear: | 7.5 m |
| Side: | 1.5 m |

Height:

The *height* of a *principal building* shall not exceed 8 m.

8.36.4 Area CD-7B

Permitted Uses:

- (1) *Single residential dwelling*
- (2) *Duplex dwelling*
- (3) *Accessory building or structure*
- (4) *Home occupation*

Minimum Lot Size:

A lot shall have an area of not less than 400.0 m².

Minimum Lot Frontage:

A lot shall have a frontage of not less than 15.0 m.

Lot coverage:

A lot shall not be covered by buildings to a greater extent than 40% of the total area of a lot.

Setbacks:

Except as otherwise specified in this bylaw, the following minimum *setback* requirements shall apply:

- Front: 2.0 m from *principal building* and 4.0 m from front of a *garage* or carport with a minimum of 6.0 m from front of *garage* or carport to back of sidewalk or curb.
- Rear: 7.5 m to *street* and 3.0 m to property line with a minimum of 6.0 m from front of *garage* or carport to back of sidewalk or curb.
- Side: 1.5 m and 3.04 m where *side yard* flanks a *street*.

Height:

The *height* of a *principal building* shall not exceed 8 m.

8.36.5 Area CD-7C

Permitted uses:

- (1) *Single residential* dwelling
- (2) *Duplex* dwelling
- (3) *Multi residential* dwellings
- (4) *Accessory* buildings and structures
- (5) *Home occupation*

Minimum Lot Size:

A lot shall have an area of not less than 1,100 m².

Minimum Lot Frontage:

A lot shall have a frontage of not less than 30 m.

Floor area ratio:

Providing all other applicable siting conditions are met, the maximum *floor area ratio* shall not exceed 0.7.

Setbacks:

Except as otherwise specified in this bylaw, the following minimum *setback* requirements shall apply:

- Front: Back Road Frontage: 7.5 m
- Marsland Place: 2.0 m from *principal building* and 4.0 m from front of a *garage* or carport with a minimum of 6.0 m from front of *garage* or carport to back of sidewalk or curb.

Rear: 90% of length to be a minimum of 7.5 m and the balance to be a minimum of 3.0 m.
Side: 3.0 m

Height:

The *height* of a *principal building* shall not exceed 8 m.

8.36.6 Area CD-7D

Permitted uses:

- (1) *Single residential dwelling*
- (2) *Duplex dwelling*
- (3) *Multi residential dwellings*
- (4) *Accessory buildings and structures*
- (5) *Boarding*
- (6) *Home occupation*

Minimum Lot Size:

A *lot* shall have an area of not less than 1,100 m².

Minimum Lot Frontage:

A *lot* shall have a frontage of not less than 30.0 m.

Floor area ratio:

Providing all other applicable siting conditions are met, the maximum *floor area ratio* shall not exceed 1.0.

Setbacks:

Except as otherwise specified in this bylaw, the following minimum *setback* requirements shall apply:

- Front: For structures with more than 2 *dwelling units* the minimum *setback* is 15.0 m. For structures with 2 or less *dwelling units*, 2.0 m from a *principal building* and 4.0 m from front of a *garage* or carport with a minimum of 6.0 m from front of *garage* or carport to back of sidewalk or curb.
- Rear: 9.0 m
- Side: 1.5 m for structures with 2 or less *dwelling units*
5.0 m for structures with more than 2 *dwelling units*

Height:

For structures with two or less *dwelling units*, 2 *storeys* or 8.0 m. For structures with more than 2 *dwelling units*, 4 *storeys* or 13.71 m, for apartments and 2 *storeys* or 9.15 m for townhouses.

Useable open space:

Useable open space shall be a minimum of 30.0 m² per unit.

8.36.7 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*;
- (2) Shall have a *floor area* not exceeding 46.45 m² or 10% of the *rear yard*, whichever is greater, except where the *structure* is used to cover parking, in which case, the *floor area* shall not exceed 20% of the rear yard, and shall not extend for more than □ of the length of any property line or 30.0 m, whichever is less.
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw;
- (4) Shall not be permitted at the front of a principal *residence*;
- (5) Shall not be located within 1.5 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m;
- (6) Shall not be situated closer than 3.0 m from the *principal building* that the *accessory building* serves.

8.36.8 Off-Street Parking and Loading

Off-*street* parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw except for CD-7D in which case parking shall be provided at a rate of 1.25 *parking spaces* per *dwelling unit*.

8.36.9 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where a multiple residential use or any parking area and/or access aisles thereto adjoins a single or *duplex* residential *lot*, a landscaped screen or a uniformly painted *fence* or wall of not less than 2.0 m in *height* and 1.5 m in width along the common *lot line* shall be provided and maintained in good condition at all times.

Part 32 - Comprehensive Development Eight Zone (CD-8)

Anfield Centre

8.37.1 Intent

This zone is intended to accommodate and regulate the development of a *retail commercial shopping centre*.

8.37.2 Permitted Uses

a. In the CD-8 zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) Small item sales, service, repair and rental
- (2) Apparel and *accessory* store
- (3) Automobile parts and supplies
- (4) Furniture and home furnishings
- (5) *Office* supplies
- (6) *Building supply* store
- (7) *Garden* store
- (8) *Retail* store
- (9) *Grocery* store
- (10) Video rental and sales

A maximum of 2 permitted *retail* uses listed above from 1 through 10 inclusive can have a gross *floor area* of less than 250.0 m² and a maximum of 3 permitted *retail* uses listed above from 1 to 10 inclusive can have a gross *floor area* between 250.0 m² and 325.0 m².

- b. (1) *Financial institution*
- (2) Barber shop and beauty salon
- (3) Theatre
- (4) Restaurants
- 2685 (5) *Medical clinic*
- (6) *Service station* and gas bar
- 2644 (7) Offsite Retail Wine Store

8.37.3 Condition of Use

- (1) Garbage containers, recycling containers, storage facilities, parking, and loading facilities shall not be located within any required *setback* as specified in Section 8.36.6.
- (2) All businesses, repair or servicing uses shall be conducted within a completely enclosed *building* except as permitted for designated outdoor display and sales.

8.37.4 Lot Coverage

Provided all other applicable size and siting conditions are met, the maximum *lot coverage* for buildings and structures shall be 30% of the total area of the *lot*.

8.37.5 Minimum Lot Size

A *lot* shall have an area of not less than 2 hectares.

8.37.6 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall be:

Cliffe Avenue Frontage	15.0 m at the northeast corner of the entire site tapering across the entire frontage to 9.5 m at the southeast corner of the entire site (Anfield Road)
Anfield Road Exchange	4.5 m at the SW corner of the entire site tapering across the entire frontage to 7.5 m at the SE corner (Cliffe Avenue)
E & N Railway R/W Frontage	7.5 m
all other <i>yards</i>	3.0 m

Notwithstanding the above, the minimum *building setback* for any *building* greater than 4,500 m² shall be 15.0 m.

8.37.7 Height

No *building* shall exceed a *height* of 9.15 m.

8.37.8 Off-Street Parking and Loading

Off-Street parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw except that all required parking for uses within this zone must be on the same *lot* as the principle use and buildings.

8.37.9 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where the property borders on Cliffe Avenue (Island Highway) a landscaped area of 15.0 m at the northeast corner of the entire site tapering across the entire frontage to 9.5 m at the southeast corner of the entire site (Anfield Road) from the inside of the property line in accordance with the approved Development Permit and maintained to the satisfaction of the *City*.
- (2) Where the property borders on Anfield Road, a landscaped area of an average of 7.5 m in width with no width less than 4.5 m at any one location shall be provided from the inside of the property line in accordance with the approved Development Permit and maintained to the satisfaction of the *City*.

- (3) Where the property borders the E & N Railway a landscaped area of an average of 6.0 m in width with no width less than 2.0 m at any one location shall be provided from the inside of the property line in accordance with the approved Development Permit and maintained to the satisfaction of the *City*.
- (4) Where the property borders all other *yards* a landscaped buffer area of an average of 4.5 m in width with no width less than 3.0 m at any one location shall be provided from the inside of the property line in accordance with the approved Development Permit and maintained to the satisfaction of the *City*.
- (5) Loading Areas, garbage containers recycling containers and storage facilities screened to a *height* of at least 2.0 m by buildings, a *landscaping* screen, a solid decorative *fence*, or a combination thereof.

Part 33 - Comprehensive Development Nine Zone (CD-9)
2nd/Duncan Avenue

8.38.1 Intent

This zone is intended to accommodate and regulate the development a *care facility* for the properties described as:

- (1) *Lot 8, Section 61, Comox District, Plan 2834;*
- (2) *Lots 3 & 4, Block A, Section 61, Comox District, Plan 1395;*
- (3) *Lot A, Section 61, Comox District, Plan VIP57557;*
- (4) *Lots 19, 20, 21 & 22, Section 61, Comox District, Plan 1517; and,*
- (5) *Lot A, Section 61, Comox District, Plan VIP54105.*

8.38.2 Permitted Uses

In the CD-9 Zone, the following uses and development are permitted and all other uses are prohibited within the area identified on Schedule 8A, Zoning Map, except as otherwise noted in this bylaw.

Use:	<i>Single residential</i> dwelling, care facility and <i>accessory</i> buildings. <i>Single residential</i> dwellings must conform to Sections 8.1.2 through 8.1.9 inclusive, of the <i>City of Courtenay Zoning Bylaw</i> .
Density:	Maximum <i>lot coverage</i> of 55% Maximum <i>floor area ratio</i> of 1.4
Minimum <i>Yards</i> :	<i>Cliffe Avenue and 2nd Street:</i> 4.5 m <i>3rd Street and Duncan Avenue:</i> 3.9 m <i>Internal side yards:</i> 4.9 m
Maximum <i>Height</i> :	<i>Building height</i> shall not exceed 8.0 m within 32.0 m of <i>2nd Street</i> . For all other areas of the site, the <i>building height</i> shall not exceed 16 m.
<i>Useable open space</i> :	10.0 m ² of usable open space shall be provided per <i>dwelling unit</i> for <i>care facility dwelling units</i> .

8.38.3 Minimum Lot Size and Frontage

The minimum *lot* sizes and frontages that may be created by *subdivision* within the CD-9 zone are:

	Minimum <i>Lot</i> Size	Minimum Frontage
<i>Care facility</i> :	1,100 m ²	30.0 m

8.38.4 Off-Street Parking and Loading

Shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.38.5 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where a *lot* in this zone adjoins a *street*, a landscaped area of at least 3.0 m in width, located within the property lines, shall be provided along all facing streets to the satisfaction of the *City*.

Part 34 - Comprehensive Development Ten Zone (CD-10)

Church (2700 Inverclyde Way)

8.39.1 Intent

This zone is intended to accommodate and to regulate the development of a church facility on part of *Lot A*, District *Lot 158*, Plan VIP53738.

8.39.2 Permitted Uses

Church including daycare, activity room, gym, clubs, youth groups and community groups to a maximum seating capacity of 450.

8.39.3 Building Size

The maximum *floor area* of the buildings within this zone shall be 1,580 m²

8.39.4 Minimum Lot Size

For the purposes of *subdivision*, the minimum *lot* size shall not be less than 1 ha.

8.39.5 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 18 m.

8.39.6 Setbacks

Except where otherwise specified in this bylaw, the *building setback* from all property lines shall be 20 m.

8.39.7 Height of Buildings

The *height* of a *principal building* shall not exceed a maximum total *height* of 12 m.

8.39.8 Off-Street Parking

Off-*street* parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

No parking or loading spaces are permitted within 10.0 m of a property line.

8.39.9 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Where a *lot* in this zone adjoins a *street*, a landscaped area of at least 10.0 m in width extending along the entire frontage of the property on the *street* except for a roadway to the *street* shall be provided and maintained to the satisfaction of the *City*.
- (2) Where a *lot* adjoins a residentially zoned property, a landscaped screen, not less than 2.0 m in *height* and 10.0 m in width shall be provided and maintained to the satisfaction of the *City*.

- (3) Large surface parking areas should be broken down into smaller *parking lots* evenly dispersed throughout the development and integrated with planted landscaped areas. Tree planting is required in parking areas.
- (4) Direct and functional pedestrian pathways to connect *building* entrances to parking areas and sidewalks of the abutting streets shall be provided. Installation of features such as distinct paving, sidewalks, special *landscaping* with trees and benches, and overhead weather protection on exterior *building* walls where appropriate is required.

Part 35 - Comprehensive Development Eleven Zone (CD-11)

Glacier View Lodge (2450 Back Road)

8.40.1 Intent

The CD-11 Zone is intended to accommodate and regulate residential development for seniors for the properties described as:

- (1) *Lot A*, Sections 6 & 8, Comox District, Plan 35008;
- (2) *Lot 1*, Section 8, Comox District, Plan 2849 except part in Plan 35008; and,
- (3) *Lot 2*, Sections 6 & 8, Comox District, Plan 2849 except part in Plan 35008.

8.40.2 Permitted Uses

In the CD-11 Zone, the following uses are permitted and all other uses are prohibited within the area identified on Schedule 8A, Zoning Map, except as otherwise noted in this bylaw.

Primary uses:

- (1) *Single residential and duplex dwellings*
- (2) *Multi residential dwellings*
- (3) *Care facility*
- (4) *Community service*

Accessory uses:

- (1) *Day care*
- (2) *Financial institution*
- (3) *Office*
- (4) *Medical clinic*
- (5) *Restaurant*
- (6) *Retail*

8.40.3 Density

Lot coverage: maximum *lot coverage* of 20% for single-residential and *duplex* residential uses; 30% for other primary uses; and 40% for *accessory* uses. *Accessory* uses are limited to a maximum *floor area* of 70 m² per use.

Accessory buildings for *single residential* or *duplex* dwellings are limited to a maximum *floor area* of 25 m²

8.40.4 Setbacks

Notwithstanding any provisions of this Bylaw, any *yard setback* from private or public streets shall be 4.5 m except 6.0 m to face of *garage/carport*.

- (1) *Internal Side yard*:
 - 2.0 m for one-*storey* buildings
 - 3.0 m for two *storey* buildings
 - 6.0 m for greater than two *storey* buildings
 - 1.5 m for *accessory* buildings for single or *duplex* dwellings
- (2) *Internal Rear yard*:
 - 7.5 m
 - 1.5 m for *accessory* buildings for single or *duplex* dwellings

The required minimum *yard setback* along the exterior perimeter of the CD-11 zone is 12 m.

8.40.5 Height of Buildings

No *single residential* or *duplex* dwellings and subordinate uses shall exceed 8.0 m.

Accessory buildings: 4.5 m.

All other primary *permitted uses*: 16 m

8.40.6 Minimum Lot Size and Frontage for Subdivision

Minimum *Lot Size*: 1100 m²

Minimum *Frontage*: 30 m

8.40.7 Off-Street Parking and Loading

Notwithstanding any provisions of this Bylaw, the minimum number of off-*street parking spaces* for the following uses shall be provided as follows:

- (1) *Single residential* or *duplex* dwelling: 1 space per unit plus 1 visitor's space per 5 units
- (2) Multi residential dwelling: 1 space per unit plus 1 visitor's space per 5 units

All other uses (e.g. *care facility, community service*) shall be provided and maintained in accordance with the requirements of Division 7 Off-*Street* Parking and Loading Spaces of this Bylaw.

8.40.8 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) The *landscaping* shall be used to ensure privacy and to complement the overall development.
- (2) A landscaped area of at least 3.0 m in width, located within the property lines, shall be provided along all facing streets including internal streets. A landscaped buffer area of at least 12.0 m in width shall be provided along the external perimeter of zone.
- (3) Where any *permitted use* adjoins a *single residential* or *duplex* property, a landscaped area of not less than 2.0 m in width and a solid *fence* or *landscaping* of not less than 2.0 m in *height* shall be provided and maintained.

Part 36 - Comprehensive Development Twelve Zone (CD-12)

Muir Road/Caledon Crescent

8.41.1 Intent

The CD-12 Zone is intended to accommodate and regulate *single residential* dwellings for the property described as part of Lot B, Section 19, Comox District, Plan 25085

8.41.2 Permitted Uses

In the CD-12 Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) *Single residential* dwelling
- (2) *Accessory* buildings and structures
- (3) *Home occupation*

8.41.3 Density

The maximum number of *dwelling units* shall not exceed 16.

8.41.4 Minimum Lot Size

For the purposes of *subdivision*, the average *lot* size shall be one *lot* per 1525 m² with a minimum *lot* size of 1250 m².

8.41.5 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 20.0 m where a *lot* is located at the end of a cul-de-sac, the frontage shall not be less than 15.25 m.

8.41.6 Minimum Lot Depth

A *lot* shall have an average depth of not less than 30 m.

8.41.7 Lot Coverage

A *lot* shall not be covered by buildings and *accessory* buildings, excluding swimming pools, to a greater extent than 40% of the total area of the *lot*.

8.41.8 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front yard*: 7.5 m
- (2) *Rear yard*: 9.0 m
- (3) *Side yard*: The *side yard setbacks* shall be 2.0 m except where a *side yard* flanks a *street* in which case the minimum distance shall be 4.5 m.

8.41.9 Height of Buildings

The *height* of a *principal building* shall not exceed 9.0 m.

8.41.10 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*
- (2) Shall have a total *floor area* not exceeding 60 square m
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw
- (4) Shall be permitted at the front of a principal *residence* provided they shall conform to all relevant siting regulations of this bylaw
- (5) Shall not be located within 2.0 m from the side and rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5 m

8.41.11 Off-Street Parking

Off-*street* parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.41.12 Landscaping and Screening

Landscaping shall conform to Part 14 of this bylaw.

Part 37 - Comprehensive Development Fourteen Zone (CD-14)
Creekside Commons Co-housing (Lambert Drive)

8.42.1 Intent

The CD-14 Zone is intended to accommodate and regulate *co-housing* dwellings, a common use *building*, a common use workshop, covered parking and *accessory* uses for the property legally described as Lot 2, District Lot 230, Plan VIP79120.

8.42.2 Permitted Uses

In the CD-14 Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

2618

- (1) Strata *cluster housing* in the form of *duplex* dwellings
- (2) Common amenity *building* including shared kitchen and dining room, two guest room, washroom, laundry, day-care and children's play area, *accessory office* and meeting room, lounge, and library.
- (3) *Accessory* buildings used for a common use workshop, ground level parking, storage, greenhouses, recycling and composting
- (4) Outdoor recreation facilities in the form of a playground, *courtyard*, kitchen garden areas, and gazebo

2513

- (5) Common gardens
- (6) *Home Occupation*

8.42.3 Density

The maximum number of *dwelling units* shall not exceed 36 units in 18 duplexes.

8.42.4 Minimum Lot Size

For the purposes of *subdivision*, the minimum *lot* size is 3.5 hectares.

8.42.5 Minimum Lot Frontage

There is no minimum *lot* frontage requirement.

8.42.6 Lot Coverage

A *lot* shall not be covered by buildings and *accessory* buildings to a greater extent than 30% of the total area of the *lot*.

8.42.7 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front yard*: 7.0 m
- (2) *Rear yard*: 7.0 m
- (3) *Side yard*: 4.5 m

8.42.8 Height of Buildings

The *height* of a *principal building* shall not exceed 9.5 m and no *building* shall be more than two stories.

8.42.9 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*.
- (2) Each *dwelling unit* is permitted a private *accessory building* with a total *floor area* of 15 m² per *dwelling unit*.
- (3) *Accessory buildings* for common uses shall be limited to a total *floor area* of 1500 m².
- (4) Shall conform to all relevant siting regulations of this bylaw.
- (5) Shall not be located within 4.5 m from all *lot lines*.

8.42.10 Off-Street Parking

Off-*street* parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw

8.42.11 Landscaping and Screening

Landscaping shall conform to Part 14 of this bylaw.

Part 38 - Comprehensive Development Fifteen Zone (CD-15)

Southwind Development (Robert Lang & 1st Street)

8.43.1 Intent

The CD-15 Zone is intended to accommodate the development of a combination of *Single residential Dwellings*, Bare land Strata *Single residential Dwellings* and Patio Home Style Multi-Residential Development for the properties legally described as *Lot B*, District *Lot 118*, Comox District, Plan VIP60328, except parts in Plans VIP61633 and VIP73074 and *Lot 1*, District *Lot 118*, Comox District, Plan VIP61663.

8.43.2 Permitted Uses

In the CD-15 Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

3071

- (1) *Single residential dwellings*
- (2) *Secondary suite*
- (3) Bare land strata *single residential dwellings*
- (4) Multi residential dwellings
- (5) *Home occupation*
- (6) *Accessory buildings and structures*

8.43.3 Density

The maximum number of *dwelling units* shall not exceed 80 units.

8.43.4 Minimum Lot Size

For the purposes of *subdivision*, the minimum *lot* size is as follows:

- | | |
|--|---------------------|
| (1) <i>Single residential dwelling</i> : | 545 m ² |
| (2) Bare land strata residential dwelling: | 450 m ² |
| (3) Multi residential dwelling: | 1100 m ² |

8.43.5 Minimum Lot Frontage

For the purposes of *subdivision*, the minimum *lot* frontage is as follows:

- | | |
|--|--------------------------------|
| (1) <i>Single residential dwelling</i> : | 13 m |
| (2) Bare land strata residential dwelling: | 10.0 m with an average of 15 m |
| (3) Multi residential dwelling: | 20 m |

8.43.6 Lot Coverage

A *lot* shall not be covered by buildings and *accessory buildings* to a greater extent than 40% of the total area of the *lot*.

8.43.7 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

<u>Use</u>	<u>Front</u>	<u>Rear</u>	<u>Side</u>	<u>Exterior Side</u>
<i>Single residential Dwelling:</i>	4.5 m 6 m to <i>garage</i> face or carport	7.5 m	1.5 m	4.5 m
Bare land Strata <i>Single residential Dwelling:</i>	4.5 m 6.0 m to <i>garage</i> face or carport	7.5 m	1.5 m	4.5 m
Multi Residential Dwelling:	4.5 m 6.0 m to <i>garage</i> face or carport	6 m	4.5 m	4.5 m

8.43.8 Height of Buildings

Single residential Dwelling – 8 m.

Bare land Strata *Single residential Dwelling* – 8 m

Multi Residential Dwelling – on any *lot* having four or more *dwelling units*, a maximum of 70% of the *dwelling units* may have a *building height* not exceeding 8.0 m and the remainder of the *dwelling units* shall have a *building height* not exceeding 4.5 m.

8.43.9 Usable Open Space

Usable open space shall be provided on a *lot* in the amount of 30 m² for each one-bedroom *dwelling unit* and 50 m² for each *dwelling unit* with two or more bedroom.

8.43.10 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*.
- (2) Shall have a *floor area* not exceeding 46.5 m² or 10% of the *rear yard*, whichever is greater.
- (3) Shall be permitted in the front, side and *rear yard* provided they conform to all relevant siting regulations of this bylaw.
- (4) Shall not be located within 1.5 m from the side or rear *lot line* except where the side or rear *lot line* flanks a *street*, in which case the minimum *setback* distance shall be 4.5 m.

8.43.11 Off-Street Parking

Off-*street* parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

8.43.12 Landscaping and Screening for Multi Residential Development

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) Any part of a *lot* not used for *building*, parking, loading facilities or outdoor recreation shall include a landscaped area of at least 2.0 m in width and *height* and separated from the paved areas by a concrete curb or other barrier.
- (2) Where a *lot* in this zone adjoins a *street*, a landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the *street* shall be provided and maintained to the satisfaction of the *City*.
- (3) Where a *lot* adjoins a *single residential* or *duplex* residential zoned property a landscaped screen, *fence* or a combination thereof of not less than 2.0 m in *height* and 3.0 m width shall be provided and maintained to the satisfaction of the *City*.

Part 39 - Comprehensive Development Sixteen Zone (CD-16)

Lot 2, District Lot 157, Plan VIP59557 (2485 Idiens Way)

8.44.1 Intent

The CD-16 Zone is intended to accommodate the development of a Multi Residential Development for the property legally described as Lot 2, District Lot 157, Comox District, Plan VIP59557 (2485 Idiens Way).

8.44.2 Permitted Uses

In the CD-16 Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

1. Multi residential dwellings
2. Accessory buildings and structures

8.44.3 Density

The maximum number of dwelling units shall not exceed 28 units.

8.44.4 Minimum Lot Size

For the purposes of subdivision, the minimum lot size is 1250 m².

8.44.5 Minimum Lot Frontage

For the purposes of subdivision, the minimum lot frontage is 30 metres.

8.44.6 Lot Coverage

A lot shall not be covered by buildings and accessory buildings to a greater extent than 40% of the total area of the lot.

8.44.7 Yards

Except where otherwise specified in this bylaw the following minimum building setbacks shall apply:

- | | | |
|-----|-------------------------|------------|
| (1) | Front Yard (Idiens Way) | 7.5 metres |
| (2) | Side Yard | 12 metres |
| (3) | Rear Yard | 12 metres |

8.44.8 Height of Buildings

The height of a principle building shall not exceed 10 metres.

8.44.9 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in height.
- (2) Shall have a floor area not exceeding 50 m².
- (3) Shall not be located within 4.5 m from the side or rear lot line.

8.44.10 Landscaping and Screening for Multi-Family Development

Any part of a lot not used for building, parking, loading facilities or outdoor recreation shall include a landscaped area of at least 2 m in width and height and separated from the paved areas by a concrete curb or other barrier.

Where a lot adjoins Lerwick Road a continuous landscaped area of at least 7.5 m in width extending along the entire frontage of the property on the street shall be provided and maintained to the satisfaction of the City.

Where a lot in this zone adjoins a street, a continuous landscaped area of at least 4.5 m in width extending along the entire frontage of the property on the street shall be provided and maintained to the satisfaction of the City.

Where a lot adjoins a residentially zoned property a landscaped screen, fence or a combination thereof of not less than 2 m in height and 4.5 m in width shall be provided and maintained to the satisfaction of the City.

8.44.11 Usable Open Space

Usable open space shall be provided on a lot in the amount of 50% of the site area.

8.44.12 Off-Street Parking

Off-street parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

Part 40 - Comprehensive Development Seventeen Zone (CD-17)
Lot 8, District Lot 155, Comox District, Plan 1241, Except Part in
Plan 40343 and Lot 3, District Lot 155, Comox District, Plan 1241
(190 Powerhouse Road)

8.45.1 Intent

The CD-17 Zone is intended to accommodate the development of a Bare Land Strata Development for the property legally described as Lot 8, District Lot 155, Comox District, Plan 1241, Except Part in Plan 40343 and Lot 3, District Lot 155, Comox District, Plan 1241 (190 Powerhouse Road).

8.45.2 Permitted Uses

In the CD-17 Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) Single family residential
- (2) Accessory buildings and structures

8.45.3 Density

The maximum number of dwelling units in this zone shall not exceed 69 units.

8.45.4 Minimum Lot Size

For the purposes of subdivision, the minimum lot size shall be 470 m².

8.46.4 Minimum Lot Frontage

For the purposes of subdivision, the minimum lot frontage is 15 metres. Except for lots which front a cul-de-sac or curved road way lot in which case the minimum lot frontage is 7 metres.

8.45.6 Lot Coverage

A lot shall not be covered by buildings and accessory buildings to a greater extent than 40% of the total area of the lot.

8.45.7 Yards

Except where otherwise specified in this bylaw the following minimum building setbacks shall apply:

- | | |
|----------------|--|
| (1) Front Yard | 6.0 m |
| (2) Side Yard | The side yard setbacks shall total 3.5 m with a minimum side yard setback on one side of 1.5 m except where a side yard flanks a street in which case the minimum distance shall be 4.5 m. |
| (4) Rear Yard | 6.0 m |

8.45.8 Height of Buildings

The height of a principle building shall not exceed 9.0 m.

8.45.9 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in height.
- (2) Shall have a floor area not exceeding 50.0 m².
- (3) Shall not be located within 1.5 m from the side or rear lot line.

8.45.10 Landscaping and Screening

Any part of a lot not used for a residential building, an accessory building, parking, strata facility or outdoor recreation shall be landscaped.

8.45.11 Usable Open Space

Useable open space is provided in the adjacent public park facility encompassing the Morrison Creek wetlands.

8.45.12 Off-Street Parking

Off-street parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw

Part 41 - Comprehensive Development Nineteen Zone (CD-19)

**Lot 1, District Lot 96, Comox District, Plan 2963, Except that Part in Plan 20420;
That Part of Lot 2, District Lot 96, Comox District, Plan 2963 Lying to the South East
of a Boundary Parallel to and Perpendicularly Distant 132 feet from the South
Easterly Boundary of Said Lot 2;**

**That Part of Lot 2, District Lot 96, Comox District, Plan 2963 Lying to the North
West of a Boundary Parallel to and Perpendicularly Distant 132 feet from the South
Easterly Boundary of Said Lot 2 (1360, 1470, 1480 Arden Road)**

8.46.1 Intent

The CD-19 Zone is intended to accommodate a multi-residential development for the property identified on Attachment A and commonly described as 1360, 1470 and 1480 Arden Road. No development or land alteration may take place within the CD-19 Zone without first obtaining a development permit the particulars of which must conform to the Environmental and Multi-Residential Development Permit Area Guidelines.

8.46.2 Permitted Uses

In the CD-19 Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- 1) Multi-residential dwelling
- 2) Single residential dwelling
- 3) Accessory buildings and structures

8.46.3 Density

The maximum number of dwelling units in this zone shall not exceed a total of 102.

8.46.4 Area CD-19A

Permitted Uses:

Multi Residential

Density:

The maximum number of residential units shall not exceed 8 within a single building.

The maximum total number of residential units shall not exceed 16.

Lot Coverage:

A lot shall not be covered by buildings to a greater extent than 40% of the total area of a lot.

Height:

The maximum height of a building shall not exceed 10 metres.

Setbacks:

Except as otherwise specified in this bylaw, the following minimum setback requirements shall apply:

Front Yard	7.5 m
Rear Yard	9.0 m
Side Yard	4.5 m

8.46.5 Area CD-19B

Permitted Uses:

1. Multi residential dwelling
2. Single residential dwelling

Density:

The maximum number of residential dwellings shall not exceed 18.

Lot Coverage:

A lot shall not be covered by buildings to a greater extent than 40% of the total area of a lot.

Height:

The maximum height of a building shall not exceed 10 metres.

Setbacks:

Except as otherwise specified in this bylaw, the following minimum setback requirements shall apply:

Front Yard	7.5 m
Rear Yard	4.5 m
Side Yard	4.5 m

8.46.6 Area CD-19C

Permitted Uses:

1. Single residential dwelling
2. Multi residential dwelling

Density:

The maximum number of residential dwellings shall not exceed 72. No more than 32 residential dwellings shall be permitted within a single building.

Lot Coverage:

A lot shall not be covered by buildings to a greater extent than 40% of the total area of a lot.

Height:

The maximum height of a building shall not exceed 13 metres.

Setbacks:

Except as otherwise specified in this bylaw, the following minimum setback requirements shall apply:

Front Yard	7.5 m
Rear Yard	6.0 m
Side Yard	4.5 m

2685 **8.46.7 Accessory Buildings and Structures**


Accessory buildings and structures shall conform to the following regulations:

- (1) A maximum *height* of 4.5 m
- (2) A maximum *floor area* of 10.0 m²
- (3) Shall not be located within 1.5 m of any lot line, excluding a street, in which case the minimum setback shall be 7.5 m

2685 **8.46.8 Off-Street Parking and Loading**

Off-street parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

SCHEDULE A



**Part 42 - Comprehensive Development Twenty-One Zone (CD- 21)
(Buckstone Road)**

8.48.1 Intent

2771

The CD-21 Zone is intended to provide for the siting and development of *single residential* and *duplex* buildings. Single family residential with secondary suites is permitted throughout the site. Duplex units or *carriage houses* are permitted on all lots that have double frontages and 900 m² or greater lot size for a duplex and 750 m² or greater lot size for a *carriage house*. *Carriage houses* are permitted on properties that have lane access and frontage onto Buckstone Road or a corner lot, with lot size of 750 m² or greater and may be connected to the principal residence by a ground level breezeway or hallway. The intent is to create greater housing diversity and housing market affordability, while retaining the aesthetic of a residential neighborhood.

8.48.2 Permitted Uses

In the CD-21 Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

1. *Single residential* means a *dwelling unit*
2. *Accessory buildings and structures*
3. *Duplex* means a residential building containing two *dwelling units*
4. *Home occupation*
5. “*Secondary Suite*”
6. “*Carriage House*” means an additional *dwelling unit*:
 - i. which is permitted on a *lot* which abuts a rear lane and is greater than 750 m² or on a *lot* which has double frontage (i.e. a corner lot)
 - ii. which is located above a *garage*
 - iii. having a total floor area of not more than 90.0 m²
 - iv. which may have internal or external access and may be connected to the primary residence

2771

8.48.3 Minimum Lot Size

1. *Single Family*
 - (a) a single-family *lot* shall have an area of not less than 600 m²
2. *Duplex*
 - (a) a duplex *lot* shall have an area on not less than 900 m² and must be a corner or double frontage *lot*
3. *Carriage House*
 - (a) a *carriage house* may be located on a lot of not less than 750 m² and must have lane access and frontage onto Buckstone Road or a corner lot

2771

8.48.4 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 16.0 m, except for a corner *lot* where the frontage shall be not less than 20.0 m.

8.48.5 Minimum Lot Depth

A *lot* shall have a depth of not less than 26.0 m.

8.48.6 Lot Coverage

A *lot* shall not be covered by buildings and *accessory* buildings to a greater extent than 60% of the total area of the *lot*.

8.48.7 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

(a) Single Family Residence or Duplex

- | | | |
|------|-----------------------|--|
| 2724 | (1) <i>Front Yard</i> | 7.5 metres except where a <i>lot</i> fronts onto Buckstone Road in which case the minimum distance can be 4.5 metres. |
| 2724 | (2) <i>Rear Yard</i> | 9.0 metres except where a <i>lot</i> is less than 36 metres in depth in Which case the minimum distance can be 7.5 metres. |
| | (3) <i>Side Yard</i> | The side yard setbacks shall total 4.5 m with a minimum <i>side yard setback</i> on one side of 1.5 m except where a <i>side yard</i> flanks a street in which case the minimum distance shall be 4.5 m. |

(b) Carriage

- | | | |
|------|-----------------------|--|
| 2771 | (1) <i>Front Yard</i> | 7.5 metres |
| 2771 | (2) <i>Rear Yard</i> | 2.0 metres |
| 2771 | (3) <i>Side Yard</i> | The side yard setbacks shall total 3.0 m with a minimum <i>side yard setback</i> on one side of 1.5 m. |

8.48.8 Height of Buildings

- | | | |
|------|-----|---|
| 2724 | (1) | The height of a <i>principle building</i> shall not exceed 9.0 m. |
| 2771 | (2) | The height of a <i>Carriage House</i> shall not exceed 7.5 m. |


8.48.9 Accessory Buildings and Accessory Structures

- | | | |
|------|-----|---|
| | (1) | Shall not exceed 4.5 m in <i>height</i> . |
| | (2) | Shall have a total <i>building area</i> not exceeding 50 m ² or 10% of the <i>rear yard</i> , whichever is greater. |
| | (3) | Shall be permitted in the <i>side</i> and <i>rear yard</i> provided they shall conform to all relevant siting regulations of this bylaw. |
| | (4) | Shall be permitted at the front of a principal <i>residence</i> provided they shall conform to all relevant siting regulations of this bylaw. |
| 2771 | (5) | Shall not be located within the minimum 1.5 m <i>side yard</i> or rear <i>lot line setback</i> except where the side or rear <i>lot line</i> flanks a <i>street</i> , excluding a lane in which case the minimum <i>yard</i> distance shall be 4.5 m. |

8.48.10 Off-Street Parking

Off-street parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw. No more than 50% of any *yard* area or frontage on a *street* or lane shall be used for off-*street* parking.

Schedule A



Part 43 - Comprehensive Development Twenty-Two Zone (CD-22) (2880 Arden Road)

8.49.1 Intent

The CD-22 Zone is intended to accommodate the development of a Bare Land Strata Development for the property legally described as Lot 1, DL 231, Comox District, Plan 2152 Except Part in Plans VIP68939 and VIP81437 (2880 Arden Road). Strata subdivision shall conform generally to Schedule A.

8.49.2 Permitted Uses

In the CD-22 Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

1. *Single residential* dwelling
2. *Duplex* residential dwelling on lot 10 only
3. *Accessory* buildings and structures

8.49.3 Density

The maximum number of dwelling units in this zone shall not exceed 26 and shall be composed of 24 single residential dwellings and one duplex residential dwelling to be located on lot 10 as per Schedule A.

8.49.4 Minimum Lot Size

For the purposes of subdivision, the minimum lot size shall be 450 m².

8.49.5 Minimum Lot Frontage

For the purposes of subdivision, the minimum lot frontage is 16 metres. Except for lots which front a cul-de-sac or curved road way lot in which case the minimum lot frontage is 10 metres; for corner lots the lot frontage may be reduced to 12 metres for one frontage only.

8.49.6 Lot Coverage

A lot shall not be covered by buildings and accessory buildings to a greater extent than 50% of the total area of the lot.

8.49.7 Setbacks

Except where otherwise specified in this bylaw the following minimum building setbacks shall apply:

- | | |
|----------------|--|
| (1) Front Yard | 6.0 m |
| (2) Side Yard | The side yard setbacks shall total 3.0 m with a minimum side yard setback on one side of 1.5 m except where a side yard flanks a street in which case the minimum distance shall be 4.5 m. |
| (3) Rear Yard | 4.0 m |

8.49.8 Height of Buildings

The height of a principle building shall not exceed 9.0 m.

8.49.9 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in height.
- (2) Shall have a floor area not exceeding 50.0 m².
- (3) Shall not be located within 1.5 m from the side or rear lot line.

8.49.10 Landscaping and Screening

Any part of a lot not used for a residential building, an accessory building, parking, strata facility or outdoor recreation shall be landscaped.


8.49.11 Usable Open Space

Useable open space is provided in the adjacent public park facility encompassing the Arden corridor wetlands.

8.49.12 Off-Street Parking

Off-street parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.

Schedule A



Part 44 - Comprehensive Development Twenty-Three Zone (CD- 23)
(1921, 1993 Arden Road & 2459 Cumberland Road)

8.50.1 Intent

The CD-23 Zone is intended to accommodate a mixed use residential development on the properties legally described as part of Lot 2, District Lot 138, Comox District, Plan 14210, Lot 1, District Lot 138, Comox District, Plan 40239, and Lot B, District Lot 138, Comox District, Plan 2607, Except that part in Plan 40239 and in general accordance with the plan attached as Schedule A.

8.50.2 CD-23A

(1) Permitted Uses

The following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

1. *Single residential dwelling*
2. *Secondary suite*
3. *Duplex residential dwelling*
4. *Accessory buildings and structures*
5. *Home occupation*

(2) Minimum Lot Size

- a) *Single Family Residential:* 500m²
- b) *Duplex:* 900m²

(3) Minimum Lot Frontage

A lot shall have a frontage of not less than 18.0m, except for a *corner lot* where the frontage shall be not less than 20.0m.

(4) Minimum Lot Depth

A lot shall have a depth of not less than 30.0 m

(5) Lot Coverage

A lot shall not be covered by *buildings* to a greater extent than 40% of the total *lot area*.

(6) Setbacks

- a) *Front Yard* 7.5 metres
- b) *Rear Yard* 9.0 metres
- c) *Side Yard* The *side yard setbacks* shall total 4.5 m with a minimum *side yard setback* on one side of 1.5 m except where a *side yard* flanks a *street* in which case the minimum distance shall be 4.5 m.

(7) Height

The maximum *height* of a *principle building* shall not exceed 9 metres

8.50.3 CD-23B

(1) Permitted Uses

The following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

1. *Single residential dwelling* with or without a *secondary suite*
2. *Accessory buildings and structures*
3. *Home occupation*

(2) Minimum Lot Size

The minimum *lot* size for all lots in this area is 400m²

(3) Minimum Lot Frontage

A *lot* shall have a frontage of not less than 13.0m, except for a corner lot where the frontage shall be not less than 15.0m.

(4) Minimum Lot Depth

A *lot* shall have a depth of not less than 30.0 m

(5) Lot Coverage

A *lot* shall not be covered by *buildings* to a greater extent than 40% of the total *lot* area.

(6) Setbacks

- a) *Front Yard* 4.5 metres
- b) *Rear Yard* 7.5 metres
- c) *Side Yard* 1.5 m except where a *side yard* flanks a *street* in which case the minimum distance shall be 3.5 m.

(7) Height

The maximum *height* of a *principle building* shall not exceed 9 metres


8.50.4 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*.
- (2) Shall have a total *building area* not exceeding 50 m² or 10% of the *rear yard*, whichever is greater.
- (3) Shall be permitted in the *side* and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw.
- (4) Shall be permitted at the front of a principal *residence* provided they shall conform to all relevant siting regulations of this bylaw.
- (5) Shall not be located within 1.5 m from the side or rear *lot line* except where the side or *rear yard* flanks a *street*, excluding a lane, in which case the minimum *yard* distance shall be 4.5m. Within the CD-23B area the minimum interior *side yard setback* shall be 1.0 metres.

8.50.5 Off-Street Parking

Off-street parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw. No more than 50% of any yard area or frontage on a street or lane shall be used for off-street parking.

Schedule A



Part 45 - Comprehensive Development Twenty-Four Zone (CD- 24) (2525 Mission Road)

8.51.1 Intent

The CD-24 Zone is intended to accommodate the development of a professional commercial centre on the property legally described as Lot 2, District Lot 236, Comox District, Plan VIP70439.

8.51.2 Permitted Uses

The following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

1. *Accessory building* and uses
2. *Medical clinic*
3. Laboratory
4. *Educational facility*
5. *Office*
6. *Financial institution*
7. *Fitness facility*
8. *General service*
9. *Personal service*
10. *Community service*
11. *Retail stores* limited to 2000 m²
12. *Studio*
13. Seniors Housing and Care Facilities
14. *Assembly hall*
15. Bakery and deli
16. Barber shop and beauty salon
17. *Day care*
18. Florist
19. *Facility for adults with a disability*
20. *Laundromat* and *dry cleaning*
21. Printing and publishing
22. Restaurant
23. *Parking lot*
24. *Veterinary clinic*
25. Combined commercial-residential use subject to the commercial use being restricted to *retail*, restaurants, *offices* (including *financial institutions*) and *studios*. Residential units must be contained within a dual use building and shall be located above storeys used for commercial purposes, and no storey can be used for both commercial and residential purposes
26. For clarity the following uses are specifically not permitted:
 - a) Convenience store
 - b) Automobile service station
 - c) Automobile sales and repairs
 - d) Building supply store

- e) Hotel/Motel
- f) Grocery store
- g) Enclosed storage building including warehouse and storage yard
- h) Methadone clinic

8.51.3 Condition of Use

Garbage containers, recycling containers, storage facilities, parking, and loading facilities shall not be located within any required *setback* as specified in Section 8.51.8.

8.51.4 Lot Coverage

A *lot* shall not be covered by buildings and *accessory* buildings to a greater extent than 40% of the total area of the *lot*.

8.51.5 Floor Area Ratio

The maximum floor area ratio shall not exceed 0.7:1

8.51.6 Minimum Lot Size

A lot shall have an area of not less than 2000 m²

8.51.7 Minimum Lot Frontage

A lot shall have a frontage of not less than 30m

8.51.8 Setbacks

Except where otherwise specified in this bylaw the following minimum building setbacks shall apply:

- | | |
|----------------|------|
| (1) Front Yard | 7.5m |
| (2) Side Yard | 7.5m |
| (3) Rear Yard | 7.5m |

Support columns may project into the minimum required yards to a maximum projection of 1m

8.51.9 Height of Building

Maximum *height* of a *building* shall not exceed 16.0 m with the exception of the core area which may be 19.0m in *height*.

8.51.10 Off-Street Parking and Loading

Off-street parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw unless otherwise specified.

No parking or loading area may be located within 2.0m of a property line.

A minimum of 2 loading bays are required on the site

8.51.11 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) A minimum 7.5m landscape area is required between all building faces and the adjacent property lines. Hard landscape features such as patios and staff seating areas are permitted within this landscape area.
- (2) To separate parking, internal roads, services or storage areas from adjacent properties, a landscaped buffer area of at least 2.0 m in width and 2.0 m in *height* shall be provided along the inside of all property lines.
- (3) Loading areas, garbage and recycling containers shall be screened and gated to a minimum *height* of 2 m by a *landscaping* screen or solid decorative *fence* or a combination thereof.

8.51.12 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5 m in *height*.
- (2) Shall have a total *building area* not exceeding 50 m² or 10% of the *rear yard*, whichever is greater.
- (3) Shall be permitted in the *side* and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw.
- (4) Shall not be permitted at the front of a principal *building*.

Part 46 - Comprehensive Development Twenty-Five Zone (CD- 25)

Lot A, District Lot 230, Comox District, Plan 48707; Parcel A (DD 10616N) of Lot 4, District Lot 230, Comox District, Plan 2152, Except that Part Shown Outlined in Red on Plan 688R and Except that Part in Plan 48707; That Part of Parcel A (DD 10616N) of Lot 4, District Lot 230, Comox District, Plan 2152 Shown Outlined in Red on Plan 688R, Except Parts in Plans 6030 and 23672 (2368, 2498 and 2650 Arden Road)

8.52.1 Intent

The CD-25 Zone is intended to accommodate two strata developments on the property identified on Attachment A and commonly described as 2368, 2498 and 2650 Arden Road, Courtenay, BC. No development or land alteration may take place within the CD-25 Zone without first obtaining a development permit the particulars of which must conform to the Environmental and Multi-Residential Development Permit Area Guidelines.

8.52.2 Permitted Uses

In the CD-25 Zone, the following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

1. Single residential dwelling
2. Duplex residential dwelling
3. Triplex residential dwelling

8.52.3 Density

The maximum number of individual dwelling units in this zone shall not exceed a total of 46. This density may be achieved through combinations of single, duplex and triplex residential units.

8.52.4 Setbacks

1. Except where otherwise specified in this bylaw the building setback from all property lines shall be 6m.
2. The minimum setback between residential buildings shall not be less than 5m.
3. The minimum setback for a residential building from a strata road shall not be less than 6m.

8.52.5 Height of Buildings

The maximum height for any building shall not exceed 8m.

Attachment A



**Part 47 - Comprehensive Development Twenty-Six Zone (CD-26)
(3040 & 3070 Kilpatrick Ave)****8.53.1 Intent**

The CD-26 Zone is intended to accommodate a use mixed commercial and residential development on the properties legally described as Lot B, Section 67, Comox District, Plan VIP81460 and Lot 3, Section 67, Comox District, Plan VIP35438. These properties shall be developed substantially in accordance with Schedules A, B, C, and D which form part of this zone.

8.53.2 Permitted Uses

The following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

1. *General Service*
2. *Medical Clinic*
3. *Financial Institution*
4. *Office*
5. *Restaurant*
6. *Personal Service*
7. *Retail*
8. *Fitness Facility*
9. *Studio*
10. *Community Service*
11. *Liquor Store*
12. *Multi Residential*
13. *Home Occupation*

8.53.3 Lot Coverage

A *lot* shall not be covered by buildings to a greater extent than 40% of the total area of the *lot*.

8.53.4 Floor Area Ratio

The maximum *floor area ratio* shall not exceed 1.2.

8.53.5 Minimum Lot Size

A *lot* shall have an area of not less than 1.0 hectare.

8.53.6 Minimum Lot Frontage

A *lot* shall have a *frontage* of not less than 30.0 m

8.53.7 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front Yard* 7.5 m for that portion of a building with a height less than 9.0 m
 11.5 m for that portion of a building with a height greater than 9.0 m
- (2) *Rear Yard* 7.5 m except for underground parking structures which shall be a minimum of 0.6 m.

Notwithstanding the required *rear yard setback* specified above, the minimum *rear yard setback* can be reduced to 4.5 m for a building including balconies or to 3.2 m for a staircase for that portion of Building 1 shown in Schedule A.

- (3) *Side Yard* 4.5 m except where a building greater than 4 *storeys* abuts a residential use, in which case the minimum distance shall be 6.5 m for the 5th storey

Notwithstanding the required *side yard setback* specified above, balconies may extend up to 1.2 m into the *side yard setback* along the north property line and up to 0.8 m along the southern property line.

Notwithstanding the required front, rear, and side yard setbacks specified above, roof overhangs may extend up to 0.76 m into the required setback.

8.53.8 Height of Building

Maximum *building height* shall be in accordance with Schedule B and includes the elevator and roof top mechanical systems. For clarity, the curb height is determined as the average curb height along the lot frontage. For Buildings 1 and 2, Lot 3 of Plan VIP35438 and for Building 3, Lot B of Plan VIP81460.

- (1) Building 1 – 10.5 m to roof parapet, 12.5 m to top of elevator
- (2) Building 2 – 12.5 m to roof parapet, 14.5 m to top of elevator
- (3) Building 3 – 8.5 m

8.53.9 Useable Open Space

- (1) A minimum of 1,930 m² of *useable open space* must be provided as shown in Schedule B. For clarity this includes common outdoor areas and private balconies or patios.
- (2) A walkway connection must be provided on the site between Cliffe Avenue Greenway and Kilpatrick Avenue as shown in Schedule A.

8.53.10 Accessory Structures

- (1) Shall not be permitted except for waste and recycling facilities
- (2) Shall not be permitted in the *front* or *rear yard*
- (3) Shall not be located within 1.5 m of the *side lot line* abutting a commercial use or within 4.5 m of a *side lot line* abutting a residential use or *street*, except for underground garbage and recycling structures which shall be located a minimum of 0.6 m from the *side lot line*.

8.53.11 Off-Street Parking and Loading

Off-street parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw except:

- (1) For multi residential uses parking shall be provided at a rate of 1.3 *parking spaces* per *dwelling unit* inclusive of visitor parking;
- (2) For general commercial uses parking shall be provided at a rate of 1.0 *parking spaces* for every 30 m² of *floor area*;
- (3) For restaurants with a drive-thru facility parking shall be provided at a rate of 1.0 *parking spaces* for every 10 m² of *floor area*.
- (4) Minimum parking stall dimensions are 2.6 m in width and 5.5 m in length for standard stalls
- (5) Minimum aisle width in the underground parking structure can be reduced to 6.7 m in accordance with Schedule C
- (6) No more than 25% of parking spaces can be designated as small car parking spaces

8.53.12 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) A landscaped area of not less than 4.0 m in width shall be provided inside all property lines adjoining residential use and public parkland except reduced widths shown in Schedule A.
- (2) A landscaped area of not less than 3.0 m in width shall be provided inside all side lot lines adjacent to commercial uses.
- (3) Where a *lot* in this zone adjoins a *street*, a landscaped area of at least 7.5 m in width extending along the entire frontage of the property shall be provided inside the property line.
- (4) Storage areas, garbage and recycling containers shall be screened and gated to a minimum *height* of 2 m by a *landscaping* screen or solid decorative *fence* or a combination thereof.



04.17.2017
1.2
 studioone
 architecture inc.

PROPOSED MIXED USE DEVELOPMENT 3040 & 3070 KILPATRICK AVE COURTENAY, B.C. Aug. 11, 2017

SITE PLAN
 SCALE: 1"=50'


SCHEDULE A

Note: Please refer to full size drawings in file 3360-20-1611



SCHEDULE B

Note: Please refer to full size drawings in file 3360-20-1611




SCHEDULE C

Note: Please refer to full size drawings in file 3360-20-1611



South Elevation Building 2
1 : 500

North Elevation Building 2
1 : 500



East Elevation Building 2
1 : 500




West Elevation Building 2
1 : 500


- 1- CEMENT COLOR: C
- 2- CEMENT COLOR: C
- 3- CEMENT COLOR: C
- 4- CEMENT COLOR: C
- 5- ARCHITECT COLOR: C
- 6- CULTURE ASPEN C
- 7- VINYL DO COLOR: V
- 8- ALUMINIUM
- 9- METAL BZ COLOR: E

SCHEDULE C


Note: Please refer to full size drawings in file 3360-20-1611



North Elevation Building 3
1 : 500




South Elevation Building 3
1 : 500



West Elevation Building 3
1 : 500


- 1- CEMENTITIOUS SIDING PANELS PAINTED
COLOR: CLV 11411N OR SIMILAR
- 2- CEMENTITIOUS SIDING PANELS PAINTED
COLOR: CL 1656N OR SIMILAR
- 3- CEMENTITIOUS SIDING BOARDS OR PANELS PAINTED
COLOR: CL 2932W OR SIMILAR
- 4- CEMENTITIOUS SIDING PANELS PAINTED
COLOR: CLC 1288N OR SIMILAR
- 5- ARCHITECTURAL FINISH EXPOSED CONCRETE PAINT
COLOR: CL 3214M OR SIMILAR
- 6- CULTURED STONE CLADDING
ASPEN COUNTRY OR SIMILAR
- 7- VINYL DOUBLE GLAZED WINDOWS
COLOR: WHITE FRAME
- 8- ALUMINUM STOREFRONT WINDOWS AND DOORS
COLOR: BLACK



East Elevation Building 3
1 : 500

SCHEDULE C

Note: Please refer to full size drawings in file 3360-20-1611



U/G PARKING PLAN
SCALE: 1:500

PROPOSED MIXED USE DEVELOPMENT | 3040 & 3070 KILPATRICK AVE | COURTENAY, B.C. | Aug. 11, 2017

studioone
architecture inc.

1.4

SCHEDULE D

Note: Please refer to full size drawings in file 3360-20-1611

Attachment A

Part 48 - Comprehensive Development Twenty-Six A Zone (CD- 26A) (3040 Kilpatrick Ave.)

8.53.13 Intent

The CD-26A Zone is intended to accommodate a multi residential development on the property legally described as Lot 1, Section 67, Comox District, Plan EPP79267 Except Air Space Plan EPP81977. This property shall be developed substantially in accordance with Schedules A, B, and C, which form part of this zone

8.53.14 Permitted Uses

The following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) *Multi Residential*
- (2) *Home Occupation*

8.53.15 Lot Coverage

A *lot* shall not be covered by buildings to a greater extent than 20% of the total area of the *lot*

8.53.16 Floor Area Ratio

The maximum *floor area ratio* shall not exceed 0.82

8.53.17 Minimum Lot Size

A *lot* shall have an area of not less than 0.40 hectares

8.53.18 Minimum Lot Frontage

A *lot* shall have a *frontage* of not less than 60.0 m

8.53.19 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front Yard*: 7.5 m for that portion of a building with a height less than 11.5 m and for railings above and affixed to said portion
17.0 m for that portion of a building with a height greater than 11.5 m
Despite the required *front yard setbacks* above, architectural fence details may project into the front yard setback up to 1.5 m with a height up to 2.0 m
- (2) *Rear Yard*: 18.0 m except for underground parking structures which shall be at least 14.0 m

- (3) *Side Yard*: 9.5 m north side except for underground parking structure which shall be at least 6.5 m
13.0 m south side

8.53.20 Height of Buildings

Maximum *building height* shall be in accordance with Schedule B and includes the elevator and roof top mechanical systems. Maximum *building height* is 15.0 m to roof parapet and 17.0 m to top of elevator measured from curb height. For clarity, the curb height is determined as the average curb height along the lot frontage

8.53.21 Useable Open Space

Useable open space must be provided and include at minimum:

- (1) 70 m² play area as shown in Schedule A
- (2) 250 m² rooftop amenity area
- (3) Patios or balconies for averaging 9 m² per unit, with a minimum size of 4.5 m²

8.53.22 Off-Street Parking and Loading

Off-street parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw except:

- (1) 52 *parking spaces* shall be provided for 41 dwelling units on the property and corresponding visitor parking
- (2) 33 *parking spaces* shall be provided for 3080 Kilpatrick Avenue commercial and residential use
- (3) Minimum parking stall dimensions are 2.6 m in width and 5.5 m in length for standard stalls
- (4) Minimum aisle width in the underground parking structure can be reduced to 6.7 m in accordance with Schedule C
- (5) Minimum additional space for *parking spaces* and maneuvering aisles where abutting a wall or building can be reduced in accordance with Schedule C
- (6) No more than 25% of *parking spaces* can be designated as small car *parking spaces*
- (7) Bicycle parking facilities must be provided at a rate of one secure stall per unit


8.53.23 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) A landscaped area of not less than 4.0 m in width shall be provided inside all property lines adjoining residential use and public parkland except reduced widths shown in Schedule A
- (2) Where a *lot* in this zone adjoins a *street*, a landscaped area of at least 7.5 m in width extending along the entire frontage of the property shall be provided inside the property line except reduced widths shown in Schedule A
- (3) Storage areas, garbage and recycling containers shall be screened and gated to a minimum *height* of 2 m by a *landscaping* screen or solid decorative *fence* or a combination thereof.

Schedule A


Note: Please refer to full size drawings in file 3360-20-2102



PROJECT TITLE		NEWPORT VILLAGE DEVELOPMENTS LTD	
CLIENT		NEWPORT VILLAGE DEVELOPMENTS LTD	
ARCHITECT		Brad Humphrey Architects 1755 TRINIDAD AVENUE COVINGTON, LA 70044 TEL: 786.871.1576	
DATE		15/01/2023	
DRAWING NO.		A1-01	
PROJECT NO.		35438	
SHEET NO.		1/1	
SHEET TOTAL		1/1	
DATE OF ISSUE		15/01/2023	
DRAWN BY		[Name]	
CHECKED BY		[Name]	
APPROVED BY		[Name]	

Schedule B

Note: Please refer to full size drawings in file 3360-20-2102





DATE		BY	
CITY & REGIONAL APPLICATION 21 OCT 2021			
STATE			
NEWPORT VILLAGE COURTESY DEVELOPMENTS LTD.			
Brad Humphrey Architect 1125 Thomas Avenue, Calgary, Alberta T2K 2L4 Tel 780.817.1578			
PROJECT TITLE			
BUILDING 3 RESIDENTIAL			
DRAWING TITLE			
ELEVATIONS: WEST & SOUTH			
DATE	SCALE	DATE	SCALE
2021	1/8" = 1'-0"	2021	1/8" = 1'-0"
Brad Humphrey Architect	Brad Humphrey Architect	Brad Humphrey Architect	Brad Humphrey Architect
DRAWING NO.			A3-01



DATE		BY	
CITY & REGIONAL APPLICATION 21 OCT 2021			
STATE			
NEWPORT VILLAGE COURTESY DEVELOPMENTS LTD.			
Brad Humphrey Architect 1125 Thomas Avenue, Calgary, Alberta T2K 2L4 Tel 780.817.1578			
PROJECT TITLE			
BUILDING 3 RESIDENTIAL			
DRAWING TITLE			
ELEVATIONS: EAST & NORTH			
DATE	SCALE	DATE	SCALE
2021	1/8" = 1'-0"	2021	1/8" = 1'-0"
Brad Humphrey Architect	Brad Humphrey Architect	Brad Humphrey Architect	Brad Humphrey Architect
DRAWING NO.			A3-02

Schedule C


Note: Please refer to full size drawings in file 3360-20-2102



OCP & REDDING APPLICATION: 21 OCT 2023 DATE: _____ DRAW: _____		
NEWPORT VILLAGE COURTESY DEVELOPMENTS LTD.		
Brad Humphrey Architect 1325 Thomas Avenue, Coquitlam, Alberta V3K 2L4 Tel 780.817.1578		
PROJECT TITLE: BUILDING 3 RESIDENTIAL		
DRAWING TITLE: PARKING PLAN		
DRAWN: BSJLH	SCALE: 1/8" = 1'-0"	PLOT DATE: 2023 September 19 21
BY: BRAD HUMPHREY ARCHITECT 20/21/22/23/24/25/26/27/28/29/30/31/32/33/34/35/36/37/38/39/40/41/42/43/44/45/46/47/48/49/50/51/52/53/54/55/56/57/58/59/60/61/62/63/64/65/66/67/68/69/70/71/72/73/74/75/76/77/78/79/80/81/82/83/84/85/86/87/88/89/90/91/92/93/94/95/96/97/98/99/100/101/102/103/104/105/106/107/108/109/110/111/112/113/114/115/116/117/118/119/120/121/122/123/124/125/126/127/128/129/130/131/132/133/134/135/136/137/138/139/140/141/142/143/144/145/146/147/148/149/150/151/152/153/154/155/156/157/158/159/160/161/162/163/164/165/166/167/168/169/170/171/172/173/174/175/176/177/178/179/180/181/182/183/184/185/186/187/188/189/190/191/192/193/194/195/196/197/198/199/200/201/202/203/204/205/206/207/208/209/210/211/212/213/214/215/216/217/218/219/220/221/222/223/224/225/226/227/228/229/230/231/232/233/234/235/236/237/238/239/240/241/242/243/244/245/246/247/248/249/250/251/252/253/254/255/256/257/258/259/260/261/262/263/264/265/266/267/268/269/270/271/272/273/274/275/276/277/278/279/280/281/282/283/284/285/286/287/288/289/290/291/292/293/294/295/296/297/298/299/300/301/302/303/304/305/306/307/308/309/310/311/312/313/314/315/316/317/318/319/320/321/322/323/324/325/326/327/328/329/330/331/332/333/334/335/336/337/338/339/340/341/342/343/344/345/346/347/348/349/350/351/352/353/354/355/356/357/358/359/360/361/362/363/364/365/366/367/368/369/370/371/372/373/374/375/376/377/378/379/380/381/382/383/384/385/386/387/388/389/390/391/392/393/394/395/396/397/398/399/400/401/402/403/404/405/406/407/408/409/410/411/412/413/414/415/416/417/418/419/420/421/422/423/424/425/426/427/428/429/430/431/432/433/434/435/436/437/438/439/440/441/442/443/444/445/446/447/448/449/450/451/452/453/454/455/456/457/458/459/460/461/462/463/464/465/466/467/468/469/470/471/472/473/474/475/476/477/478/479/480/481/482/483/484/485/486/487/488/489/490/491/492/493/494/495/496/497/498/499/500/501/502/503/504/505/506/507/508/509/510/511/512/513/514/515/516/517/518/519/520/521/522/523/524/525/526/527/528/529/530/531/532/533/534/535/536/537/538/539/540/541/542/543/544/545/546/547/548/549/550/551/552/553/554/555/556/557/558/559/560/561/562/563/564/565/566/567/568/569/570/571/572/573/574/575/576/577/578/579/580/581/582/583/584/585/586/587/588/589/590/591/592/593/594/595/596/597/598/599/600/601/602/603/604/605/606/607/608/609/610/611/612/613/614/615/616/617/618/619/620/621/622/623/624/625/626/627/628/629/630/631/632/633/634/635/636/637/638/639/640/641/642/643/644/645/646/647/648/649/650/651/652/653/654/655/656/657/658/659/660/661/662/663/664/665/666/667/668/669/670/671/672/673/674/675/676/677/678/679/680/681/682/683/684/685/686/687/688/689/690/691/692/693/694/695/696/697/698/699/700/701/702/703/704/705/706/707/708/709/710/711/712/713/714/715/716/717/718/719/720/721/722/723/724/725/726/727/728/729/730/731/732/733/734/735/736/737/738/739/740/741/742/743/744/745/746/747/748/749/750/751/752/753/754/755/756/757/758/759/760/761/762/763/764/765/766/767/768/769/770/771/772/773/774/775/776/777/778/779/780/781/782/783/784/785/786/787/788/789/790/791/792/793/794/795/796/797/798/799/800/801/802/803/804/805/806/807/808/809/810/811/812/813/814/815/816/817/818/819/820/821/822/823/824/825/826/827/828/829/830/831/832/833/834/835/836/837/838/839/840/841/842/843/844/845/846/847/848/849/850/851/852/853/854/855/856/857/858/859/860/861/862/863/864/865/866/867/868/869/870/871/872/873/874/875/876/877/878/879/880/881/882/883/884/885/886/887/888/889/890/891/892/893/894/895/896/897/898/899/900/901/902/903/904/905/906/907/908/909/910/911/912/913/914/915/916/917/918/919/920/921/922/923/924/925/926/927/928/929/930/931/932/933/934/935/936/937/938/939/940/941/942/943/944/945/946/947/948/949/950/951/952/953/954/955/956/957/958/959/960/961/962/963/964/965/966/967/968/969/970/971/972/973/974/975/976/977/978/979/980/981/982/983/984/985/986/987/988/989/990/991/992/993/994/995/996/997/998/999/1000		A2-00

OCP & REDDING APPLICATION: 21 OCT 2023 DATE: _____ DRAW: _____		
NEWPORT VILLAGE COURTESY DEVELOPMENTS LTD.		
Brad Humphrey Architect 1325 Thomas Avenue, Coquitlam, Alberta V3K 2L4 Tel 780.817.1578		
PROJECT TITLE: BUILDING 3 RESIDENTIAL		
DRAWING TITLE: MAIN FLOOR PLAN		
DRAWN: BSJLH	SCALE: 1/8" = 1'-0"	PLOT DATE: 2023 09 19 10 21
BY: BRAD HUMPHREY ARCHITECT 20/21/22/23/24/25/26/27/28/29/30/31/32/33/34/35/36/37/38/39/40/41/42/43/44/45/46/47/48/49/50/51/52/53/54/55/56/57/58/59/60/61/62/63/64/65/66/67/68/69/70/71/72/73/74/75/76/77/78/79/80/81/82/83/84/85/86/87/88/89/90/91/92/93/94/95/96/97/98/99/100/101/102/103/104/105/106/107/108/109/110/111/112/113/114/115/116/117/118/119/120/121/122/123/124/125/126/127/128/129/130/131/132/133/134/135/136/137/138/139/140/141/142/143/144/145/146/147/148/149/150/151/152/153/154/155/156/157/158/159/160/161/162/163/164/165/166/167/168/169/170/171/172/173/174/175/176/177/178/179/180/181/182/183/184/185/186/187/188/189/190/191/192/193/194/195/196/197/198/199/200/201/202/203/204/205/206/207/208/209/210/211/212/213/214/215/216/217/218/219/220/221/222/223/224/225/226/227/228/229/230/231/232/233/234/235/236/237/238/239/240/241/242/243/244/245/246/247/248/249/250/251/252/253/254/255/256/257/258/259/260/261/262/263/264/265/266/267/268/269/270/271/272/273/274/275/276/277/278/279/280/281/282/283/284/285/286/287/288/289/290/291/292/293/294/295/296/297/298/299/300/301/302/303/304/305/306/307/308/309/310/311/312/313/314/315/316/317/318/319/320/321/322/323/324/325/326/327/328/329/330/331/332/333/334/335/336/337/338/339/340/341/342/343/344/345/346/347/348/349/350/351/352/353/354/355/356/357/358/359/360/361/362/363/364/365/366/367/368/369/370/371/372/373/374/375/376/377/378/379/380/381/382/383/384/385/386/387/388/389/390/391/392/393/394/395/396/397/398/399/400/401/402/403/404/405/406/407/408/409/410/411/412/413/414/415/416/417/418/419/420/421/422/423/424/425/426/427/428/429/430/431/432/433/434/435/436/437/438/439/440/441/442/443/444/445/446/447/448/449/450/451/452/453/454/455/456/457/458/459/460/461/462/463/464/465/466/467/468/469/470/471/472/473/474/475/476/477/478/479/480/481/482/483/484/485/486/487/488/489/490/491/492/493/494/495/496/497/498/499/500/501/502/503/504/505/506/507/508/509/510/511/512/513/514/515/516/517/518/519/520/521/522/523/524/525/526/527/528/529/530/531/532/533/534/535/536/537/538/539/540/541/542/543/544/545/546/547/548/549/550/551/552/553/554/555/556/557/558/559/560/561/562/563/564/565/566/567/568/569/570/571/572/573/574/575/576/577/578/579/580/581/582/583/584/585/586/587/588/589/590/591/592/593/594/595/596/597/598/599/600/601/602/603/604/605/606/607/608/609/610/611/612/613/614/615/616/617/618/619/620/621/622/623/624/625/626/627/628/629/630/631/632/633/634/635/636/637/638/639/640/641/642/643/644/645/646/647/648/649/650/651/652/653/654/655/656/657/658/659/660/661/662/663/664/665/666/667/668/669/670/671/672/673/674/675/676/677/678/679/680/681/682/683/684/685/686/687/688/689/690/691/692/693/694/695/696/697/698/699/700/701/702/703/704/705/706/707/708/709/710/711/712/713/714/715/716/717/718/719/720/721/722/723/724/725/726/727/728/729/730/731/732/733/734/735/736/737/738/739/740/741/742/743/744/745/746/747/748/749/750/751/752/753/754/755/756/757/758/759/760/761/762/763/764/765/766/767/768/769/770/771/772/773/774/775/776/777/778/779/780/781/782/783/784/785/786/787/788/789/790/791/792/793/794/795/796/797/798/799/800/801/802/803/804/805/806/807/808/809/810/811/812/813/814/815/816/817/818/819/820/821/822/823/824/825/826/827/828/829/830/831/832/833/834/835/836/837/838/839/840/841/842/843/844/845/846/847/848/849/850/851/852/853/854/855/856/857/858/859/860/861/862/863/864/865/866/867/868/869/870/871/872/873/874/875/876/877/878/879/880/881/882/883/884/885/886/887/888/889/890/891/892/893/894/895/896/897/898/899/900/901/902/903/904/905/906/907/908/909/910/911/912/913/914/915/916/917/918/919/920/921/922/923/924/925/926/927/928/929/930/931/932/933/934/935/936/937/938/939/940/941/942/943/944/945/946/947/948/949/950/951/952/953/954/955/956/957/958/959/960/961/962/963/964/965/966/967/968/969/970/971/972/973/974/975/976/977/978/979/980/981/982/983/984/985/986/987/988/989/990/991/992/993/994/995/996/997/998/999/1000		A2-01

Attachment B



Part 49 - Comprehensive Development Twenty-Seven Zone (CD-27) (1025 Ryan Rd)

8.54.1 Intent

The CD-27 Zone is intended to accommodate a rental apartment development on the property legally described as Lot B, Section 14, Comox District, Plan VIP74579. The property shall be developed substantially in accordance with Schedules A and B which form part of this zone.

8.54.2 Permitted Uses

The following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

1. *Rental Apartment*

8.54.3 Lot Coverage

A *lot* shall not be covered by buildings to a greater extent than 35% of the total area of the *lot*.

8.54.4 Floor Area Ratio

The maximum *floor area ratio* shall not exceed 1.6.

8.54.5 Minimum Lot Size

A *lot* shall have an area of not less than 0.55 hectare.

8.54.6 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- | | |
|--|--------|
| (1) <i>Front Yard</i> (interpreted as the yard adjacent to the northwest property line): | 12.0 m |
| (2) <i>Rear Yard</i> (interpreted as the yard adjacent to the southeast property line): | 17.0 m |
| (3) <i>Side Yard</i> (interpreted as all other yards): | 4.5 m |

Notwithstanding the required *front, rear and side yard setbacks* specified above, roof overhangs may extend up to 0.76 m into the required setback.

8.54.7 Height of Building

Maximum *building height* shall be 17.7m in accordance with Schedule B and includes the elevator and roof top mechanical systems.

8.54.8 Useable Open Space

A minimum of 2,966m² of useable open space must be provided as shown in Schedule B. For clarity this includes common outdoor areas and private balconies or patios.

A minimum of 2.6m² of interior amenity space must be provided. For clarity this includes fitness facilities, common rooms and co-work areas.

8.54.9 Accessory Structures

Shall not be permitted except for bike storage structures.

8.54.10 Off-Street Parking and Loading

Off-street parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw except:

- (4) For *Rental Apartment* uses parking shall be provided at a rate of 1.20 parking spaces per dwelling unit inclusive of visitor parking;
- (5) Bicycle parking facilities must be provided at a rate of two covered, secure stall per unit.

CONTRACTOR RESPONSIBLE FOR THE PROTECTION AND MAINTENANCE OF ALL UTILITIES AND SERVICES UNDERGROUND AND ABOVE GROUND. ALL UTILITIES AND SERVICES TO BE PROTECTED BY THE CONTRACTOR SHALL BE IDENTIFIED BY THE CONTRACTOR.



DATE: 11/11/2016

GENERAL NOTES:

NO.	REVISION	DATE
1	ISSUED FOR PERMIT	11/11/2016
2	REVISED FOR COMMENTS	11/11/2016
3	REVISED FOR COMMENTS	11/11/2016
4	REVISED FOR COMMENTS	11/11/2016
5	REVISED FOR COMMENTS	11/11/2016
6	REVISED FOR COMMENTS	11/11/2016
7	REVISED FOR COMMENTS	11/11/2016
8	REVISED FOR COMMENTS	11/11/2016
9	REVISED FOR COMMENTS	11/11/2016
10	REVISED FOR COMMENTS	11/11/2016
11	REVISED FOR COMMENTS	11/11/2016
12	REVISED FOR COMMENTS	11/11/2016
13	REVISED FOR COMMENTS	11/11/2016
14	REVISED FOR COMMENTS	11/11/2016
15	REVISED FOR COMMENTS	11/11/2016
16	REVISED FOR COMMENTS	11/11/2016
17	REVISED FOR COMMENTS	11/11/2016
18	REVISED FOR COMMENTS	11/11/2016
19	REVISED FOR COMMENTS	11/11/2016
20	REVISED FOR COMMENTS	11/11/2016
21	REVISED FOR COMMENTS	11/11/2016
22	REVISED FOR COMMENTS	11/11/2016
23	REVISED FOR COMMENTS	11/11/2016
24	REVISED FOR COMMENTS	11/11/2016
25	REVISED FOR COMMENTS	11/11/2016
26	REVISED FOR COMMENTS	11/11/2016
27	REVISED FOR COMMENTS	11/11/2016
28	REVISED FOR COMMENTS	11/11/2016
29	REVISED FOR COMMENTS	11/11/2016
30	REVISED FOR COMMENTS	11/11/2016
31	REVISED FOR COMMENTS	11/11/2016
32	REVISED FOR COMMENTS	11/11/2016
33	REVISED FOR COMMENTS	11/11/2016
34	REVISED FOR COMMENTS	11/11/2016
35	REVISED FOR COMMENTS	11/11/2016
36	REVISED FOR COMMENTS	11/11/2016
37	REVISED FOR COMMENTS	11/11/2016
38	REVISED FOR COMMENTS	11/11/2016
39	REVISED FOR COMMENTS	11/11/2016
40	REVISED FOR COMMENTS	11/11/2016
41	REVISED FOR COMMENTS	11/11/2016
42	REVISED FOR COMMENTS	11/11/2016
43	REVISED FOR COMMENTS	11/11/2016
44	REVISED FOR COMMENTS	11/11/2016
45	REVISED FOR COMMENTS	11/11/2016
46	REVISED FOR COMMENTS	11/11/2016
47	REVISED FOR COMMENTS	11/11/2016
48	REVISED FOR COMMENTS	11/11/2016
49	REVISED FOR COMMENTS	11/11/2016
50	REVISED FOR COMMENTS	11/11/2016
51	REVISED FOR COMMENTS	11/11/2016
52	REVISED FOR COMMENTS	11/11/2016
53	REVISED FOR COMMENTS	11/11/2016
54	REVISED FOR COMMENTS	11/11/2016
55	REVISED FOR COMMENTS	11/11/2016
56	REVISED FOR COMMENTS	11/11/2016
57	REVISED FOR COMMENTS	11/11/2016
58	REVISED FOR COMMENTS	11/11/2016
59	REVISED FOR COMMENTS	11/11/2016
60	REVISED FOR COMMENTS	11/11/2016
61	REVISED FOR COMMENTS	11/11/2016
62	REVISED FOR COMMENTS	11/11/2016
63	REVISED FOR COMMENTS	11/11/2016
64	REVISED FOR COMMENTS	11/11/2016
65	REVISED FOR COMMENTS	11/11/2016
66	REVISED FOR COMMENTS	11/11/2016
67	REVISED FOR COMMENTS	11/11/2016
68	REVISED FOR COMMENTS	11/11/2016
69	REVISED FOR COMMENTS	11/11/2016
70	REVISED FOR COMMENTS	11/11/2016
71	REVISED FOR COMMENTS	11/11/2016
72	REVISED FOR COMMENTS	11/11/2016
73	REVISED FOR COMMENTS	11/11/2016
74	REVISED FOR COMMENTS	11/11/2016
75	REVISED FOR COMMENTS	11/11/2016
76	REVISED FOR COMMENTS	11/11/2016
77	REVISED FOR COMMENTS	11/11/2016
78	REVISED FOR COMMENTS	11/11/2016
79	REVISED FOR COMMENTS	11/11/2016
80	REVISED FOR COMMENTS	11/11/2016
81	REVISED FOR COMMENTS	11/11/2016
82	REVISED FOR COMMENTS	11/11/2016
83	REVISED FOR COMMENTS	11/11/2016
84	REVISED FOR COMMENTS	11/11/2016
85	REVISED FOR COMMENTS	11/11/2016
86	REVISED FOR COMMENTS	11/11/2016
87	REVISED FOR COMMENTS	11/11/2016
88	REVISED FOR COMMENTS	11/11/2016
89	REVISED FOR COMMENTS	11/11/2016
90	REVISED FOR COMMENTS	11/11/2016
91	REVISED FOR COMMENTS	11/11/2016
92	REVISED FOR COMMENTS	11/11/2016
93	REVISED FOR COMMENTS	11/11/2016
94	REVISED FOR COMMENTS	11/11/2016
95	REVISED FOR COMMENTS	11/11/2016
96	REVISED FOR COMMENTS	11/11/2016
97	REVISED FOR COMMENTS	11/11/2016
98	REVISED FOR COMMENTS	11/11/2016
99	REVISED FOR COMMENTS	11/11/2016
100	REVISED FOR COMMENTS	11/11/2016


WMA ARCHITECTS
 CONSULTANT

PROJECT NAME: RYAN ROAD RESIDENTIAL

PROJECT ADDRESS: 105 RYAN ROAD, COURTNEY, B.C.

SITE PLAN

PROJECT NO: 3360-20-1916
 SCALE: 1/8"=1'-0"
 DRAWN BY: DM
 REVISION: A1.1




SCHEDULE A

Note: Please refer to full size drawings in file 3360-20-1916

THIS DRAWING IS THE PROPERTY OF WMA ARCHITECTS, INC. AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF WMA ARCHITECTS, INC. THIS DRAWING IS THE PROPERTY OF WMA ARCHITECTS, INC. AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF WMA ARCHITECTS, INC.

OWNER/CLIENT: _____
 GENERAL NOTES: _____



NO.	REVISION	DATE	BY
1	ISSUED FOR PERMIT	10/1/20	WMA
2			
3			
4			
5			
6			
7			
8			
9			
10			

CONCEPT:



PROJECT NAME:
RYAN ROAD RESIDENTIAL

PROJECT ADDRESS:
 100 WYOMING COURT, S.E.

OWNER/CLIENT:

MATERIAL BOARD

PROJECT NO.: 1905 DRAWN BY: DC
 SCALE: AS NOTED REVISION: DM
 DWG. NO.: A3.1

- 1) GLASS GUARDRAIL 
- 2) CORRUGATED POWDER COATED METAL PANEL 
- 3) 3-LAYER OFF-WHITE STUCCO 
- 4) WHITE VINYL WINDOW AND DOOR FRAMES 
- 5) WOOD LOOK CLADDING 
- 6) BLUE ALUMINUM COMPOSITE PANEL 
- 7) ALUMINUM STOREFRONT (FOR GROUND FLOOR) 

SCHEDULE B

Note: Please refer to full size drawings in file 3360-20-1916

**Part 50 - Comprehensive Development Twenty-Eight Zone (CD-28)
(2355 Mansfield Drive)****8.55.1 Intent**

The CD-28 Zone is intended to accommodate a combination of commercial and multi-residential uses on the property legally described as Lot B, Section 66, Plan 28292. The property shall be developed substantially in accordance with Schedules A and B which form part of this zone.

8.55.2 Permitted Uses

The following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

1. *Multi Residential*
2. *Liquor Store*
3. *Licensed Premises*
4. *Retail*
5. *Restaurant*

8.55.3 Lot Coverage

A *lot* shall not be covered by buildings to a greater extent than 50% of the total area of the *lot*.

8.55.4 Floor Area Ratio

The maximum *floor area ratio* shall not exceed 1.6.

8.55.5 Minimum Lot Size

A *lot* shall have an area of not less than 2,7992 m².

8.55.6 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front Yard* (interpreted as the yard adjacent to the north property line): 0 m
- (2) *Rear Yard* (interpreted as the yard adjacent to the south property line): 19.5 m
- (3) *Side Yard* (interpreted as the yard adjacent to the west property line): 0.5 m
- (4) *Side Yard* (interpreted as the yard adjacent to the east property line): 2.7 m

8.55.7 Height of Building

Maximum *building height* shall be 18.0 m and in accordance with Schedule B and includes rooftop parapets, elevator and roof top mechanical systems.

8.55.8 Useable Open Space

A minimum of 826m² of useable open space must be provided as shown in Schedule B. For clarity this includes private amenity space in the form of private balconies or patios.


8.55.9 Accessory Structures

Shall not be permitted except for waste and recycling facilities.

8.55.10 Off-Street Parking and Loading

Off-street parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw except:

- (1) For *Multi Residential* uses parking shall be provided at a rate of 1.1 parking spaces per *dwelling unit* inclusive of visitor parking;
- (2) For *Liquor Store* use parking shall be provided at a rate of 1 space per 20m² of *floor area*; and
- (3) For *Neighborhood Pub* use parking shall be provided at a rate of 1 space per 6 seats.






SCHEDULE B

Note: Please refer to full size drawings in file 3360-20-1912



SCHEDULE B

Note: Please refer to full size drawings in file 3360-20-1912



SCHEDULE B

Note: Please refer to full size drawings in file 3360-20-1912



SCHEDULE B

Note: Please refer to full size drawings in file 3360-20-1912

**Part 56 - Comprehensive Development Twenty-Nine Zone (CD-29)
(1375 Piercy Ave)****8.56.1 Intent**

The CD-29 Zone is intended to accommodate an affordable housing development composed of three, four-unit townhomes on the property legally described as Lot 7, District Lot 104, Comox District, Plan 5659. The property shall be developed substantially in accordance with Schedule A which form part of this zone.

8.56.2 Permitted Uses

The following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

1. *Dwelling, Townhouse*

8.56.3 Lot Coverage

A *lot* shall not be covered by buildings to a greater extent than 35% of the total area of the *lot*.

8.56.4 Minimum Lot Size

A *lot* shall have an area of not less than 2,274 m².

8.56.5 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front Yard* 1.0 m
- (2) *Rear Yard* 6.0 m
- (3) *Side Yard* 2.0 m

Notwithstanding the required *front, rear and side yard setbacks* specified above, roof overhangs and decks may extend up to 0.80 m into the required setback.

8.56.6 Height of Building

Maximum *building height* shall be 8.0 m.

8.56.7 Off-Street Parking and Loading

Off-street parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw except:

- (1) In this zone, parking shall be provided at a rate of 1.17 parking spaces per dwelling unit inclusive of visitor parking;
- (2) A minimum of 14 secure, enclosed bicycle parking stalls and 4 exterior stalls shall be provided.

All driveways and parking shall be located in the yard with direct access from the lane.

Parking stalls shall be delineated using concrete curbs.

8.56.8 Accessory Buildings and Structures

Except where otherwise specified in this bylaw the following minimum building setbacks shall apply:

- (1) Rear Yard: 2.2m
- (2) Side Yards: 1.3m

Notwithstanding the required rear, and side yard setbacks specified above, roof overhands extend up to 0.80m into the required setback.

**Part 52 – Comprehensive Development Thirty (CD-30)
(Lot A, Copperfield Road)****8.57.1 Intent**

The CD-30 Zone is intended to accommodate a strata community on Lot A, District Lot 138, Comox District, Plan 2607 Except Parts in Plans 312R, 14210 and 29833. The property shall be developed in accordance with Schedule A which form part of this zone.

8.57.2 CD-30A**1. Permitted Uses**

The following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- a) Dwelling, Single Residential with or without Carriage House
- b) Accessory Buildings and Structures

2. Minimum Lot Size

- a) Dwelling, Single Family with or without Carriage House: 300m²

3. Minimum Lot Frontage

- a) Dwelling, Single Family with or without Carriage House: 10m

4. Maximum Lot Coverage

- a) A lot shall not be covered by building to a greater extent than 70% of the total lot area

5. Setbacks

- a) Front Yard: 4.5m except 2.25m for porch projections and second storey building area
- b) Rear Yard (with laneway access): 13.5m except 1.2m for Carriage Houses and Accessory Buildings
- c) Rear Yard (without laneway access): 13.5m
- d) Side Yard: 1.5m except 2.25m for side yards abutting the strata road

6. Height

- a) Dwelling, Single Residential: 9.0m
- b) Carriage House: 7.5m

8.57.3 CD-30B

(1) Permitted Uses

The following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- a) Dwelling, Duplex
- b) Accessory Buildings and Structures

(2) Minimum Lot Size

- a) Dwelling, Duplex: 200m²

(3) Minimum Lot Frontage

- a) Dwelling, Duplex (per unit): 8% of lot perimeter

(4) Maximum Lot Coverage

- a) A lot shall not be covered by building to a greater extent than 70% of the total lot area

(5) Setbacks

- a) Front Yard: 4.5m except 2.25m for porch projections and second storey building area
- b) Rear Yard: 13.5m
- c) Side Yard: 1.5m except 2.25m for side yards abutting the strata road

(6) Height

- a) Dwelling, Duplex: 9.0m

8.57.4 CD-30C

(1) Permitted Uses

The following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- a) Dwelling, Townhouse with or without Carriage House
- b) Accessory Buildings and Structures

(2) Minimum Lot Size

- a) Dwelling, Townhouse: 200m²

(3) Minimum Lot Frontage

- a) Dwelling, Duplex (per unit): 8% of lot perimeter

(4) Maximum Lot Coverage

- a) A lot shall not be covered by building to a greater extent than 70% of the total lot area


(5) Setbacks

- a) Front Yard: 4.5m except 2.25m for porch projections and second storey building area
- b) Rear Yard (with laneway access): 13.5m except 1.2m for Carriage Houses and Accessory Buildings
- c) Rear Yard (without laneway access): 13.5m
- d) Side Yard: 0m except 2.25m for side yards adjacent to the strata road or CD-30 A or B areas.

SCHEDULE A



Subject Property Map



THE CITY OF COURTENAY
ATTACHMENT "B"
Part of Bylaw No. 2912, 2020
Amendment to the
Zoning Bylaw No. 2500, 2007

Part 53 - Comprehensive Development Thirty-One Zone (CD-31) (310 Hunt Road)

8.58.1 Intent

The CD-31 Zone is intended to accommodate a Hotel on the property legally described as Lot A, Section 14, Comox District, Plan EPP101533. The property shall be developed substantially in accordance with Schedules A and B which form part of this zone.

8.58.2 Permitted Uses

The following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

1. *Hotel*

8.58.3 Minimum Lot Size

A *lot* shall have an area of not less than 7,320m²

8.58.4 Floor Area Ratio

The maximum floor area ratio shall not exceed 0.75

8.58.5 Lot Coverage

A lot shall not be covered by buildings to a greater extent than 20% of the total area of the lot.

8.58.6 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front Yard* (interpreted as the yard adjacent to the south property line): 45.0m
- (2) *Rear Yard* (interpreted as the yard adjacent to the north property line): 15.0m
- (3) *Side Yard* (interpreted as the yard adjacent to the west property line): 5.0m
- (4) *Side Yard* (interpreted as the yard adjacent to the east property line): 14.98m

8.56.7 Height of Building

Maximum *building height* shall be 15.0m and in accordance with Schedule B and includes rooftop parapets, elevator and roof top mechanical systems.

8.56.8 Accessory Structures

Shall not be permitted except for waste and recycling facilities and exterior bicycle storage areas.


8.58.9 Off-Street Parking and Loading

Off-street parking, small car parking and loading shall be provided and maintained in accordance with the requirements of Division 7 of *Zoning Bylaw No. 2500, 2007*.

8.58.10 Landscaping and Screening


- (1) A landscape area of at least 7.0m in width extending along Ryan Road shall be provided.
- (2) A landscape area of at least 3.5m in width extending along the eastern property line shall be provided.
- (3) A landscape area of at least 0m to 6.0m in width extending along Hunt Road shall be provided.
- (4) A landscape area of at least 0 to 3.5m in width extending along Tunner Drive shall be provided.
- (5) Loading areas, garbage and recycling containers shall be screened and gated to a minimum *height* of 2.0m by a landscaping screen or solid decorative *fence* or combination thereof.

Attachment A



SCHEDULE A

Note: Please Refer to Full Sized Drawings in File No. 3360-20-2002



SEE PLANETS FOR PLAN NO. 3360-20-2002

PROPERTY LINE	EXISTING CONCRETE PAVEMENT
BUILDING FOOTPRINT	ASPHALT DRIVE
5 FT. FENCE	GRAVEL DRIVE
5 FT. RETAINING WALL	GRAVEL DRIVE
AREA OF LANDSCAPING	GRAVEL DRIVE
MANHOLE	GRAVEL DRIVE
STANDARD CONCRETE PAVEMENT	GRAVEL DRIVE
CONCRETE SEE PLAN	GRAVEL DRIVE

SITE LEGEND

(Symbol)	PROPERTY LINE
(Symbol)	BUILDING FOOTPRINT
(Symbol)	5 FT. FENCE
(Symbol)	5 FT. RETAINING WALL
(Symbol)	AREA OF LANDSCAPING
(Symbol)	MANHOLE
(Symbol)	STANDARD CONCRETE PAVEMENT
(Symbol)	CONCRETE SEE PLAN



LOWICK SCOTT

 ARCHITECTS

SCHEDULE A

Note: Please Refer to Full Sized Drawings in File No. 3360-20-2002



SCHEDULE B

Note: Please Refer to Full Sized Drawings in File No. 3360-20-2002



SCHEDULE B

Note: Please Refer to Full Sized Drawings in File No. 3360-20-2002

Part 54 – Comprehensive Development Thirty-Two Zone (CD-32) (801 Ryan Road)

8.54.1 Intent

The CD-32 Zone is intended to accommodate a rental apartment development on the property legally described as Lot 1, Section 14, Comox District, Plan 27905 Except Parts in Plans 38112 and VIP 53727. The property shall be developed substantially in accordance with Schedules A and B which form part of this zone.

8.54.2 Permitted Uses

The following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

7. *Rental Apartment*

8.54.3 Lot Coverage

A *lot* shall not be covered by buildings to a greater extent than 30% of the total area of the lot.

8.54.4 Floor Area Ratio

The maximum *floor area ratio* shall not exceed 1.4.

8.54.5 Minimum Lot Size

A lot shall have an area of not less than 1.8 hectares.

8.54.6 Setbacks

Except where otherwise specified in this bylaw the following minimum building setbacks shall apply:

- (4) Front Yard (interpreted as the yard adjacent to the northwest property line): 7.5 m
- (5) Rear Yard (interpreted as the yard adjacent to the southeast property line): 6.0 m
- (6) Side Yard (interpreted as all other yards): 3.0 m

Notwithstanding the required front, rear, and side yard setbacks specified above, roof overhangs and decks may extend up to 0.6 m into the required setback.

8.54.7 Height of Buildings

Maximum building height shall be 17.5 m and in accordance with Schedule B.

Notwithstanding the maximum height specified above, roof projections, elevator shafts and mechanical equipment may project beyond 17.5 m.

8.54.9 Usable Open Space

A minimum of 20 m² of useable open space must be provided per unit as shown in Schedule B. For clarity this includes common outdoor areas and private balconies or patios.

8.54.10 Accessory Structures

Shall not be permitted except for bike storage structures, pergolas, sheds, and playgrounds.

8.54.11 Off-Street Parking and Loading


Off-street parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw except:

- (6) For *Rental Apartment* uses parking shall be provided at a rate of 1.20 parking spaces per dwelling unit inclusive of visitor parking;
- (7) Bicycle parking facilities must be provided at a rate of one covered, secure stall per unit.

8.54.12 Fencing

The maximum height of fencing along the side property line (southwest property line) is 4.0 m.

SCHEDULE A



SCHEDULE B

SEAWOIR PACIFIC DEVELOPMENTS LTD.
100 St Johns Street, Campbell River, B.C.
(250) 833-2222
www.seawoirpacific.ca

REVISIONS

No.	REVISED FOR	REVISION
A	REVISED FOR PERMITS	PERMITS
B	REVISED FOR VENDOR	VENDOR
C	REVISED FOR VENDOR	VENDOR
D	REVISED FOR VENDOR	VENDOR
E	REVISED FOR VENDOR	VENDOR
F	REVISED FOR VENDOR	VENDOR
G	REVISED FOR VENDOR	VENDOR
H	REVISED FOR VENDOR	VENDOR
I	REVISED FOR VENDOR	VENDOR
J	REVISED FOR REZONING	REZONING

PROJECT STATUS
RE ISSUED FOR REZONING

SEAL: AMEL ARCHITECTURE
REGISTERED ARCHITECT
BRITISH COLUMBIA
NO. 12345
1000 10th Street, Campbell River, BC V9W 2G8
250.833.2222

1 FRONT ELEVATION
Scale: 1:120

2 BACK ELEVATION
Scale: 1:120

EXTERIOR CLADDING PRODUCT

ID	DESCRIPTION	COLOR	LOCATION
C1	4" CEMENT BOARD TRIM	ARTIC WHITE	WINDOW & DOOR TRIM
C2	12" CEMENT BOARD TRIM	ARTIC WHITE	BELLY BAND
C3	PAWK - CEDARWELL	DEEP OCEAN	VERT. PARTITION WALL
C4	PAWK - CEDARWELL	DEEP OCEAN	LEVEL 1-3
C5	PAWK - CEDARWELL	DEEP OCEAN	LEVEL 4-6
C6	PAWK - CEDARWELL	DEEP OCEAN	LEVEL 1-3 BALCONY/PTAC
C7	PAWK - CEDARWELL	DEEP OCEAN	LEVEL 4-6 BALCONY/PTAC
C8	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C9	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C10	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C11	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C12	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C13	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C14	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C15	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C16	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C17	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C18	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C19	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C20	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C21	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C22	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C23	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C24	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C25	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C26	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C27	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C28	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C29	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C30	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C31	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C32	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C33	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C34	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C35	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C36	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C37	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C38	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C39	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C40	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C41	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C42	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C43	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C44	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C45	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C46	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C47	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C48	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C49	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C50	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C51	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C52	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C53	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C54	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C55	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C56	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C57	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C58	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C59	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C60	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C61	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C62	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C63	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C64	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C65	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C66	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C67	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C68	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C69	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C70	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C71	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C72	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C73	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C74	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C75	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C76	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C77	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C78	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C79	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C80	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C81	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C82	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C83	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C84	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C85	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C86	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C87	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C88	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C89	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C90	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C91	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C92	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C93	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C94	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C95	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C96	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C97	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C98	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C99	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK
C100	PAWK - CEDARWELL	DEEP OCEAN	TRAMP OFF FLOORING DECK

EXTERIOR METAL PRODUCT

ID	DESCRIPTION	COLOR	LOCATION
M1	ALUMINUM DOWNSPOUTS	BLACK	
M2	ALUMINUM DOWNSPOUTS	BLACK	REFERS TO DETAIL 6A42
M3	ALUMINUM FLASHING	BLACK	REFERS TO DETAIL 6A42
M4	PREPARED FLAT COIL	WHITE	FACIA BAND
M5	4 PANEL CLASSIC SOFFIT	LENN	REFERS TO DETAIL 6A42
M6	WALL FLASHING	BLACK	
M7	BRIDGE DEEP FLASHING	BLACK	
M8	ROOF EDGE FLASHING	BLACK	REFERS TO DETAIL 6A42
M9	DEEP GAP FLASHING	WHITE	PARADES
M10	REVERSE DEEP FLASHING	WHITE	PLANK WINDOW TRIM
M11	GETTER COIL FLASHING	BLACK	
M12	FOUNDATION TRANSITION F.		

EXTERIOR ROOFING PRODUCT

ID	DESCRIPTION	COLOR
R1	ROOFING SHINGLES - 35 YEAR LAMINATE	BLACK
R2	ATTC BRACK GIRT	BLACK

NOTES

1. ALL RESIDENTIAL UNITS TO HAVE WINDOWS WITH RATING OF R1C-50
2. ALL RESIDENTIAL UNITS TO HAVE WINDOWS WITH RATING OF R1C-50

PROJECT NAME: GLENHART VIEWS
PROJECT NUMBER:
ADDRESS: 80 RYAN ROAD COURTNEY, BC
DRAWING TITLE:
ELEVATIONS 1 OF 2 - BUILDING A

DRAWN BY: PD
CHECKED BY: RF
DATE: 08/14/2020
SCALE:
DRAWING #: AS REVISION
REV #:

A3.1

RE ISSUED FOR REZONING



PROJECT STATUS:
RE-ISSUED FOR REZONING


Revision Schedule

No.	Description	Revision Date
A	ISSUED FOR PERMIT	08/09/2020
B	ISSUED FOR REZONING	08/09/2020
C	RE-ISSUED FOR VENDOR	08/09/2020
D	RE-ISSUED FOR REZONING	08/09/2020
E	RE-ISSUED FOR VENDOR	08/09/2020
F	RE-ISSUED FOR REZONING	08/09/2020
G	RE-ISSUED FOR VENDOR	08/09/2020
H	RE-ISSUED FOR REZONING	08/09/2020
I	RE-ISSUED FOR VENDOR	08/09/2020
J	RE-ISSUED FOR REZONING	08/09/2020


SEAL: **ARLE ARCHITECTURE**
 ARCHITECT




TRADE CONTRACTORS SHALL VERIFY ALL DIMENSIONS OF WORK SUBMITTED TO BE CONFORMANT WITH THE PERMIT AND WITHOUT DELAY FOR CLARIFICATION. DRAWINGS, SPECIFICATIONS AND MATERIALS SHALL BE SUBJECT TO INSPECTION AND APPROVAL BY THE LOCAL AUTHORITY. TRADE CONTRACTORS SHALL BE RESPONSIBLE TO OBTAIN ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AUTHORITY. TRADE CONTRACTORS SHALL BE RESPONSIBLE TO OBTAIN ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AUTHORITY. TRADE CONTRACTORS SHALL BE RESPONSIBLE TO OBTAIN ALL NECESSARY PERMITS AND APPROVALS FROM THE LOCAL AUTHORITY.




2 RIGHT ELEVATION
 Scale: 1:125



1 LEFT ELEVATION
 Scale: 1:125



4 SIDE ENTRY ELEVATION
 Scale: 1:48



3 FRONT ENTRY ELEVATION
 Scale: 1:48

EXTERIOR ROOFING PRODUCT		
DESCRIPTION	COLOR	NOTES
ROOFING SHEET: 30 YEAR LAMINATE	BLACK	1 ALL RECREATIONAL UNITS TO HAVE INDIVIDUAL AC UNIT
ATIS BENT PAINT	BLACK	2 ALL RECREATIONAL UNITS TO HAVE WINDOWS WITH RATINGS OF R30C8


EXTERIOR METAL PRODUCT		
DESCRIPTION	COLOR	LOCATION
ALUMINUM DOWNSPUTTERS	BLACK	REFER TO DETAIL BMA2
ALUMINUM GUTTERS	BLACK	REFER TO DETAIL BMA2
ALUMINUM FLASHING	BLACK	REFER TO DETAIL BMA2
REFINISHED FLAT COIL	WHITE	FASCIA BOARD
4 PANEL CLASSIC ROFFT	UNFIN	REFER TO DETAIL BMA2
WALL FLASHING	BLACK	REFER TO DETAIL BMA2
BINGLE STEP FLASHING	BLACK	REFER TO DETAIL BMA2
ROOF EDGE FLASHING	BLACK	VARIOUS
DRIP CAP FLASHING	WHITE	PLANK/WINDOW TRIM
REVERSE DRIP FLASHING	BLACK	VARIOUS
GUTTER COIL FLASHING	BLACK	FOUNDATION TRANSITION F.

EXTERIOR CLADDING PRODUCT		
DESCRIPTION	COLOR	LOCATION
4" CEMENT BOARD TRIM	ARTIC WHITE	WINDOOR/WINDOW TRIM
17" CEMENT BOARD TRIM	ARTIC WHITE	BELLY BAND
12" CEMENT BOARD TRIM	ARTIC WHITE	VERT. PARTITION WALL
PLANK - CEDARWALL	DEEP OCEAN	LEVEL 1-3
PLANK - CEDARWALL	BOOTHBAY BLUE	LEVEL 4-5
PLANK - CEDARWALL	DEEP OCEAN	LEVEL 1-3 BALCONY/PATIO
PLANK - CEDARWALL	BOOTHBAY BLUE	LEVEL 4-5 BALCONY/PATIO
SHAKE - STRAIGHT EDGE	GRAY SLATE	BUMP OUT BUILDING ENDS
SHAKE - STRAIGHT EDGE	TRADITIONAL RED	BUMP OUT
COLORFUL STONE	ELEGANT/TELE COUNTRY	FOOT CHAIRS/POSTS & BUILDING ENDS
TIMBER BEAM	LEICESTER GREY	
17" CEMENT BOARD TRIM	STAINED	

RE ISSUED FOR REZONING

A3.2

J



PROJECT STATUS:
 RE-ISSUED FOR REZONING

No.	Description	Revision Date
A	CITY PRE-APP	03/24/2020
B	RE-ISSUED FOR REZONING	07/28/2020
C	RE-ISSUED FOR REZONING	08/24/2020
D	RE-ISSUED FOR REZONING	08/24/2020
E	RE-ISSUED FOR REZONING	08/24/2020
F	RE-ISSUED FOR REZONING	07/28/2021
G	RE-ISSUED FOR REZONING	07/28/2021
H	RE-ISSUED FOR REZONING	07/28/2021
I	RE-ISSUED FOR REZONING	07/28/2021
J	RE-ISSUED FOR REZONING	07/28/2021


SEAL: ABLE ARCHITECTURE
 REGISTERED ARCHITECT
 1100 WEST 10TH AVENUE, SUITE 100
 VANCOUVER, BC V6H 1T5
 JUL 18 2021

THOSE CONTRACTORS SHALL VERIFY ALL DIMENSIONS OF WORKMANSHIP TO THE DRAWINGS AND SPECIFICATIONS WITHOUT DELAY FOR CLARIFICATION. CONTRACTORS SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS. CONTRACTORS SHALL MAINTAIN THE COPYRIGHT AND PROPRIETARY RIGHTS OF THE ARCHITECT AND SHALL NOT REPRODUCE OR TRANSMIT THE DRAWINGS OR ANY PART THEREOF TO ANY OTHER PARTY WITHOUT THE WRITTEN PERMISSION OF THE ARCHITECT. CONTRACTORS SHALL MAINTAIN THE ORIGINAL DRAWINGS AND ALL REVISIONS AT ALL TIMES AND MAKE THEM AVAILABLE FOR INSPECTION AT ALL TIMES. CONTRACTORS SHALL MAKE EVERY EFFORT TO MAINTAIN GOOD COMMUNICATION WITH THE ARCHITECT AND SHALL PROVIDE PROGRESSIVE REPORTS. CONTRACTORS SHALL MAKE EVERY EFFORT TO MAINTAIN GOOD COMMUNICATION WITH THE ARCHITECT AND SHALL PROVIDE PROGRESSIVE REPORTS. CONTRACTORS SHALL MAKE EVERY EFFORT TO MAINTAIN GOOD COMMUNICATION WITH THE ARCHITECT AND SHALL PROVIDE PROGRESSIVE REPORTS.

PROJECT NAME: GLENHART VIEWS
PROJECT NUMBER:
ADDRESS: 801 RYAN ROAD
 COURTNEY, BC
DRAWING TITLE:
 ELEVATIONS 1 OF 2 - BUILDING B
DRAWN BY: PD
CHECKED BY: RE
DATE: 06/22/2020
SCALE: AS INDICATED
DRAWING #: A3.3
REV #: J



1 FRONT ELEVATION
 SCALE: 1:100




2 BACK ELEVATION
 SCALE: 1:100

EXTERIOR ROOFING PRODUCT		
DESCRIPTION	COLOR	NOTES
ROOFING SHIMS (R-30) YEAR 1 AMANTE	BLACK	
A1122 SLANT VENT	BLACK	

NOTES
 1) ALL RESIDENTIAL UNITS TO HAVE INDIVIDUAL AC UNIT
 2) ALL RESIDENTIAL UNITS TO HAVE WINDOWS WITH RATING OF STC 30

EXTERIOR METAL PRODUCT		
DESCRIPTION	COLOR	LOCATION
ALUMINUM DOWNSPOUTS	BLACK	
ALUMINUM GUTTER	BLACK	REFER TO DETAIL 044.2
ALUMINUM BALUNS	BLACK	REFER TO DETAIL 044.3
PROFILES FOR FL COIL	WHITE	PANOS BOARD
4 PANEL GLASS DOOR KIT	LUSH	REFER TO DETAIL 044.3
WALL FLASHING	BLACK	
SHINGLE STEP FLASHING	BLACK	
ROOF EDGE FLASHING	BLACK	REFER TO DETAIL 044.2
DRIP CAP FLASHING	WHITE	WINDOWS
RECESSED FLASHING	WHITE	FLANK WINDOW TRIM
FLANK WINDOW TRIM	BLACK	
BILTER COIL FLASHING	BLACK	
FOUNDATION TRANSITION F.		

EXTERIOR CLADDING PRODUCT		
DESCRIPTION	COLOR	LOCATION
4" CEMENT BOARD TRIM	ARTIC WHITE	WINDY BALCONY WALLS
12" CEMENT BOARD TRIM	ARTIC WHITE	BELLY BAND
12" CEMENT BOARD TRIM	ARTIC WHITE	VERT PARTITION WALL
PLANK - CEDARWALL	DEEP OCEAN	LEVEL 1 - 3
PLANK - CEDARWALL	ROCKWAY BLUE	LEVEL 4 - 5
PLANK - CEDARWALL	DEEP OCEAN	LEVEL 1 - 3 BALCONY/PAC
PLANK - CEDARWALL	BOONBAY BLUE	LEVEL 4 - 5 BALCONY/PAC
SHAKE - 5" TIGHT EDGE	GRAY SLATE	BUMP OUT BUILDING END
SHAKE - 5" TIGHT EDGE	TRADITIONAL RED	BUMP OUT BUILDING END
CULTURED STONE	ENCAUSTIC COUNTRY	FRONT CANCHIES PORTALS BUILDING END
LEGGESTONE	LEGGESTONE	
TIMBER COLUMN		
TIMBER BEAM		
12" CEMENT BOARD TRIM	STAINED	




3 3/4" Up - Inside Deck Corner
 Scale:



4 3/4" Up - Inside Corner Bump-out
 Scale:

SEYMOUR PACIFIC
 DEVELOPMENTS LTD.
 100 St Arns Street, Campbell River, B.C.
 (779) 206-8046 (F) 250-236-8046
 www.seymourpacific.ca

SITE MAP




PROJECT STATUS:
 REISSUED FOR REZONING

Revision Schedule


No.	City and Province	Revision	Date
A	BC	ISSUED FOR PERMIT	09/09/2020
B	BC	REISSUED FOR PERMIT	09/09/2020
C	BC	REISSUED FOR PERMIT	09/09/2020
D	BC	REISSUED FOR PERMIT	09/09/2020
E	BC	REISSUED FOR PERMIT	09/09/2020

SEAL: AMELIA B. PETERSON
 ARCHITECT
 100 St Arns Street, Campbell River, BC V9W 1A4

THIS DOCUMENT IS THE PROPERTY OF SEYMOUR PACIFIC DEVELOPMENTS LTD. AND IS TO BE USED ONLY FOR THE PROJECT AND LOCATION SPECIFICALLY IDENTIFIED IN THE DRAWINGS. ANY REUSE OR REPRODUCTION OF THIS DOCUMENT WITHOUT THE WRITTEN PERMISSION OF SEYMOUR PACIFIC DEVELOPMENTS LTD. IS STRICTLY PROHIBITED. THE USER OF THIS DOCUMENT AGREES TO HOLD SEYMOUR PACIFIC DEVELOPMENTS LTD. HARMLESS FROM AND AGAINST ALL CLAIMS, DAMAGES, LOSSES AND EXPENSES, INCLUDING REASONABLE ATTORNEY'S FEES, THAT MAY BE ASSERTED AGAINST SEYMOUR PACIFIC DEVELOPMENTS LTD. BY ANY THIRD PARTY AS A RESULT OF THE USER'S USE OF THIS DOCUMENT. THE USER OF THIS DOCUMENT AGREES TO HOLD SEYMOUR PACIFIC DEVELOPMENTS LTD. HARMLESS FROM AND AGAINST ALL CLAIMS, DAMAGES, LOSSES AND EXPENSES, INCLUDING REASONABLE ATTORNEY'S FEES, THAT MAY BE ASSERTED AGAINST SEYMOUR PACIFIC DEVELOPMENTS LTD. BY ANY THIRD PARTY AS A RESULT OF THE USER'S USE OF THIS DOCUMENT.



1 FRONT ELEVATION
 Scale: 1:150



2 BACK (EAST) ELEVATION
 Scale: 1:150

EXTERIOR ROOFING PRODUCT

DESCRIPTION	COLOR
ROOFING SHIMBLES 30 YEAR LAMINATE	BLACK
ATTIC FINISH	WHITE

NOTES


1. ALL RESIDENTIAL UNITS TO HAVE INDIVIDUAL AC UNIT
 2. ALL RESIDENTIAL UNITS TO HAVE WINDOWS WITH RATING OF STC 30

EXTERIOR METAL PRODUCT

DESCRIPTION	COLOR	LOCATION
ALUMINUM DOWNPOUTS	BLACK	-
ALUMINUM FINISH	BLACK	REFER TO DETAIL BM42
ALUMINUM FILING	BLACK	REFER TO DETAIL BM43
PREFINISHED FLAT COIL	WHITE	FASCIA BOARD
PANEL CL. CL. COIL SUPPORT	UNFIN.	REFER TO DETAIL BM42
WALL FLASHING	BLACK	-
SHINGLE STEP FLASHING	BLACK	-
ROOF EDGE FLASHING	BLACK	REFER TO DETAIL BM42
DWP CAP FLASHING	WHITE	VARIOUS
REVERSE DRIP FLASHING	WHITE	PLANK WINDOW TRIM
PARTEY VENT	BLACK	-
GUTTER COIL FLASHING	-	-
FOUNDATION TRANSITION F.	-	-

EXTERIOR CLADDING PRODUCT

DESCRIPTION	COLOR	LOCATION
4" CEDAR BOARD TRIM	ARTIC WHITE	WINDOW DOCK TRIM
1/2" CEDAR BOARD TRIM	ARTIC WHITE	BALCONY WALL
1/2" CEDAR BOARD TRIM	ARTIC WHITE	BELLY BAND
PLANK - CEDARWELL	ARTIC WHITE	VERT. PARTITION WALL
PLANK - CEDARWELL	ARTIC WHITE	LEVEL 1-3
PLANK - CEDARWELL	BOOTHBY BLUE	LEVEL 4-6
PLANK - CEDARWELL	DEEP OCEAN	LEVEL 1-3 BALCONY/FASCIA
PLANK - CEDARWELL	BOOTHBY BLUE	LEVEL 4-6 BALCONY/FASCIA
SHAKE - STRAIGHT EDGE	GRAY SLATE	BUMP OUT BUILDING EDGES
SHAKE - STRAIGHT EDGE	TRADITIONAL RED	BUMP OUT
GL-TILED STONE	ESCALPUS COUNTRY	FRONT CANOPES/ENTR & BALCONY EDGES
TRIMER COLUMN	TRIMERSTONE	-
TRIMER BEAM	STAINED	-
1/2" CEDAR BOARD TRIM	STAINED	-



3 3/8" - Inside Dusk Corner
 Scale:




4 3/8" - Inside Dusk Corner
 Scale:

RE ISSUED FOR REZONING

A3.5

J

Attachment B



Subject Property Map

**Part 55 – Comprehensive Development Thirty-Four Zone (CD-34)
(1679 McPhee Ave)**

8.59.1 Intent

The CD-34 Zone is intended to accommodate an affordable housing multi residential development on the property legally described as Lot 5, Section 41, Comox District, Plan 13075, Except Part in Plan VIP68431. This property shall be developed substantially in accordance with Schedule A which forms part of this zone.

8.59.2 Permitted Uses

The following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (1) *Multi Residential*

8.59.3 Lot Coverage

A lot shall not be covered by buildings to a greater extent than 55% of the total *lot area*

8.59.4 Floor Area Ratio

The maximum floor area ratio shall not exceed 2.1

8.59.5 Minimum Lot Size

A lot shall have an area of not less than 1200 m²

8.59.6 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (1) *Front Yard*: 4.0 m; canopy may project 2.0 m into setback
- (2) *Rear Yard*: 2.0 m
- (3) *Side Yard (NW)*: 5.5 m
- (4) *Side Yard (SE)*: 3.0 m ground floor; canopy may project 1.3 m into setback
5.0 m all other floors; roof may project 1.0 m into setback

8.59.7 Height of Building

Maximum building height shall be 17.5 m.

8.59.8 Useable Open Space

Useable open space must be provided and include at minimum:

- (1) Internal pathways with furnished rest areas
- (2) 40 m² indoor amenity area
- (3) Patios for ground floor residents

8.59.9 Off-Street Parking and Loading

Off-street parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw except:

- (1) Parking shall be provided at a rate of 0.25 parking spaces per dwelling unit inclusive of visitor parking
- (2) Minimum parking stall dimensions are 2.7 m in width for standard stall

Schedule A

Note: Please refer to full size drawings in file 6480-20-2101 / 3360-20-2101





3 - CONCEPT DEVELOPMENT

PROJECT INFORMATION

City of Courtenay
 1787 MacPhee Ave
 Legal Description
 Lot 5, Section 11, Crown District (Plan 13105)
 VLP 66431

UNIT MIXTURE	UNIT TYPE	Gross floor area	# OF UNITS
1 Bedroom unit	1013 sqm	222 sqm	23
2 Bedroom unit	1380 sqm	222 sqm	8
TOTAL RESIDENTIAL UNITS			31

This subject land is a 1.1 acre parcel bounded by 17' street to the north, MacPhee Ave to the east, property 11, Lot 5, Section 11, Crown District, Courtenay, British Columbia, to the south, and the Courtenay River to the west. The subject land is zoned R-1 (Residential Single-Family). The proposed development is a 31-unit residential building. The proposed development is a 31-unit residential building. The proposed development is a 31-unit residential building.



ITEM	DESCRIPTION	QUANTITY	UNIT
FRONT LAND SETBACK	1.1 METERS	3.1	METERS
REAR LAND SETBACK	1.1 METERS	3.1	METERS
SIDE LAND SETBACK	1.1 METERS	3.1	METERS
MINIMUM LOT WIDTH	11 METERS	11	METERS
MINIMUM LOT AREA	121 SQM	121	SQM
MINIMUM LOT COVERAGE	10%	12.1	SQM
MINIMUM LOT FRONT SETBACK	1.1 METERS	3.1	METERS
MINIMUM LOT SIDE SETBACK	1.1 METERS	3.1	METERS
MINIMUM LOT REAR SETBACK	1.1 METERS	3.1	METERS
MINIMUM LOT FRONT YARD SETBACK	1.1 METERS	3.1	METERS
MINIMUM LOT SIDE YARD SETBACK	1.1 METERS	3.1	METERS
MINIMUM LOT REAR YARD SETBACK	1.1 METERS	3.1	METERS

PERMITTED FUNCTIONAL PROGRAM

FUNCTIONAL AREA	DESCRIPTION	AREA (SQM)	AREA (SQ FT)
RESIDENTIAL UNITS	31 UNITS	222	2385
PARKING STALLS	20 STALLS	200	2150
LANDSCAPE + SCREENING	LANDSCAPE + SCREENING	200	2150
TOTAL		622	6685

AO.01

Wachlaj Architecture
 Housing Project
 1879 MacPhee Ave
 Courtenay, BC



PROJECT DATA & SITE PLAN



1 MAIN FLOOR PLAN
SCALE: 1/100



Wachiy Affordable Housing Project
1679 MacPhee Ave. Courtenay, BC



1	2024.08.15	Revised Per Approval #1
2	2024.08.15	Revised Per Approval #2
3	2024.08.15	Revised Per Approval #3
4	2024.08.15	Revised Per Approval #4

MAIN FLOOR PLAN

A1.01

MATERIAL BOARD



Material Legend


- ① Contrasting wood batten
- ② 4" board and batten vertical-grain wood panel
- ③ Charcoal Vinyl window
- ④ semi-transparent Black Smooth Finish Colour Charcoal
- ⑤ Walnut Timberframe Elements
- ⑥ 4" metal panel, wood print



4 NORTH ELEVATION
Scale: 1/125




3 SOUTH ELEVATION
Scale: 1/125




1 EAST ELEVATION
Scale: 1/125




2 WEST ELEVATION
Scale: 1/125



4 SETBACKS
Scale: 1/200



3 SECTION PARALLEL TO MCPHIE
Scale: 1/100



1 SECTION PARALLEL TO 17TH
Scale: 1/100



WACHIA Y
Friendship Centre

Wachia y
Affordable
Housing Project

1679 McPhie Ave.
Countryside, BC



Issued for 2023/05/1

1 2023/05/1 Issued for Issuing #1
4 2023/05/1 Issued for Issuing #2
1 2023/05/1 Issued for Issuing #3

ELEVATIONS

A2.01



WACHIA Y
Friendship Centre

Wachia y
Affordable
Housing Project

1679 McPhie Ave.
Countryside, BC



Issued for 2023/05/1

1 2023/05/1 Issued for Issuing #1
4 2023/05/1 Issued for Issuing #2
1 2023/05/1 Issued for Issuing #3

SETBACK DIAGRAM

SK1.2

242

3051

**Part 56 - Comprehensive Development Thirty-Five Zone (CD-35)
(1790 15th Street.)**

8.60.1 Intent

The CD-35 Zone is intended to accommodate a strata development of two duplexes on the property legally described as Lot 8, District Lot 96, Comox District, Plan 6619. This property shall be developed substantially in accordance with Schedule A which forms part of this zone

8.60.2 Permitted Uses

The following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

- (3) *Duplex dwellings*
- (4) *Accessory buildings and structures*
- (5) *Home occupation*

8.60.5 Minimum Lot Size

A *lot* shall have an area of not less than 1250 m²

8.60.3 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 25.0 m

8.60.4 Floor Area Ratio

Providing all other applicable size, shape and siting conditions are met, the maximum *floor area ratio* shall not exceed 0.40.

8.60.6 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

- (7) *Front Yard:* 7.5 m
- (8) *Rear Yard:* 7.5 m
- (9) *Side Yard:* The *side yard setbacks* shall total 4.5 m with a minimum *side yard setback* on one side of 1.5 m.

8.60.7 Height of Building

Maximum *building height* shall be 10 m.

8.60.8 Useable Open Space

Useable open space must be provided on a *lot* in the amount of 30.0 m² for each one-bedroom *dwelling unit* and 50.0m² for each *dwelling unit* with two or more bedrooms.

8.60.9 Accessory Buildings and Accessory Structures

- (1) Shall not exceed 4.5m in *height*
- (2) Shall have a total building area not exceeding 50.0m² or 10% of the *rear yard*, whichever is greater, except where the structure is used to cover parking, in which case, the *floor area* shall not exceed 20% of the *rear yard* and shall not extend for more than 2/3 of the length of any property line or 30.0m, whichever is less.
- (3) Shall be permitted in the side and *rear yard* provided they shall conform to all relevant siting regulations of this bylaw.
- (4) Shall not be permitted at the front of a principal residence.
- (5) Shall not be located within 1.5, from the side and rear *lot line*.

8.60.10 Off-Street Parking and Loading

Off-street parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw.


8.60.11 Landscaping and Screening

In addition to the Landscape Requirements identified in Part 14 of this bylaw, the following landscape requirements shall be met:

- (1) A landscaped screen, *fence* or a combination thereof of not less than 3.0m in *height* and 1.5m in *width* shall be provided and maintained along the southern property boundary.

Schedule A

Note: Please refer to full size drawings in file 6480-20-2201 / 3360-20-2111



NO.	DESCRIPTION	DATE	BY	CHECKED	SCALE	PROJECT	CLIENT	STATUS
1	ISSUED FOR PERMIT	2023/08/15	J. SMITH	M. JONES	1:2000	CHAMBERLAIN'S DEVELOPMENT	CHAMBERLAIN'S DEVELOPMENT	PERMIT
2	REVISED	2023/08/20	J. SMITH	M. JONES	1:2000	CHAMBERLAIN'S DEVELOPMENT	CHAMBERLAIN'S DEVELOPMENT	REVISED
3	REVISED	2023/09/05	J. SMITH	M. JONES	1:2000	CHAMBERLAIN'S DEVELOPMENT	CHAMBERLAIN'S DEVELOPMENT	REVISED

McEILPATRICK
 CONSULTING ENGINEERS
 1799 15TH STREET
 CAMBERLAIN'S DEVELOPMENT

CHAMBERLAIN'S DEVELOPMENT
 PRELIMINARY SITE PLAN
 1799 15TH STREET DEVELOPMENT
 2023/08/15

Project Renderings











FRONT ELEVATION



REAR ELEVATION

1790 15TH STREET




RIGHT ELEVATION



LEFT ELEVATION

1790 15TH STREET



THE CITY OF COURTENAY
ATTACHMENT "B"
 Part of Bylaw No. 3051, 2022
 Amendment to the
 Zoning Bylaw No. 2500, 2007

**Part 57 - Comprehensive Development Thirty-Six Zone (CD-36)
(1077 Piercy Ave.)**

8.60.1 Intent

The CD-36 Zone is intended to accommodate a multi residential development on the property legally described as Lot 2, District Lot 104, Comox District, Plan 12602. This property shall be developed substantially in accordance with Schedule A and Schedule B which form part of this zone, any contrary requirements of Zoning Bylaw No. 2500 notwithstanding.

8.60.2 Permitted Uses

The following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

(6) *Rental Multi Residential, Accessory buildings and structures*

8.60.3 Minimum Lot Size

A *lot* shall have an area of not less than 2,350 m²

8.60.4 Minimum Lot Frontage

A *lot* shall have a frontage of not less than 30.0 m²

8.60.5 Floor Area Ratio

The maximum *floor area ratio* shall not exceed 0.75

8.60.6 Setbacks

Except where otherwise specified in this bylaw the following minimum *building setbacks* shall apply:

(10) *Front Yard:* 7.5 m

(11) *Rear Yard:* 23.0 m

(12) *Side Yard* : 2.4 m

8.60.7 Height of Building

Maximum *building height* shall be 9.0 m.

8.60.8 Useable Open Space

Useable open space and screening must be provided and include at minimum an average of 10 m² of patios/balconies per unit within an average of 16.8 m² of outdoor space per unit between the unit and the nearest side property line.

8.60.9 Accessory Buildings and Accessory Structures

A detached front entry archway structure and a rear refuse enclosure shall be permitted in substantial conformance to Schedule A

8.60.10 Off-Street Parking and Loading

Off-street parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw except:

- (8) Parking shall be provided at a rate of 0.83 *parking spaces per dwelling unit* inclusive of visitor parking
- (9) Maximum proportion of small car parking is 35%
- (10) Minimum number of stalls for people with disabilities is one (1)

8.60.11 Bicycle Parking Requirements

The minimum number of off-street bicycle parking spaces shall be 1.5 per unit, sited and specified in substantial conformance to Schedule A.

8.60.12 Landscaping and Screening



Must be in substantial conformance to Schedule B, including fencing and tree clusters along side lot lines.

Schedule A



Note: Please refer to full size drawings in file 6480-20-2104 / 3360-20-2113



GENERAL INFORMATION	
CIVIC ADDRESS	1071 PERCY AVENUE
ZONING DISTRICT	CD-1 (CD)
APPLICABLE BUILDING CODE	2021 IBC
APPLICABLE PLUMBING CODE	2021 UPC
APPLICABLE MECHANICAL CODE	2021 IMC
APPLICABLE ELECTRICAL CODE	2021 NEC
APPLICABLE ENERGY STANDARDS	2021 IECC
APPLICABLE LAND USE CODE	2021 LDC
APPLICABLE FIRE CODE	2021 FC
APPLICABLE ENVIRONMENTAL CODE	2021 EDC
APPLICABLE TRANSPORTATION CODE	2021 TDC
APPLICABLE ASBESTOS CODE	2021 ABC
APPLICABLE LEAD CODE	2021 LCC
APPLICABLE RADON CODE	2021 RDC
APPLICABLE SOIL REMEDIATION CODE	2021 SRC
APPLICABLE PEST CODE	2021 PC
APPLICABLE HAZARDOUS WASTE CODE	2021 HC
APPLICABLE AIR QUALITY CODE	2021 AQC
APPLICABLE CLIMATE CODE	2021 CC
APPLICABLE WATER CODE	2021 WC
APPLICABLE WIND CODE	2021 WC
APPLICABLE SOUND CODE	2021 SC
APPLICABLE VIBRATION CODE	2021 VC
APPLICABLE SEISMIC CODE	2021 SC
APPLICABLE GEOTECHNICAL CODE	2021 GTC
APPLICABLE MARINE CODE	2021 MC
APPLICABLE AVIATION CODE	2021 AC
APPLICABLE SPACE PROGRAMMING CODE	2021 SPC
APPLICABLE USER EXPERIENCE CODE	2021 UXC
APPLICABLE WELL-BEING CODE	2021 WB
APPLICABLE COMMUNITY DESIGN CODE	2021 CDC
APPLICABLE CULTURAL RESOURCES CODE	2021 CRC
APPLICABLE HISTORIC PRESERVATION CODE	2021 HPC
APPLICABLE LANDSCAPE ARCHITECTURE CODE	2021 LAC
APPLICABLE PLAYSPACE CODE	2021 PC
APPLICABLE RECREATION CODE	2021 RC
APPLICABLE SENIORS CODE	2021 SC
APPLICABLE WOMEN'S EQUITY CODE	2021 WC
APPLICABLE YOUTH CODE	2021 YC



<p>HEARTH ARCHITECTURAL</p> <p>4055 University Ave. Suite 100 Vancouver, BC V6N 1S7 Telephone: 604-681-4277 Fax: 604-681-4277</p> <p>WHEARTHWALKS</p> <p>11101 Kingsway, Suite 100 Vancouver, BC V2K 2K1 Telephone: 604-278-4800 Fax: 604-278-4801</p>	<p>PROJECT</p> <p>CLIENT</p> <p>COMPLIANT BC</p>	<p>DATE</p> <p>PROJECT NO.</p> <p>PROJECT NAME</p>	<p>SITE PLAN</p> <p>QUARTERS</p> <p>PROJECT STATISTICS</p> <p>AI00</p>
--	---	---	--



PIERCY AVENUE

HEARTH
architectural

450 Southwest Marine Drive, Suite 1000
Vancouver BC V6X 3C3 P: 604-266-4677

www.HEARTHto.co

DESIGN RESPONSIBILITY STATEMENT

I, the Designer, accept responsibility for the design of the building and the work of the Designer and the Architectural Firm. I have prepared the design and the Architectural Firm has prepared the construction documents. I have prepared the design and the Architectural Firm has prepared the construction documents. I have prepared the design and the Architectural Firm has prepared the construction documents.

Revisions

No.	Date	By
1	JULY 18 2020	ISSUED FOR REVIEW V.P.T.
2	JULY 28 2020	ISSUED FOR REVIEW V.P.T.
3	AUG 11 2020	ISSUED FOR REVIEW V.P.T.
4	AUG 11 2020	ISSUED FOR REVIEW V.P.T.
5	AUG 11 2020	ISSUED FOR REVIEW V.P.T.
6	AUG 11 2020	ISSUED FOR REVIEW V.P.T.

Project

APARTMENT BUILDING
1075 PIERCY ROAD
COURTNEY BC

Drawing Title

PROJECT FLOOR PLANS

Date MAR 2020 **Project No.** 210

Scale AS SHOWN **Drawing No.**

Drawn By H.A. **A200**

Checked By V.P.T.

HEARTH
architectural

450 Southwest Marine Drive, Suite 1000
Vancouver BC V6X 3C3 P: 604-266-4677

www.HEARTHto.co

DESIGN RESPONSIBILITY STATEMENT

I, the Designer, accept responsibility for the design of the building and the work of the Designer and the Architectural Firm. I have prepared the design and the Architectural Firm has prepared the construction documents. I have prepared the design and the Architectural Firm has prepared the construction documents. I have prepared the design and the Architectural Firm has prepared the construction documents.

Revisions

No.	Date	By
1	JULY 18 2020	ISSUED FOR REVIEW V.P.T.
2	JULY 28 2020	ISSUED FOR REVIEW V.P.T.
3	AUG 11 2020	ISSUED FOR REVIEW V.P.T.
4	AUG 11 2020	ISSUED FOR REVIEW V.P.T.
5	AUG 11 2020	ISSUED FOR REVIEW V.P.T.
6	AUG 11 2020	ISSUED FOR REVIEW V.P.T.

Project

APARTMENT BUILDING
1075 PIERCY ROAD
COURTNEY BC

Drawing Title

PROJECT ELEVATIONS

Date MAR 2020 **Project No.** 210







Scale AS SHOWN **Drawing No.**

Drawn By H.A. **A300**

Checked By V.P.T.

Schedule B

Note: Please refer to full size drawings in file 6480-20-2104 / 3360-20-2113



Hotel Legend

- 100% concrete
- 100% brick
- 100% stone
- 100% wood
- 100% metal
- 100% glass
- 100% other

Legend

- 100% concrete
- 100% brick
- 100% stone
- 100% wood
- 100% metal
- 100% glass
- 100% other

Construction Notes

1. Match lines shown - refer to drawings 1, 2, 3, 4, 5, 6.
2. Match lines shown - refer to drawings 1, 2, 3, 4, 5, 6.
3. Match lines shown - refer to drawings 1, 2, 3, 4, 5, 6.
4. Match lines shown - refer to drawings 1, 2, 3, 4, 5, 6.
5. Match lines shown - refer to drawings 1, 2, 3, 4, 5, 6.
6. Match lines shown - refer to drawings 1, 2, 3, 4, 5, 6.

the TULA project

1077 Piercy Ave. Apartments

DATE	DESCRIPTION
2/20/20	4. Reveal for Land/Use
2/20/21	3. Reveal for City Review
2/20/21	2. Reveal for Client Review
2/20/18	1. Reveal for Review
2/20/18	0. Reveal for Review


1077 Piercy Ave. Condominiums

DATE	DESCRIPTION
2/20/18	1. Reveal for Review
2/20/18	0. Reveal for Review

General Notes

1. All dimensions are in feet and inches.
2. All dimensions are to the centerline of the wall.
3. All dimensions are to the centerline of the door.
4. All dimensions are to the centerline of the window.
5. All dimensions are to the centerline of the balcony.
6. All dimensions are to the centerline of the patio.
7. All dimensions are to the centerline of the driveway.
8. All dimensions are to the centerline of the sidewalk.
9. All dimensions are to the centerline of the curb.
10. All dimensions are to the centerline of the street.
11. All dimensions are to the centerline of the property line.
12. All dimensions are to the centerline of the building footprint.
13. All dimensions are to the centerline of the building envelope.
14. All dimensions are to the centerline of the building massing.
15. All dimensions are to the centerline of the building volume.
16. All dimensions are to the centerline of the building height.
17. All dimensions are to the centerline of the building depth.
18. All dimensions are to the centerline of the building width.
19. All dimensions are to the centerline of the building area.
20. All dimensions are to the centerline of the building perimeter.
21. All dimensions are to the centerline of the building boundary.
22. All dimensions are to the centerline of the building footprint.
23. All dimensions are to the centerline of the building envelope.
24. All dimensions are to the centerline of the building massing.
25. All dimensions are to the centerline of the building volume.
26. All dimensions are to the centerline of the building height.
27. All dimensions are to the centerline of the building depth.
28. All dimensions are to the centerline of the building width.
29. All dimensions are to the centerline of the building area.
30. All dimensions are to the centerline of the building perimeter.

L1.01



THE CITY OF COURTENAY
ATTACHMENT "B"
 Part of Bylaw No. 3054, 2022
 Amendment to the
 Zoning Bylaw No. 2500, 2007

8.64.1 Intent

The CD-38 Zone is intended to accommodate a supportive rental cluster housing development on the property legally described as Lot 14, Section 41, Comox District, Plan 9456. The property shall be developed substantially in accordance with Schedule A which form part of this zone, any contrary requirements of Zoning Bylaw No. 2500 notwithstanding.

8.64.2 Permitted Uses

The following uses are permitted and all other uses are prohibited except as otherwise noted in this bylaw:

8. Rental residential in *single, duplex and apartment dwelling units*
9. One amenity building for shared resident use that may have a second-floor dwelling unit for a support person
10. One *dwelling unit* for a support person located above a shared indoor resident amenity space
11. *Accessory buildings* and structures

8.64.3 Lot Coverage

A *lot* shall not be covered by buildings to a greater extent than 40% of the total area of the lot.

8.64.4 Floor Area Ratio

The maximum *floor area ratio* shall not exceed 0.55.

8.64.5 Minimum Lot Size

A lot shall have an area of not less than 1,600 m².

8.64.6 Setbacks

Except where otherwise specified in this bylaw the following minimum building setbacks shall apply for the principle buildings:

- (13) Front Yard: 7.5 m
- (14) Rear Yard: 7.5 m
- (15) Side Yard (interpreted as the yard adjacent to the northwest property line): 3.0 m except 1.5 m for the seating wall of the amenity building
- (16) Side Yard (interpreted as the yard adjacent to the southeast property line): 3.0 m

For clarity, heat pumps are permitted to project into setbacks.

8.64.7 Height of Buildings

Maximum *building height* shall be 8.5 m.

8.64.9 Usable Open Space

A minimum of 450 m² of useable open space must be provided plus a minimum of 50 m² of indoor amenity space.

8.64.10 Accessory Structures

Shall not be permitted except for bike and scooter storage structures and entry gazebo.

- (1) The front and southeast side yard setbacks for accessory buildings shall be 2.5 m
- (2) The rear yard setback for accessory buildings shall be 4.0 m
- (3) The northwest side yard setback for accessory buildings shall be 1.0 m
- (4) The maximum height for accessory buildings shall be 3.5 m

8.64.11 Off-Street Parking and Loading


Off-street parking shall be provided and maintained in accordance with the requirements of Division 7 of this bylaw except:

- (8) A total of six (6) vehicle parking spaces shall be provided, including a minimum of three (3) visitor spaces;
- (9) Bicycle parking facilities shall be provided at a minimum rate of 0.875 Class II covered, secure stall per unit plus 0.25 Class I stalls per unit; and
- (10) Bicycle parking specification Sections 7.3.2 2,3,7,8,12 and 14g and h do not apply

8.64.12 Fencing

- (1) The maximum height of side and rear fencing is 2.5 m.
- (2) The minimum height of landscaping or fencing on all property lines adjoining all other adjoining properties is 2.0 m.


SCHEDULE A



2 AMENITY AREAS

Amenity area calculations:
 Pkts, plaza and lawn: 112m²
 Accessible garden areas: 151m²
 Total: 463m²

1 SITE PLAN



Tree retention legend:
 1. Existing cedar
 2. Existing dogwood
 3. Existing cherry
 4. Existing maple
 5. Existing Douglas fir

john gover design
 1000 West Broadway, Vancouver, BC
 Tel: 604.681.1111
 www.johngoverdesign.com

SCALE: AS NOTED
 PROJECT: 2023
 DRAWN: JGO
 CHECKED: JGO
 ISSUED: June 21, 2023
 REFERENCE: BC2023-019


DRAWING NAME:
A-A-4



4573 BURNING BUSH DRIVE, COURTESY BC
 VANIC 580
 TEL: 778.764.8322
 www.larchecomoxvalley.com

L'Arche Comox Valley "The Anchorage"
 1560 Grieve Avenue, Courteney BC

NOTE: ALL DESIGN MATERIAL, INCLUDING THIS DRAWING, IS THE PROPERTY OF L'ARCHE COMOX VALLEY AND IS NOT TO BE REPRODUCED IN ANY MANNER WITHOUT THE WRITTEN PERMISSION OF L'ARCHE COMOX VALLEY.



THE CITY OF COURTENAY

ATTACHMENT "B"

Part of Bylaw No. 3094
 Amendment to the
 Zoning Bylaw No. 2500, 2007

Justification

In accordance with the Local Government Act (Sections 492 & 493), the Zoning Bylaw designates areas allowing temporary uses, and specifies general conditions regarding the issuance of Temporary Use Permit in the areas.

Objective

A Temporary Use Permit allows for flexible use of land, on a temporary basis, not otherwise permitted in the Zoning Bylaw. Council may, by resolution, issue a Temporary Use Permit and specify the conditions under which the temporary use be carried on such as addressing potential negative effects on existing residences, businesses, or other surrounding properties in terms of noise, lighting, parking, traffic, or other adverse impacts.

All Temporary Use Permits must conform to policy direction in the OCP, including fit within the character of the neighbourhood and surrounding uses. Upon expiry of a Temporary Use Permit, the permitted uses revert to those outlined in the Zoning Bylaw.

Policies

1. All zones in the City are designated a Temporary Use Permit area.
2. The applicant must include the following relevant information at the time of the permit application:
 - a) Duration of the proposed temporary use including assurance that the use is temporary or seasonal in nature;
 - b) Map indicating the existing and surrounding land use;
 - c) Plan of the buildings or structures that may be used;
 - d) Potential conflict with residential land uses;
 - e) Potential impacts on Environmentally Sensitive Areas;
 - f) Provision of adequate servicing that meets City requirements; and
 - g) Site rehabilitation plan.
3. TUPs may be issued for a period up to three (3) years, but generally shall be a maximum of two (2) years, and may be renewed once, subject to Council approval.
4. Conditions under which a temporary use may be allowed are established in the permit and may include, but not be limited to: location, site design and layout, screening, landscaping, demolition, site restoration, and length of time the temporary use can occur.
5. Security deposits may be required and included in the permit condition to ensure all the conditions are met and the subject land is properly rehabilitated upon cessation of the use.

DIVISION 10 DEVELOPMENT PERMIT AREAS GUIDELINES

As included in Schedule A (after page 264)

DIVISION 11 ADOPTION

Part 1 Repeal of Previous Bylaws

Bylaw No. 1427, being the "City of Courtenay Zoning Bylaw No. 1427, 1986", and all amending bylaws thereto, are hereby repealed.

Part 2 Effective Date of Bylaw

This Bylaw shall come into force and effect upon final adoption hereof.

Starr Winchester
Mayor

John Ward
Manager of Corporate Administration